Bruhat Bangalore Mahanagara Palike
Executive Engineer Yelahanka Division

Name of Work:Modified Estimate For Improvements To Roads and Drains And Other Developmental Works At Akskshaya,Thirumalanagar,Muneshwara Layout,Sri Sai Layout, B Sector And Surrounding Areas in Ward No-03 And 04 Of Yelahanka Division Under Amruth Nagarothan Grants[PACKAGE NO-03]

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
1	Removing and Resetting of Footpath Slab and pointing in C.M (1:3) (Approved Rate)								
	For Desilt								
	2nd main road Attur Layout	2	344.80	0.90		620.64			
	3nd main road Attur Layout	2	424.30	0.90		763.74			
	4th main road Attur Layout	2	369.30	0.90		664.74			
	Attur Layout 5th main road	2	381.00	0.90		685.80			
	Attur Layout 6th main road	2	321.30	0.90		578.34			
	Attur Layout 7th main road	2	299.70	0.90		539.46			
	Attur Layout 8th main road	2	316.20	0.90		569.16			
	Attur Layout 1st cross road	2	222.90	0.90		401.22			
	Attur Layout 2nd cross road	2	225.90	0.90		406.62			
	Attur Layout 3rd cross road	2	247.90	0.90		446.22			
	Attur Layout 4th cross road	2	226.20	0.90		407.16			
	Akshaynagar								
	2nd cross road	2	153.50	0.90		276.30			
	3rd cross road	2	154.50	0.90		278.10			
	4th cross road	2	153.50	0.90		276.30			
	5th cross road	2	90.00	0.90		162.00			
	6th cross road	2	155.00	0.90		279.00			
	7th cross road	2	154.00	0.90		277.20			
						7632.00			
	Consider 90%					**7021.44**			
	Deduct 15% Missing/Damaged Slab					**1078.00**			
						5943.44			
	Akshay Nagara								
	1st Cross Rd LHS	1	67.00	0.90		60.30			
	1st Cross Rd RHS	1	67.00	0.90		60.30			
	Main Rd From Sandeep Unnikrishan rd RHS	1	338.00	0.90		304.20			
	Escorts Colony								
	6th C Cross Rd LHS	1	58.60	0.90		52.74			
	6Th B Cross Rd	1	54.40	0.90		48.96			
	6th A Main Rd LHS	1	154.00	0.90		138.60			
	6th A Main Rd RHS	1	154.20	0.90		138.78			
	2nd A main Rd	2	120.00	0.75		180.00			
	Escorts Colony	2	171.70	0.90		309.06			
	7th A Main Road LHS	1	207.70	0.90		186.93			
	7th A Main Road RHS	1	215.50	0.90		193.95			
	Santhosh Nagara								
	2nd Cross Rd LHS	2	159.00	0.75		238.50			
	4th Cross Rd LHS	1	99.00	0.90		89.10			
	4th Cross Rd RHS	1	123.00	0.75		92.25			
	Connecting Rd-2	1	24.00	0.90		21.60			
	Connecting Rd-1	2	24.00	0.90		43.20			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	6th Cross Rd LHS	1	243.40	0.90		219.06			
	6th Cross Rd RHS	1	255.70	0.90		230.13			
	Health Care Home Road LHS	1	127.80	0.90		115.02			
	Health Care Home Road RHS	1	78.80	0.90		70.92			
	Amruthagra Care Road	2	24.00	0.75		36.00			
	Sri Laasya Road[19]	2	21.15	0.75		31.73			
	Door No-13	2	24.80	0.75		37.20			
	Varaha Entreprises Rd	2	17.50	0.75		26.25			
	7th Cross Rd LHS	1	125.20	0.90		112.68			
	Muneshwara Layout								
	11th Cross Rd LHS	1	35.00	0.90		31.50			
	11th Cross Rd RHS	1	47.20	0.90		42.48			
	RHS Side Roads								
	10th Cross Rd LHS	1	163.50	0.90		147.15			
	10th Cross Rd RHS	1	157.20	0.90		141.48			
	9th Cross Rd LHS	1	161.40	0.90		145.26			
	9th Cross Rd RHS	1	162.70	0.90		146.43			
	4th Cross Rd LHS	1	56.20	0.90		50.58			
	Veerasagara								
	6th Cross Rd LHS	1	50.90	0.75		38.18			
	6th Cross Rd RHS	1	56.80	0.75		42.60			
	6th B Cross Rd LHS	1	70.00	0.75		52.50			
	6th B Cross Rd RHS	1	57.20	0.75		42.90			
	6th A Cross Rd RHS	1	65.20	0.75		48.90			
	6th A Cross Rd LHS	1	65.00	0.75		48.75			
						4016.16			
	Deduct 20% Missing/Damaged Slab					872.35			
						3143.81			
	SFS 407								
	3rd B Cross Rd	2	76.80	0.90		138.24			
	Santhosh Nagara								
	1st Cross Rd	2	39.20	0.90		70.56			
	1stA Cross Rd	2	73.90	0.75		110.85			
	Attur Layout								
	Opp To Post Office 1stA Cross Rd	2	90.95	0.75		136.43			
	Connecting Road	1	46.10	0.75		34.58			
						490.65			
	Deduct 40% Missing/Damaged Slab					196.26			
						294.39			
						9381.64	Sqm		
				Upto 125%		7946.83	Sqm	259.93	2065645.10
				Above 125%		1434.81	Sqm	259.93	372955.02
	Approved Amount	259.93							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
2	**Earth work excavation by manual means** for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such similar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 5.5 m3) (V-I.No 1.4,Page No-5 PWD SR 2021-22)								
	Rcc Drain								
	Ward No-03								
	From Sandeep Unnikrishan Main Road, Thirumala nagara main road	2	285.45	1.10	1.00	627.99			
	8th A Main road (LHS)	1	77.80	1.10	1.00	85.58			
	From Sandeep Unnikrishan Main Road, 3rd A Main road	2	82.85	0.95	0.85	133.80			
	3rd A Main road Continued (RHS)	1	17.90	0.95	0.85	14.45			
	From Veersagar Main Road, 5th Cross road (LHS) Muneshwara layout	1	44.50	0.95	0.85	35.93			
	Cross road 1	2	53.05	1.10	1.00	116.71			
	Sri Sai Layout								
	From Veersagar Main Road, Sai Layout Main Road (LHS)	2	100.70	1.10	1.00	221.54			
	Sai Layout Cross Road(RHS)	1	13.50	1.10	1.00	14.85			
	Sai Layout 1st A Main Road (LHS)	2	147.50	1.10	1.00	324.50			
	Sai Layout 1st A Main Road	1	22.50	1.10	1.00	24.75			
	From Veersagar Main Road, Hanumayya Layout(Adjacent to Trivik Apt)								
	1st Main Road (LHS)	1	147.90	0.80	0.85	100.57			
	Cross Road 1 (LHS)	1	8.80	0.85	0.85	8.84			
	2nd Main Road (LHS) (From Dhanush Nialaya)	1	38.30	0.85	0.85	27.67			
	From Veersagar Main Road, Cross Road 1	2	17.50	1.10	1.00	38.50			
	Sai Layout 2nd A Main Road	2	136.65	1.10	1.00	300.63			
	From Veersagar Main Road, 11th Cross Road (RHS)	1	49.00	1.10	1.00	53.90			
	6th Cross Road	2	59.95	1.10	1.00	131.89			
	Santhosh Nagara								
	1st Cross Rd LHS	1	149.60	1.10	1.10	181.02			
	7th Cross Rd RHS	1	117.30	1.05	1.10	135.48			
	Attur Village Rd RHS	1	111.30	1.00	1.00	111.30			
	Veerasagara								
	5th Cross Rd LHS	1	95.30	1.00	1.10	104.83			
	Muneshwara Layout								
	4th Cross Rd LHS	1	45.00	1.00	1.00	45.00			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	2nd Cross Rd LHS	1	44.80	1.00	1.00	44.80			
	1st Cross Rd LHS	1	34.10	1.00	1.00	34.10			
	4th Cross Rd RHS	1	172.00	1.00	1.00	172.00			
	6th Cross Rd								
	1st Cross Rd LHS	1	22.50	1.10	1.10	27.23			
	2nd Cross Rd	2	25.00	1.10	1.00	55.00			
	3rd Cross Rd	2	22.25	1.10	1.00	48.95			
	4th Cross Rd LHS	1	11.10	1.10	1.00	12.21			
	4th Cross Rd RHS	1	22.50	1.10	1.00	24.75			
	Ward No -04								
	From 9th B Cross Road, 6th B Main road - B - Sector (RHS)	1	12.70	1.40	1.00	17.78			
	From 9th B Cross Road 6th B Main road - B - Sector (LHS)	1	305.80	1.40	1.00	428.12			
	From 9th B Cross Road, 7th B Main Road (RHS)	1	245.60	1.40	1.00	343.84			
	From 8th B Cross Road, 7th B Main road - B - Sector (RHS)	1	226.20	1.40	1.00	316.68			
	7th B Main road - B - Sector (LHS)	1	52.70	1.10	1.00	57.97			
	From Sandeep Unnikrishan Main Road, 4th B Cross road - B - Sector	2	124.50	1.10	1.00	273.90			
	4th B Cross road Continued (RHS)	1	17.40	1.10	1.00	19.14			
	From 4th B Cross road - B - Sector, 8th B Main road (LHS)	1	58.00	1.10	1.00	63.80			
	From 10th B Cross road, 11th B Cross road (RHS)	1	17.00	1.10	1.00	18.70			
	From 10th B Cross road, 11th B Cross road (RHS)	1	16.40	1.10	1.00	18.04			
	For RCC Culverts								
	Ward No -03								
		8	5.78	1.50	1.00	69.36			
	3rd A Main road	1	3.70	1.40	1.00	5.18			
	Ward No -04								
	6th B Main road - B - Sector (LHS)	1	7.80	1.70	1.00	13.26			
		1	7.50	1.70	1.00	12.75			
		1	4.90	1.70	1.00	8.33			
	7th B Main Road (RHS)	1	6.00	1.40	1.00	8.40			
		1	7.50	1.70	1.00	12.75			
		1	3.50	1.70	1.00	5.95			
	7th B Main road - B - Sector (RHS)	1	8.00	1.70	1.00	13.60			
		1	9.00	1.70	1.00	15.30			
	4th B Cross road - B - Sector (RHS)	1	4.90	1.40	1.00	6.86			
	4th B Cross road Continued (RHS)	1	9.30	1.70	1.00	15.81			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	2nd B Main road (RHS)	1	7.60	1.40	1.00	10.64			
	For Pathway								
	Ward No-03								
	SFS 208								
	15th Block	1	58.30	3.15	0.25	45.91			
	S-HIG 32	1	41.80	5.40	0.25	56.43			
	Opp To Annapurnashweri Catering	1	73.70	4.15	0.25	76.46			
	S-LIG 42								
	Beside Neha Praksha Hospital	1	48.50	3.40	0.25	41.23			
	SFS 208								
	2nd Main Road RHS	1	161.50	1.33	0.25	53.70			
	3rd Main Road LHS	1	28.30	1.00	0.25	7.08			
	4th Cross Rd RHS From United Residency Association	1	116.60	0.62	0.25	18.07			
	4th Cross Rd LHS From Dental Clinic	1	78.20	0.80	0.25	15.64			
	BMS Hostel Opp Road LHS	1	71.20	0.59	0.25	10.50			
	BMS Hostel Opp Road RHS	1	102.80	0.59	0.25	15.16			
	Urdhu School Surrounding	1	100.00	3.05	0.25	76.25			
	Ward No-04								
	7th B Cross Rd	1	24.00	1.00	0.25	6.00			
	For Kerb Stone								
	Akshay Nagara								
	8th A Main Rd LHS	1	113.70	0.20	0.25	5.69			
	SFS 208								
	2nd Main Rd RHS	1	201.15	0.20	0.25	10.06			
	3rd Main Road LHS	1	30.00	0.20	0.25	1.50			
	SFS 407								
	1st A Main Road	1	182.50	0.20	0.25	9.13			
	1st Cross Rd	2	33.50	0.20	0.25	3.35			
	3rd B Cross Rd	2	74.40	0.20	0.25	7.44			
	Virupaksha Nilaya Rd	2	37.85	0.20	0.25	3.79			
	Shri Vinayaka Prathana Mandira	1	18.00	0.20	0.25	0.90			
	Akkaya Devi Temple Road RHS	2	184.00	0.20	0.25	18.40			
	11th Main rd	1	77.50	0.20	0.25	3.88			
	Urdhu School	1	23.90	0.20	0.25	1.20			
	Vaidhika Sabha Building Surrounding	1	272.70	0.20	0.25	13.64			
	Rcc Drain Desilt								
	2nd main road Attur Layout	2	344.80	0.45	0.45	139.64			
	3nd main road Attur Layout	2	424.30	0.45	0.45	171.84			
	4th main road Attur Layout	2	369.30	0.45	0.45	149.57			
	Attur Layout 5th main road	2	381.00	0.45	0.45	154.31			
	Attur Layout 6th main road	2	321.30	0.45	0.15	43.38			
	Attur Layout 7th main road	2	299.70	0.45	0.15	40.46			
	Attur Layout 8th main road	2	316.20	0.45	0.45	128.06			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Attur Layout 1st cross road	2	222.90	0.60	0.40	106.99			
	Attur Layout 2nd cross road	2	225.90	0.60	0.40	108.43			
	Attur Layout 3rd cross road	2	247.90	0.60	0.40	118.99			
	Attur Layout 4th cross road	2	226.20	0.60	0.40	108.58			
	Akshaynagar								
	2nd cross road	2	153.50	0.60	0.40	73.68			
	3rd cross road	2	154.50	0.60	0.40	74.16			
	4th cross road	2	153.50	0.60	0.40	73.68			
	5th cross road	2	90.00	0.60	0.45	48.60			
	6th cross road	2	155.00	0.60	0.60	111.60			
	7th cross road	2	154.00	0.60	0.60	110.88			
	1st Cross Rd LHS	1	67.00	0.60	0.70	28.14			
	1st Cross Rd RHS	1	67.00	0.60	0.65	26.13			
	Main Rd From Sandeep Unnikrishan rd RHS	1	338.00	0.60	0.63	127.76			
	Escorts Colony								
	6th C Cross Rd LHS	1	58.60	0.60	0.60	21.10			
	6Th B Cross Rd	1	54.40	0.60	0.60	19.58			
	6th A Main Rd LHS	1	154.00	0.60	0.65	60.06			
	6th A Main Rd RHS	1	154.20	0.60	0.55	50.89			
	2nd A main Rd	2	120.00	0.45	0.55	59.40			
	Escorts Colony	2	171.70	0.60	0.60	123.62			
	7th A Main Road LHS	1	207.70	0.60	0.60	74.77			
	7th A Main Road RHS	1	215.50	0.60	0.60	77.58			
	Santhosh Nagara								
	2nd Cross Rd LHS	2	159.00	0.45	0.63	90.15			
	4th Cross Rd LHS	1	99.00	0.60	0.64	38.02			
	4th Cross Rd RHS	1	123.00	0.45	0.62	34.32			
	Connecting Rd-2	1	24.00	0.60	0.60	8.64			
	Connecting Rd-1	2	24.00	0.60	0.60	17.28			
	6th Cross Rd LHS	1	243.40	0.60	0.55	79.59			
	6th Cross Rd RHS	1	255.70	0.60	0.60	92.05			
	Health Care Home Road LHS	1	127.80	0.60	0.65	49.84			
	Health Care Home Road RHS	1	78.80	0.60	0.55	26.00			
	Amruthagra Care Road	2	24.00	0.45	0.60	12.96			
	Sri Laasya Road[19]	2	21.15	0.45	0.60	11.42			
	Door No-13	2	24.80	0.45	0.60	13.39			
	Varaha Entreprises Rd	2	17.50	0.45	0.61	9.61			
	7th Cross Rd LHS	1	125.20	0.60	0.62	46.57			
	Muneshwara Layout								
	11th Cross Rd LHS	1	35.00	0.60	0.59	12.39			
	11th Cross Rd RHS	1	47.20	0.60	0.56	15.86			
	RHS Side Roads								
	10th Cross Rd LHS	1	163.50	0.60	0.59	57.88			
	10th Cross Rd RHS	1	157.20	0.60	0.60	56.59			
	9th Cross Rd LHS	1	161.40	0.60	0.61	59.07			
	9th Cross Rd RHS	1	162.70	0.60	0.58	56.62			
	4th Cross Rd LHS	1	136.40	0.60	0.55	45.01			
	Veerasagara								
	6th Cross Rd LHS	1	50.90	0.45	0.60	13.74			
	6th Cross Rd RHS	1	56.80	0.45	0.60	15.34			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	6th B Cross Rd LHS	1	70.00	0.45	0.55	17.33			
	6th B Cross Rd RHS	1	57.20	0.45	0.55	14.16			
	6th A Cross Rd RHS	1	65.20	0.45	0.60	17.60			
	6th A Cross Rd LHS	1	65.00	0.45	0.55	16.09			
	SFS 407								
	3rd B Cross Rd	2	76.80	0.60	0.55	50.69			
	Santhosh Nagara								
	1st Cross Rd	2	39.20	0.60	0.55	25.87			
	1stA Cross Rd	2	73.90	0.45	0.55	36.58			
	Attur Layout								
	Opp To Post Office 1stA Cross Rd	2	90.95	0.45	0.55	45.02			
	Connecting Road	1	46.10	0.45	0.55	11.41			
	Compound Wall								
		1	87.20	0.75	1.20	78.48			
						9123.77	**Cum**	**336.25**	**3067907.35**
	Approved Amount	**336.25**							
3	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) **Mix 1:3:6 (M10) Using 40 mm** nominal size graded crushed coarse aggregates (V-1, P No-15, I No-2.1.3 of PWD SR 2021-22)								
	Rcc Drain								
	Ward No-03								
	From Sandeep Unnikrishan Main Road, Thirumala nagara main road	2	285.45	1.10	0.15	94.20			
	8th A Main road (LHS)	1	77.80	1.10	0.15	12.84			
	From Sandeep Unnikrishan Main Road, 3rd A Main road	2	82.85	0.95	0.15	23.61			
	3rd A Main road Continued (RHS)	1	17.90	0.95	0.15	2.55			
	From Veersagar Main Road, 5th Cross road (LHS) Muneshwara layout	1	44.50	0.95	0.15	6.34			
	Cross road 1	2	53.05	1.10	0.15	17.51			
	Sri Sai Layout								
	From Veersagar Main Road, Sai Layout Main Road (LHS)	2	100.70	1.10	0.15	33.23			
	Sai Layout Cross Road(RHS)	1	13.50	1.10	0.15	2.23			
	Sai Layout 1st A Main Road (LHS)	2	147.50	1.10	0.15	48.68			
	Sai Layout 1st A Main Road	1	22.50	1.10	0.15	3.71			
	From Veersagar Main Road, Hanumayya Layout(Adjacent to Trivik Apt)								
	1st Main Road (LHS)	1	147.90	0.80	0.15	17.75			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Cross Road 1 (LHS)	1	8.80	0.85	0.15	1.56			
	2nd Main Road (LHS) (From Dhanush Nialaya)	1	38.30	0.85	0.15	4.88			
	From Veersagar Main Road, Cross Road 1	2	17.50	1.10	0.15	5.78			
	Sai Layout 2nd A Main Road	2	136.65	1.10	0.15	45.09			
	From Veersagar Main Road, 11th Cross Road (RHS)	1	49.00	1.10	0.15	8.09			
	6th Cross Road	2	59.95	1.10	0.15	19.78			
	Santhosh Nagara								
	1st Cross Rd LHS	1	149.60	1.10	0.15	24.68			
	7th Cross Rd RHS	1	117.30	1.05	0.15	18.47			
	Attur Village Rd RHS	1	111.30	1.00	0.15	16.70			
	Veerasagara								
	5th Cross Rd LHS	1	95.30	1.00	0.15	14.30			
	Muneshwara Layout								
	4th Cross Rd LHS	1	45.00	1.00	0.15	6.75			
	2nd Cross Rd LHS	1	44.80	1.00	0.15	6.72			
	1st Cross Rd LHS	1	34.10	1.00	0.15	5.12			
	4th Cross Rd RHS	1	172.00	1.00	0.15	25.80			
	6th Cross Rd								
	1st Cross Rd LHS	1	22.50	1.10	0.15	3.71			
	2nd Cross Rd	2	25.00	1.10	0.15	8.25			
	3rd Cross Rd	2	22.25	1.10	0.15	7.34			
	4th Cross Rd LHS	1	11.10	1.10	0.15	1.83			
	4th Cross Rd RHS	1	22.50	1.10	0.15	3.71			
	Ward No -04								
	From 9th B Cross Road, 6th B Main road - B - Sector (RHS)	1	12.70	1.40	0.15	2.67			
	From 9th B Cross Road 6th B Main road - B - Sector (LHS)	1	305.80	1.40	0.18	77.06			
	From 9th B Cross Road, 7th B Main Road (RHS)	1	245.60	1.40	0.15	51.58			
	From 8th B Cross Road, 7th B Main road - B - Sector (RHS)	1	226.20	1.40	0.15	47.50			
	7th B Main road - B - Sector (LHS)	1	52.70	1.10	0.15	8.70			
	From Sandeep Unnikrishan Main Road, 4th B Cross road - B - Sector	2	124.50	1.10	0.15	41.09			
	4th B Cross road Continued (RHS)	1	17.40	1.10	0.17	3.25			
	From 4th B Cross road - B - Sector, 8th B Main road (LHS)	1	58.00	1.10	0.18	11.48			
	From 10th B Cross road, 11th B Cross road (RHS)	1	17.00	1.10	0.15	2.81			
	From 10th B Cross road, 11th B Cross road (RHS)	1	16.40	1.10	0.15	2.71			
	For RCC Culverts								
	Ward No -03								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	3rd A Main road	1	3.70	1.40	0.15	0.78			
		8	5.78	1.50	0.15	10.40			
	Ward No -04								
	6th B Main road - B - Sector (LHS)	1	7.80	1.70	0.15	1.99			
		1	7.50	1.70	0.15	1.91			
		1	4.90	1.70	0.15	1.25			
	7th B Main Road (RHS)	1	6.00	1.40	0.15	1.26			
		1	7.50	1.70	0.15	1.91			
		1	3.50	1.70	0.15	0.89			
	7th B Main road - B - Sector (RHS)	1	8.00	1.70	0.14	1.90			
		1	9.00	1.70	0.15	2.30			
	4th B Cross road - B - Sector (RHS)	1	4.90	1.40	0.15	1.03			
	4th B Cross road Continued (RHS)	1	9.30	1.70	0.15	2.37			
	2nd B Main road (RHS)	1	7.60	1.40	0.15	1.60			
	For Pathway								
	Ward No-03								
	S-LIG - 10,11	1	39.80	6.20	0.15	37.01			
	S-LIG - 08,09	1	24.20	6.70	0.15	24.32			
	S-LIG - 07	1	6.80	4.00	0.15	4.08			
	S-LIG - 06	1	35.50	7.00	0.15	37.28			
	S-LIG - 05	1	4.20	4.20	0.15	2.65			
	S-LIG - 03	1	39.60	4.00	0.15	23.76			
	S-LIG - 01	1	34.60	6.26	0.15	32.49			
	Near Nandini Parlour(Indian Sweets Bakery)	1	31.30	3.50	0.15	16.43			
	Bheema Blocks HIG - B - 2	1	41.40	5.00	0.15	31.05			
	SFS 208								
	15th Block	1	58.30	3.15	0.15	27.55			
	S-HIG 32	1	41.80	5.40	0.15	33.86			
	Opp To Annapurnashweri Catering	1	73.70	4.15	0.15	45.88			
	S-LIG 42								
	Beside Neha Praksha Hospital	1	48.50	3.40	0.15	24.74			
	SFS 208								
	2nd Main Road RHS	1	161.50	1.33	0.15	32.22			
	3rd Main Road LHS	1	28.30	1.00	0.15	4.25			
	4th Cross Rd RHS From United Residency Association	1	116.60	0.62	0.15	10.84			
	4th Cross Rd LHS From Dental Clinic	1	78.20	0.80	0.15	9.38			
	BMS Hostel Opp Road LHS	1	71.20	0.59	0.15	6.30			
	BMS Hostel Opp Road RHS	1	102.80	0.59	0.15	9.10			
	Urdhu School Surrounding	1	100.00	3.05	0.15	45.75			
	Ward No-04								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	7th B Cross Rd	1	24.00	1.00	0.15	3.60			
	Vaidhika Sabha Building								
	Footings	19	1.80	1.80	0.15	9.23			
	SSM Foundation								
	Ritual Rooom-1								
	Long Wall	2	6.40	0.60	0.15	1.15			
	Short Wall	2	5.70	0.60	0.15	1.03			
	Ritual Rooom-2								
	Long Wall	2	6.40	0.75	0.15	1.44			
	Short Wall	1	5.70	0.75	0.15	0.64			
	Ritual Rooom-3								
	Long Wall	2	6.40	0.75	0.15	1.44			
	Short Wall	1	5.70	0.75	0.15	0.64			
	Store Room								
	Long Wall	1	5.70	0.75	0.15	0.64			
	Short Wall	2	4.90	0.75	0.15	1.10			
	Kitchen								
	Long Wall	2	4.40	0.75	0.15	0.99			
	Short Wall	2	3.80	0.75	0.15	0.86			
	Room								
	Long Wall	2	4.40	0.75	0.15	0.99			
	Short Wall	1	3.80	0.75	0.15	0.43			
	Room-1								
	Long Wall	1	3.80	0.75	0.15	0.43			
	Short Wall	2	3.30	0.75	0.15	0.74			
	Toilet-1								
	Long Wall	1	3.80	0.75	0.15	0.43			
	Short Wall	2	2.90	0.75	0.15	0.65			
	Toilet-2								
	Long Wall	2	4.40	0.75	0.15	0.99			
	Short Wall	1	3.80	0.75	0.15	0.43			
	Corridor	2	5.50	0.75	0.15	1.24			
	Near Compound	2	0.90	0.75	0.15	0.20			
	SUMP								
	Sump	1	3.00	3.00	0.15	1.35			
	Compound Wall								
		1	87.20	0.75	0.15	9.81			
						1269.01	**Cum**	**6362.29**	**8073826.30**
	Approved Amount	**6362.29**							
4	**Supplying, Fitting and Placing un-coated TMT bar** Reinforcement in sub-structure complete as per Drawing and Technical Specifications.(V-III, I No 13.1 Page No 99, PWD SR 2021-22)								
	For RCC Drain, 63kg/Cum	1	1354.59	63.00		85339.32			
	For RCC Culvert, 85kg/Cum	1	61.73	85.00		5246.88			
						90.61	**Tn**	**114292.20**	**10356016.24**
	Approved Amount	**114292.20**							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
5	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) **M20 Design Mix Using 20 mm nominal** size graded crushed coarse aggregates (V-1,P.No.17, I.No.2.4.2 of PWD SR 2021-22)								
	Rcc Drain Raft								
	Ward No-03								
	From Sandeep Unnikrishan Main Road, Thirumala nagara main road	2	285.45	0.90	0.15	77.07			
	8th A Main road (LHS)	1	77.80	0.90	0.15	10.50			
	From Sandeep Unnikrishan Main Road, 3rd A Main road	2	82.85	0.75	0.15	18.64			
	3rd A Main road Continued (RHS)	1	17.90	0.75	0.15	2.01			
	From Veersagar Main Road, 5th Cross road (LHS) Muneshwara layout	1	44.50	0.75	0.15	5.01			
	Cross road 1	2	53.05	0.90	0.15	14.32			
	Srl Sai Layout								
	From Veersagar Main Road, Sai Layout Main Road (LHS)	2	100.70	0.90	0.15	27.19			
	Sai Layout Cross Road(RHS)	1	13.50	0.90	0.15	1.82			
	Sai Layout 1st A Main Road (LHS)	2	147.50	0.90	0.15	39.83			
	Sai Layout 1st A Main Road	1	22.50	0.90	0.15	3.04			
	From Veersagar Main Road, Hanumayya Layout(Adjacent to Trivik Apt)								
	1st Main Road (LHS)	1	147.90	0.60	0.15	13.31			
	Cross Road 1 (LHS)	1	8.80	0.60	0.15	1.10			
	2nd Main Road (LHS) (From Dhanush Nilaya)	1	38.30	0.60	0.15	3.45			
	From Veersagar Main Road, Cross Road 1	2	17.50	0.90	0.15	4.73			
	Sai Layout 2nd A Main Road	2	136.65	0.90	0.15	36.90			
	From Veersagar Main Road, 11th Cross Road (RHS)	1	49.00	0.90	0.15	6.62			
	6th Cross Road	2	59.95	0.90	0.15	16.19			
	Santhosh Nagara								
	1st Cross Rd LHS	1	149.60	0.90	0.15	20.20			
	7th Cross Rd RHS	1	117.30	0.84	0.15	14.69			
	Attur Village Rd RHS	1	111.30	0.80	0.15	13.36			
	Veerasagara								
	5th Cross Rd LHS	1	95.30	0.80	0.15	11.44			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Muneshwara Layout								
	4th Cross Rd LHS	1	45.00	0.80	0.15	5.40			
	2nd Cross Rd LHS	1	44.80	0.80	0.15	5.38			
	1st Cross Rd LHS	1	34.10	0.80	0.15	4.09			
	4th Cross Rd RHS	1	172.00	0.80	0.15	20.64			
	6th Cross Rd								
	1st Cross Rd LHS	1	22.50	0.90	0.15	3.04			
	2nd Cross Rd	2	25.00	0.90	0.15	6.75			
	3rd Cross Rd	2	22.25	0.90	0.15	6.01			
	4th Cross Rd LHS	1	11.10	0.90	0.15	1.50			
	4th Cross Rd RHS	1	22.50	0.90	0.15	3.04			
	Ward No -04								
	From 9th B Cross Road, 6th B Main road - B - Sector (RHS)	1	12.70	1.20	1.00	15.24			
	From 9th B Cross Road 6th B Main road - B - Sector (LHS)	1	305.80	1.20	0.15	55.04			
	From 9th B Cross Road, 7th B Main Road (RHS)	1	245.60	1.20	0.15	44.21			
	From 8th B Cross Road, 7th B Main road - B - Sector (RHS)	1	226.20	1.20	0.15	40.72			
	7th B Main road - B - Sector (LHS)	1	52.70	1.20	0.15	9.49			
	From Sandeep Unnikrishan Main Road, 4th B Cross road - B - Sector	2	124.50	0.90	0.15	33.62			
	4th B Cross road Continued (RHS)	1	17.40	0.90	0.15	2.35			
	From 4th B Cross road - B - Sector, 8th B Main road (LHS)	1	58.00	0.90	0.15	7.83			
	From 10th B Cross road, 11th B Cross road (RHS)	1	17.00	0.90	0.15	2.30			
	From 10th B Cross road, 11th B Cross road (RHS)	1	16.40	0.90	0.15	2.21			
	Rcc Drain Wall								
	Ward No-03								
	From Sandeep Unnikrishan Main Road, Thirumala nagara main road	4	285.45	0.15	0.60	102.76			
	8th A Main road (LHS)	2	77.80	0.15	0.60	14.00			
	From Sandeep Unnikrishan Main Road, 3rd A Main road	4	82.85	0.15	0.45	22.37			
	3rd A Main road Continued (RHS)	2	17.90	0.15	0.37	1.99			
	From Veersagar Main Road, 5th Cross road (LHS) Muneshwara layout	2	44.50	0.15	0.37	4.93			
	Cross road 1	4	53.05	0.15	0.60	19.10			
	Sri Sai Layout								
	From Veersagar Main Road, Sai Layout Main Road (LHS)	4	100.70	0.15	0.60	36.25			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Sai Layout Cross Road(RHS)	2	13.50	0.15	0.60	2.43			
	Sai Layout 1st A Main Road (LHS)	4	147.50	0.15	0.60	53.10			
	Sai Layout 1st A Main Road	2	22.50	0.15	0.60	4.05			
	From Veersagar Main Road, Hanumayya Layout(Adjacent to Trivik Apt)								
	1st Main Road (LHS)	2	147.90	0.10	0.40	11.83			
	Cross Road 1 (LHS)	2	8.80	0.10	0.40	0.70			
	2nd Main Road (LHS) (From Dhanush Nialaya)	2	38.30	0.10	0.40	3.06			
	From Veersagar Main Road, Cross Road 1	4	17.50	0.15	0.60	6.30			
	Sai Layout 2nd A Main Road	4	136.65	0.15	0.60	49.19			
	From Veersagar Main Road, 11th Cross Road (RHS)	2	49.00	0.15	0.60	8.82			
	6th Cross Road	4	59.95	0.15	0.60	21.73			
	Santhosh Nagara								
	1st Cross Rd LHS	2	149.60	0.15	0.60	26.93			
	7th Cross Rd RHS	2	117.30	0.15	0.60	21.11			
	Attur Village Rd RHS	2	111.30	0.15	0.60	20.03			
	Veerasagara								
	5th Cross Rd LHS	2	95.30	0.15	0.60	17.15			
	Muneshwara Layout								
	4th Cross Rd LHS	2	45.00	0.15	0.60	8.10			
	2nd Cross Rd LHS	2	44.80	0.15	0.60	8.06			
	1st Cross Rd LHS	2	34.10	0.15	0.60	6.14			
	4th Cross Rd RHS	2	172.00	0.15	0.60	30.96			
	6th Cross Rd								
	1st Cross Rd LHS	2	22.50	0.15	0.60	4.05			
	2nd Cross Rd	4	25.00	0.15	0.60	9.00			
	3rd Cross Rd	4	22.25	0.15	0.60	8.01			
	4th Cross Rd LHS	2	11.10	0.15	0.60	2.00			
	4th Cross Rd RHS	2	22.50	0.15	0.60	4.05			
	Ward No -04								
	From 9th B Cross Road, 6th B Main road - B - Sector (RHS)	2	12.70	0.15	0.60	2.29			
	From 9th B Cross Road 6th B Main road - B - Sector (LHS)	2	305.80	0.15	0.60	55.04			
	From 9th B Cross Road, 7th B Main Road (RHS)	2	245.60	0.15	0.60	44.21			
	From 8th B Cross Road, 7th B Main road - B - Sector (RHS)	2	226.20	0.15	0.60	40.72			
	7th B Main road - B - Sector (LHS)	2	52.70	0.15	0.60	9.49			
	From Sandeep Unnikrishan Main Road, 4th B Cross road - B - Sector	4	124.50	0.15	0.60	44.82			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	4th B Cross road Continued (RHS)	2	17.40	0.15	0.60	3.13			
	From 4th B Cross road - B - Sector, 8th B Main road (LHS)	2	58.00	0.15	0.60	10.44			
	From 10th B Cross road, 11th B Cross road (RHS)	2	17.00	0.15	0.60	3.06			
	From 10th B Cross road, 11th B Cross road (RHS)	2	16.40	0.15	0.60	2.95			
						1354.59			
	Drain Coping								
	Attur Village Rd LHS	2	60.00	0.15	0.30	5.40			
	SFS 407								
	3rd B Cross Rd LHS	2	71.50	0.15	0.10	2.15			
	3rd B Cross Rd RHS	2	82.00	0.15	0.15	3.69			
	Tirumalanagaara								
	Connecting Road RAFT	1	41.20	0.60	0.15	3.71			
	Connecting Road Coping	2	41.20	0.15	0.15	1.85			
						16.80			
	Culvert Raft								
	Ward No -03								
	3rd A Main road	1	3.70	1.20	0.15	0.67			
		8	5.78	1.20	0.20	11.10			
	Ward No -04								
	6th B Main road - B - Sector (LHS)	1	7.80	1.50	0.15	1.76			
		1	7.50	1.50	0.15	1.69			
		1	4.90	1.50	0.15	1.10			
	7th B Main Road (RHS)	1	6.00	1.20	0.15	1.08			
		1	7.50	1.50	0.15	1.69			
		1	3.50	1.50	0.15	0.79			
	7th B Main road - B - Sector (RHS)	1	8.00	1.50	0.15	1.80			
		1	9.00	1.50	0.15	2.03			
	4th B Cross road - B - Sector (RHS)	1	4.90	1.20	0.15	0.88			
	4th B Cross road Continued (RHS)	1	9.30	1.50	0.15	2.09			
	2nd B Main road (RHS)	1	7.60	1.20	0.15	1.37			
	Culvert Wall								
	Ward No -03								
	3rd A Main road	2	3.70	0.20	0.65	0.96			
		16	5.78	0.23	0.61	12.97			
	Ward No -04								
	6th B Main road - B - Sector (LHS)	2	7.80	0.20	0.65	2.03			
		2	7.50	0.20	0.65	1.95			
		2	4.90	0.20	0.65	1.27			
	7th B Main Road (RHS)	2	6.00	0.20	0.65	1.56			
		2	7.50	0.20	0.65	1.95			
		2	3.50	0.20	0.65	0.91			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	7th B Main road - B - Sector (RHS)	2	8.00	0.20	0.65	2.08			
		2	9.00	0.20	0.65	2.34			
	4th B Cross road - B - Sector (RHS)	2	4.90	0.20	0.65	1.27			
	4th B Cross road Continued (RHS)	2	9.30	0.20	0.65	2.42			
	2nd B Main road (RHS)	2	7.60	0.20	0.65	1.98			
						61.73			
						1433.12	Cum	7265.75	10412667.79
	Approved Amount	7265.75							
6	Providing and fixing **precast reinforced cement concrete covering slabs of 10Cm** thick made of M20 with OPC cement,with 20mm and down size graded granite metal coarse aggregate @0.70 mixed, Inculding providing and removing centering, shuttering, strutting propping etc., for edges of slabs with TMT steel (Fe500) cost of all materials, labour, all lead and lift, HOM of machinery, curing, including cost of reinforcement etc., complete as directed by the Engineer in charge of the work								
	Ward No-03								
	From Sandeep Unnikrishan Main Road, Thirumala nagara main road	2	229.30	0.90		412.74			
	8th A Main road (LHS)	1	68.80	0.90		61.92			
	From Sandeep Unnikrishan Main Road, 3rd A Main road	2	57.85	0.75		86.78			
	3rd A Main road Continued (RHS)	1	11.80	0.75		8.85			
	From Veersagar Main Road, 5th Cross road (LHS) Muneshwara layout	1	34.80	0.75		26.10			
	Cross road 1	2	48.60	0.90		87.48			
	Sri Sai Layout								
	From Veersagar Main Road, Sai Layout Main Road (LHS)	2	100.70	0.90		181.26			
	Sai Layout Cross Road(RHS)	1	13.50	0.90		12.15			
	Sai Layout 1st A Main Road (LHS)	2	93.35	0.90		168.03			
	Sai Layout 1st A Main Road	1	22.50	0.90		20.25			
	From Veersagar Main Road, Hanumayya Layout(Adjacent to Trivik Apt)								
	1st Main Road (LHS)	1	147.90	0.60		88.74			
	Cross Road 1 (LHS)	1	8.80	0.60		7.34			
	2nd Main Road (LHS) (From Dhanush Nialaya)	1	38.30	0.60		22.98			
	From Veersagar Main Road, Cross Road 1	2	17.50	0.90		31.50			
	Sai Layout 2nd A Main Road	2	129.45	0.90		233.01			
	6th Cross Road	2	41.05	0.90		73.89			
	Santhosh Nagara								
	1st Cross Rd LHS	1	94.90	0.90		85.41			
	7th Cross Rd RHS	1	63.40	0.75		47.55			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Attur Village Rd RHS	1	111.30	0.75		83.48			
	Veerasagara								
	5th Cross Rd LHS	1	41.00	0.75		30.75			
	Muneshwara Layout								
	4th Cross Rd LHS	1	24.10	0.75		18.08			
	2nd Cross Rd LHS	1	36.10	0.75		27.08			
	1st Cross Rd LHS	1	31.80	0.75		23.85			
	4th Cross Rd RHS	1	100.90	0.75		75.68			
	6th Cross Rd								
	1st Cross Rd LHS	1	22.50	0.90		20.25			
	2nd Cross Rd	2	25.00	0.90		45.00			
	3rd Cross Rd	2	22.25	0.90		40.05			
	4th Cross Rd LHS	1	11.10	0.90		9.99			
	4th Cross Rd RHS	1	12.00	0.90		10.80			
	Attur Village Rd	1	60.00	0.90		54.00			
	Tirumalanagaara								
	Connecting Road RAFT	1	41.20	1.20		49.44			
	Ward No -04								
	From 9th B Cross Road 6th B Main road - B - Sector (LHS)	1	241.00	1.20		289.20			
	From 9th B Cross Road, 7th B Main Road (RHS)	1	260.60	1.20		312.72			
	From 8th B Cross Road, 7th B Main road - B - Sector (RHS)	1	226.20	1.20		271.44			
	7th B Main road - B - Sector (LHS)	1	19.70	0.90		17.73			
	From Sandeep Unnikrishan Main Road, 4th B Cross road - B - Sector	2	103.80	0.90		186.84			
	4th B Cross road Continued (RHS)	1	17.40	0.90		15.66			
	From 4th B Cross road - B - Sector, 8th B Main road (LHS)	1	58.00	0.90		52.20			
	From 10th B Cross road, 11th B Cross road (RHS)	1	17.00	0.90		15.30			
	From 10th B Cross road, 11th B Cross road (RHS)	1	16.40	0.90		14.76			
	Add Missing/Damaged Slab					2146.55			
						5466.80	**Sqm**	**2083.49**	**11390027.73**
	Approved Amount	**2083.49**							
7	Providing and fixing **RCC precast cover slab of 230mm thick** for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)								
	For Culverts								
	Ward No -03								
	3rd A Main road	1	3.70	1.20		4.56			
		8	5.78	1.20		55.49			
	Ward No -04								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	6th B Main road - B - Sector (LHS)	1	7.80	1.50		11.70			
		1	7.50	1.50		11.25			
		1	4.90	1.50		7.35			
	7th B Main Road (RHS)	1	6.00	1.50		9.00			
		1	7.50	1.50		11.25			
		1	3.50	1.50		5.25			
	7th B Main road - B - Sector (RHS)	1	8.00	1.20		9.60			
		1	9.00	1.20		10.80			
	4th B Cross road - B - Sector (RHS)	1	4.90	1.20		5.88			
	4th B Cross road Continued (RHS)	1	9.30	1.20		11.16			
	2nd B Main road (RHS)	1	7.60	1.20		9.12			
						162.41	**Sqm**	**5064.93**	**822586.79**
	Approved Amount	**5064.93**							
8	Providing and laying in position **plain cement concrete** for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. **Mix 1:3:6 (M10) Using 20** mm nominal size graded crushed coarse aggregates (V-I, No-2.1.4, P.No-15 of PWD SR 2021-22).								
	For Below Kerb Stone								
	Ward No-03								
	From Sandeep Unnikrishan Main Road, Thirumala nagara main road	1	220.00	0.20	0.10	4.40			
	From Sandeep Unnikrishan Main Road, 8th A Main road	1	305.80	0.20	0.10	6.12			
	8th A Main road (LHS)	1	77.80	0.20	0.10	1.56			
	From Veersagar Main Road, 5th Cross road (LHS) Muneshwara layout	1	44.50	0.20	0.10	0.89			
	Cross road 1	2	53.05	0.20	0.10	2.12			
	Sri Sai Layout								
	From Veersagar Main Road, Sai Layout Main Road (LHS)	2	100.70	0.20	0.10	4.03			
	Sai Layout Cross Road(RHS)	1	13.50	0.20	0.10	0.27			
	Sai Layout 1st A Main Road (LHS)	2	147.50	0.20	0.10	5.90			
	Attur Layout 3rd cross road	2	129.05	0.20	0.10	5.16			
	Attur Layout 4th cross road	2	158.25	0.20	0.10	6.33			
	Akshay Nagara								
	8th A Main Rd LHS	1	113.70	0.20	0.10	2.27			
	Santhosh Nagara								
	6th Cross Rd	2	148.05	0.20	0.10	5.92			
	Ward No -04								
	From 9th B Cross Road, 6th B Main road - B - Sector (RHS)	1	12.70	0.20	0.10	0.25			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	From 9th B Cross Road 6th B Main road - B - Sector (LHS)	1	305.80	0.20	0.10	6.12			
	From 9th B Cross Road, 7th B Main Road (RHS)	1	245.60	0.20	0.10	4.91			
	From 8th B Cross Road, 7th B Main road - B - Sector (RHS)	1	226.20	0.20	0.10	4.52			
	7th B Main road - B - Sector (LHS)	1	52.70	0.20	0.10	1.05			
	From Sandeep Unnikrishan Main Road, 4th B Cross road - B - Sector	2	124.50	0.20	0.10	4.98			
	4th B Cross road Continued (RHS)	1	17.40	0.20	0.10	0.35			
	From 4th B Cross road - B - Sector, 8th B Main road (LHS)	1	58.00	0.20	0.10	1.16			
	From 10th B Cross road, 11th B Cross road (RHS)	1	17.00	0.20	0.10	0.34			
	From 10th B Cross road, 11th B Cross road (RHS)	1	16.40	0.20	0.10	0.33			
	SFS 208								
	2nd Main Rd RHS	1	201.15	0.20	0.10	4.02			
	3rd Main Road LHS	1	30.00	0.20	0.10	0.60			
	SFS 407								
	1st A Main Road	1	182.50	0.20	0.10	3.65			
	1st Cross Rd	2	33.50	0.20	0.10	1.34			
	3rd B Cross Rd	2	74.40	0.20	0.10	2.98			
	Virupaksha Nilaya Rd	2	37.85	0.20	0.10	1.51			
	Shri Vinayaka Prathana Mandira	1	18.00	0.20	0.10	0.36			
	Akkaya Devi Temple Road RHS	2	184.00	0.20	0.10	7.36			
	11th Main rd	1	77.50	0.20	0.10	1.55			
	Urdhu School	1	23.90	0.20	0.10	0.48			
	Vaidhika Sabha Building Surrounding	1	272.70	0.20	0.10	5.45			
						98.29	**Cum**	**6554.75**	**644272.50**
	Approved Amount	**6554.75**							
9	**Providing and fixing pre cast solid cement concrete kerb stones** made out of M20 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc. complete as directed by the Engineer in Charge of the work (Approved Rate)								
	Ward No-03								
	From Sandeep Unnikrishan Main Road, Thirumala nagara main road	1	220.00			220.00			
	From Sandeep Unnikrishan Main Road, 8th A Main road	1	305.80			305.80			
	8th A Main road (LHS)	1	77.80			77.80			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	From Veersagar Main Road, 5th Cross road (LHS) Muneshwara layout	1	44.50			44.50			
	Cross road 1	2	53.05			106.10			
	Sri Sai Layout								
	From Veersagar Main Road, Sai Layout Main Road (LHS)	2	100.70			201.40			
	Sai Layout Cross Road(RHS)	1	13.50			12.96			
	Sai Layout 1st A Main Road (LHS)	2	147.50			295.00			
	Attur Layout 3rd cross road	2	173.60			347.20			
	Attur Layout 4th cross road	2	169.60			339.20			
	Akshay Nagara								
	8th A Main Rd LHS	1	113.70			113.70			
	Santhosh Nagara								
	6th Cross Rd	2	76.40			152.80			
	Ward No -04								
	From 9th B Cross Road, 6th B Main road - B - Sector (RHS)	1	12.70			12.70			
	From 9th B Cross Road 6th B Main road - B - Sector (LHS)	1	305.80			305.80			
	From 9th B Cross Road, 7th B Main Road (RHS)	1	245.60			245.60			
	From 8th B Cross Road, 7th B Main road - B - Sector (RHS)	1	226.20			226.20			
	7th B Main road - B - Sector (LHS)	1	52.70			52.70			
	From Sandeep Unnikrishan Main Road, 4th B Cross road - B - Sector	2	124.50			249.00			
	4th B Cross road Continued (RHS)	1	17.40			17.40			
	From 4th B Cross road - B - Sector, 8th B Main road (LHS)	1	58.00			58.00			
	From 10th B Cross road, 11th B Cross road (RHS)	1	17.00			17.00			
	From 10th B Cross road, 11th B Cross road (RHS)	1	16.40			16.40			
	SFS 208								
	2nd Main Rd RHS	1	201.15			201.15			
	3rd Main Road LHS	1	30.00			30.00			
	SFS 407								
	1st A Main Road	1	182.50			182.50			
	1st Cross Rd	2	33.50			67.00			
	3rd B Cross Rd	2	74.40			148.80			
	Virupaksha Nilaya Rd	2	37.85			75.70			
	Shri Vinayaka Prathana Mandira	1	18.00			18.00			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Akkaya Devi Temple Road RHS	2	184.00			368.00			
	11th Main rd	1	77.50			77.50			
	Urdhu School	1	23.90			23.90			
	Vaidhika Sabha Building Surrounding	1	272.70			272.70			
						4882.51	M		
						10850.00	Nos	509.81	5531452.77
	Approved Amount	509.81							
10	**Painting two coats** after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces (V-III, P.No.56, I.No.8.10 of PW, PWD SR 2021-22)								
	Ward No-03								
	From Sandeep Unnikrishan Main Road, Thirumala nagara main road	1	220.00		0.35	77.00			
	From Sandeep Unnikrishan Main Road, 8th A Main road	1	305.80		0.35	107.03			
	8th A Main road (LHS)	1	77.80		0.35	27.23			
	From Veersagar Main Road, 5th Cross road (LHS) Muneshwara layout	1	44.50		0.35	15.58			
	Cross road 1	2	53.05		0.35	37.14			
	Sri Sai Layout								
	From Veersagar Main Road, Sai Layout Main Road (LHS)	2	100.70		0.35	70.49			
	Sai Layout Cross Road(RHS)	1	13.50		0.35	4.54			
	Sai Layout 1st A Main Road (LHS)	2	147.50		0.35	103.25			
	Attur Layout 3rd cross road	2	173.60		0.35	121.52			
	Attur Layout 4th cross road	2	169.60		0.35	118.72			
	Akshay Nagara								
	8th A Main Rd LHS	1	113.70		0.35	39.80			
	Santhosh Nagara								
	6th Cross Rd	2	148.05		0.35	103.64			
	Ward No -04								
	From 9th B Cross Road, 6th B Main road - B - Sector (RHS)	1	12.70		0.35	4.45			
	From 9th B Cross Road 6th B Main road - B - Sector (LHS)	1	305.80		0.35	107.03			
	From 9th B Cross Road, 7th B Main Road (RHS)	1	245.60		0.35	85.96			
	From 8th B Cross Road, 7th B Main road - B - Sector (RHS)	1	226.20		0.35	79.17			
	7th B Main road - B - Sector (LHS)	1	52.70		0.35	18.45			
	From Sandeep Unnikrishan Main Road, 4th B Cross road - B - Sector	2	124.50		0.35	87.15			
	4th B Cross road Continued (RHS)	1	17.40		0.35	6.09			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	From 4th B Cross road - B - Sector, 8th B Main road (LHS)	1	58.00		0.35	20.30			
	From 10th B Cross road, 11th B Cross road (RHS)	1	17.00		0.35	5.95			
	From 10th B Cross road, 11th B Cross road (RHS)	1	16.40		0.35	5.74			
	SFS 208								
	2nd Main Rd RHS	1	201.15		0.35	70.40			
	3rd Main Road LHS	1	30.00		0.35	10.50			
	SFS 407								
	1st A Main Road	1	182.50		0.35	63.88			
	1st Cross Rd	2	33.50		0.35	23.45			
	3rd B Cross Rd	2	74.40		0.35	52.08			
	Virupaksha Nilaya Rd	2	37.85		0.35	26.50			
	Shri Vinayaka Prathana Mandira	1	18.00		0.35	6.30			
	Akkaya Devi Temple Road RHS	2	184.00		0.35	128.80			
	11th Main rd	1	77.50		0.35	27.13			
	Urdhu School	1	23.90		0.35	8.37			
	Vaidhika Sabha Building Surrounding	1	272.70		0.35	95.45			
						1759.03	**Sqm**	**94.02**	**165381.62**
	Approved Amount	**94.02**							
11	Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work ((V-I, P.No-8, I No-1.12 of PWD SR 2021-22)								
	Asphalt Road								
	Cut Portion								
	Akshay Nagar								
	1st Cross Rd	1	67.60	1.00	0.40	27.04			
	Main Road From Sandeep Unnikrishan Rd	1	338.50	1.00	0.40	135.40			
	Tirumalanagara 1st Cross Rd	1	61.80	1.00	0.40	24.72			
	Escorts Colony								
	6th C Cross Rd	1	58.60	1.00	0.40	23.44			
	6th B Cross Rd	1	54.40	1.20	0.40	26.11			
	6th A Main Road	1	156.30	1.00	0.40	62.52			
	1st Cross Rd	1	208.70	1.00	0.40	83.48			
	7th A Main Rd From Dead End	1	238.20	1.00	0.40	95.28			
	Ramadasappa Garden								
	1st Cross Rd	1	266.80	1.00	0.40	106.72			
	Santhosh Nagara								
	2nd Cross Rd	1	159.60	1.00	0.40	63.84			
	Connecting Rd-1	1	25.00	1.00	0.40	10.00			
	Connecting Rd-2	1	24.30	1.00	0.40	9.72			
	6th Cross Rd	1	165.40	1.20	0.40	79.39			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	6th Cross Rd Continue	1	259.30	1.00	0.40	103.72			
	Cross rd-1	1	64.20	1.20	0.40	30.82			
	Cross rd-2	1	19.00	1.00	0.40	7.60			
	Helath Care Home Rd	1	49.00	1.00	0.40	19.60			
	Helath Care Home Rd Continue	1	79.50	1.00	0.40	31.80			
	Cross rd-3	1	21.30	1.00	0.40	8.52			
	Amruthnagar Care Rd	1	24.00	1.00	0.40	9.60			
	Cross rd-4	1	36.40	1.60	0.40	23.30			
	Cross rd-5	1	23.20	1.60	0.40	14.85			
	Sri Laasya Rd	1	24.20	1.60	0.40	15.49			
	Cross rd-6[Door 13]	1	24.80	1.60	0.40	15.87			
	Varaha Entreprises Rd	1	22.50	1.20	0.40	10.80			
	Manjunatha Nilaya Rd	1	19.00	1.60	0.40	12.16			
	7th Cross Rd	1	218.70	2.00	0.40	174.96			
	White Petal School Rd	1	27.20	1.00	0.40	10.88			
	Muneshwara Layout								
	11th Cross Rd	1	47.20	1.00	0.40	18.88			
	Left Side Roads								
	10th Cross Rd	1	46.00	1.00	0.40	18.40			
	9th Cross Rd	1	99.00	1.00	0.40	39.60			
	Right Side Roads								
	10th Cross Rd	1	170.00	1.00	0.40	68.00			
	4th Cross Rd	1	45.00	1.60	0.40	28.80			
	2nd Cross Rd From Dead End	1	44.20	1.60	0.40	28.29			
	1st Cross Rd	1	45.00	1.60	0.40	28.80			
	3rd Cross Rd	1	161.00	1.60	0.40	103.04			
	5th Cross rd	1	270.60	1.60	0.40	173.18			
	6th Cross Rd								
	3rd Cross Rd	1	23.30	1.00	0.40	9.32			
	4th Cross Rd	1	21.60	1.00	0.40	8.64			
	Veerasagara Main Rd								
	[Muneshwaara Layout]								
	6th Cross Rd	1	56.80	1.00	0.40	22.72			
	6th A Cross Rd	1	65.20	1.10	0.40	28.69			
	8th Main Cross Rd-2	1	36.30	1.00	0.40	14.52			
	9th Main Rd	1	109.60	1.60	0.40	70.14			
	10th Main Road	1	46.50	1.60	0.40	29.76			
	11th Main rd	1	53.40	1.60	0.40	34.18			
	Attur Village Rd	1	118.10	1.60	0.40	75.58			
	Attur Village Main Rd	1	92.10	1.60	0.40	58.94			
	Sri Sai Layout								
	Cross Rd-4	1	140.50	1.00	0.40	56.20			
	Chitra Layout								
	Harshitha Nilaya	1	74.20	1.20	0.40	35.62			
	5th cross rd Attur layout	1	26.80	1.40	0.40	15.01			
	Ward No-04								
	B-sector								
	6th B Main Road	1	52.00	1.00	0.40	20.80			
	9th Cross Rd	1	45.30	1.00	0.40	18.12			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	7th B Main Rd	1	180.00	1.00	0.40	72.00			
	Edge Correction								
	Akshyanagar								
	2nd cross road	2	63.50	0.90	0.25	28.58			
	3rd cross road	2	64.50	0.95	0.25	30.64			
	4th cross road	2	63.50	1.00	0.25	31.75			
	5th cross road	2	60.00	1.20	0.25	36.00			
	6th cross road	2	65.00	0.90	0.25	29.25			
	7th cross road	2	64.00	0.95	0.25	30.40			
	8th A main road	2	257.60	1.00	0.25	128.80			
	State Bank of India road	2	139.00	1.20	0.25	83.40			
	2nd A main road	2	125.60	0.90	0.25	56.52			
	Attur Layout 2nd main road	2	341.90	0.95	0.25	162.40			
	Attur Layout 3rd main road	2	421.60	1.00	0.25	210.80			
	Attur Layout 4th main road (From End)	2	383.40	1.20	0.25	230.04			
	Attur Layout 5th main road	2	373.60	0.90	0.25	168.12			
	Attur Layout 6th main road (From End)	2	321.30	0.95	0.25	152.62			
	Attur Layout 7th main road	2	323.90	1.00	0.25	161.95			
	Attur Layout 8th main road	2	324.20	1.20	0.25	194.52			
	Attur Layout 1st cross road	2	226.20	0.55	0.25	62.21			
	Attur Layout 2nd cross road	2	255.10	0.50	0.25	63.78			
	Attur Layout 3rd cross road (From End)	2	285.70	0.49	0.25	70.00			
	Attur Layout 4th cross road	2	263.70	0.55	0.25	72.52			
	Under 11th cross Road (Muneshwara Layout)								
	1st Cross Road	2	33.00	0.55	0.25	9.08			
	2nd Cross Road	2	34.60	0.60	0.25	10.38			
	3rd Cross Road	2	38.20	0.45	0.25	8.60			
	Akshay Nagar								
	1st Cross Rd	2	67.60	0.50	0.40	27.04			
	Main Road From Sandeep Unnikrishan Rd	2	338.50	0.50	0.40	135.40			
	Tirumalanagara 1st Cross Rd	2	61.80	0.50	0.40	24.72			
	Escorts Colony								
	6th C Cross Rd	2	58.60	0.50	0.40	23.44			
	6th B Cross Rd	2	54.40	0.50	0.40	21.76			
	6th A Main Road	2	156.30	0.50	0.40	62.52			
	1st Cross Rd	2	208.70	0.50	0.40	83.48			
	7th A Main Rd From Dead End	2	238.20	0.50	0.40	95.28			
	Ramadasappa Garden								
	1st Cross Rd	2	266.80	0.50	0.40	106.72			
	Santhosh Nagara								
	2nd Cross Rd	2	159.60	0.50	0.40	63.84			
	Connecting Rd-1	2	25.00	0.50	0.40	10.00			
	Connecting Rd-2	2	24.30	0.50	0.40	9.72			
	6th Cross Rd	2	165.40	0.50	0.40	66.16			
	6th Cross Rd Continue	2	259.30	0.50	0.40	103.72			
	Cross rd-1	2	64.20	0.50	0.40	25.68			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Cross rd-2	2	19.00	0.50	0.40	7.60			
	Helath Care Home Rd	2	49.00	0.50	0.40	19.60			
	Helath Care Home Rd Continue	2	79.50	0.50	0.40	31.80			
	Cross rd-3	2	21.30	0.50	0.40	8.52			
	Amruthnagar Care Rd	2	24.00	0.50	0.40	9.60			
	Cross rd-4	2	36.40	0.50	0.40	14.56			
	Cross rd-5	2	23.20	0.40	0.40	7.42			
	Sri Laasya Rd	2	24.20	0.50	0.40	9.68			
	Cross rd-6(Door 13)	2	24.80	0.40	0.40	7.94			
	Varaha Entreprises Rd	2	22.50	0.40	0.40	7.20			
	Manjunatha Nilaya Rd	2	19.00	0.50	0.40	7.60			
	7th Cross Rd	2	218.70	0.50	0.40	87.48			
	White Petal School Rd	2	27.20	0.50	0.40	10.88			
	Muneshwara Layout								
	11th Cross Rd	2	47.20	0.50	0.40	18.88			
	Left Side Roads								
	10th Cross Rd	2	46.00	0.50	0.40	18.40			
	9th Cross Rd	2	99.00	0.50	0.40	39.60			
	Right Side Roads								
	10th Cross Rd	2	170.00	0.50	0.40	68.00			
	4th Cross Rd	2	45.00	0.50	0.40	18.00			
	2nd Cross Rd From Dead End	2	44.20	0.50	0.40	17.68			
	1st Cross Rd	2	45.00	0.50	0.40	18.00			
	3rd Cross Rd	2	161.00	0.50	0.40	64.40			
	5th Cross rd	2	270.60	0.50	0.40	108.24			
	6th Cross Rd								
	3rd Cross Rd	2	23.30	1.00	0.40	18.64			
	4th Cross Rd	2	21.60	1.00	0.40	17.28			
	Veerasagara Main Rd								
	[Muneshwaara Layout]								
	6th Cross Rd	2	56.80	0.65	0.40	29.54			
	6th A Cross Rd	2	65.20	0.50	0.40	26.08			
	8th Main Cross Rd-2	2	36.30	0.50	0.40	14.52			
	9th Main Rd	2	109.60	0.50	0.40	43.84			
	10th Main Road	2	46.50	0.40	0.40	14.88			
	11th Main rd	2	53.40	0.40	0.40	17.09			
	Attur Village Rd	2	118.10	0.50	0.40	47.24			
	Attur Village Main Rd	2	92.10	0.50	0.40	36.84			
	Sri Sai Layout								
	Cross Rd-4	2	140.50	0.50	0.40	56.20			
	Chitra Layout								
	Harshitha Nilaya	2	74.20	0.50	0.40	29.68			
	5th cross rd Attur layout	2	26.80	0.48	0.40	10.29			
	SFS 407								
	1st A Main Road From Dead End	2	98.80	1.00	0.40	79.04			
	1st Cross Rd	2	42.00	1.00	0.40	33.60			
	5th Phase 2nd Main Rd	2	119.10	1.10	0.40	104.81			
	Santhosh Nagara								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	1st Cross Rd	2	47.50	1.00	0.40	38.00			
	1st A Cross Rd	2	102.70	1.30	0.40	106.81			
	Mamatha Nilaya Rd	2	12.50	1.30	0.40	13.00			
	1st A Cross Rd Continue	2	33.10	1.30	0.40	34.42			
	Attur Layout								
	1st Cross Rd From 9th Main Rd	2	22.10	1.30	0.40	22.98			
	10th Main Road	2	184.70	1.30	0.40	192.09			
	4th Main Road[SFS 407]	2	128.10	1.05	0.40	107.60			
	2nd Main Rd[SFS 208]	2	211.20	1.50	0.40	253.44			
	1st Main Road[SFS 208]	2	166.00	1.50	0.40	199.20			
	1st Main Road Continue	2	145.10	1.50	0.40	174.12			
	1st Main Rd[25 to 38] SFS 208	2	158.10	1.50	0.40	189.72			
	SFS 208	2	200.00	1.50	0.40	240.00			
	SFS Cross Rd	2	300.00	1.60	0.40	384.00			
	SFS Cross Rd	2	265.00	1.50	0.40	318.00			
	Ward No-04								
	10th B Main B Sector	2	35.20	0.55	0.25	9.68			
	2nd B Main B Sector	2	72.10	0.60	0.25	21.63			
	11th B Cross Road B Sector	2	76.20	0.45	0.25	17.15			
	From Sandeep Unnikrishnan Main Road, 4th B Cross Road	2	137.30	0.55	0.25	37.76			
	th B Cross Road Continued	2	16.20	0.60	0.40	7.78			
	From 3rd B Cross Road, 7th B Main	2	67.30	0.60	0.25	20.19			
	B-sector								
	6th B Main Road	2	52.00	0.50	0.40	20.80			
	9th Cross Rd	2	45.30	0.55	0.40	19.93			
	7th B Main Rd	2	180.00	0.50	0.40	72.00			
	New Asphalt Road								
	Santhosh Nagara								
	1st Cross Rd	1	164.50	4.65	0.40	305.97			
	4th Cross Rd	1	148.10	4.80	0.40	284.35			
	Tharaman Sharma Rd	1	33.20	4.14	0.40	54.98			
	9th B Cross Rd	1	36.00	3.93	0.40	56.52			
	Muneshwara Layout								
	Right Side Roads								
	9th Cross Rd	1	170.00	4.76	0.40	323.68			
	4th Cross Rd	1	172.40	5.22	0.40	359.97			
	1st Cross Rd	1	27.50	4.39	0.40	48.29			
	2nd Cross Rd	1	25.00	5.00	0.40	50.00			
	Veerasagara Main Rd								
	[Muneshwaara Layout]								
	6th B Cross Rd	1	116.50	4.48	0.40	208.77			
	5th A Cross Rd	1	92.30	5.50	0.40	203.06			
	6th Cross Rd	1	133.00	5.05	0.40	268.66			
	Sri Sai Layout								
	Cross Rd-1	1	109.00	7.42	0.40	323.51			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Cross RD-2	1	30.00	8.40	0.40	100.80			
	Cross RD-3	1	131.00	6.03	0.40	315.97			
	Chitra Layout								
	3rd Cross Rd	1	150.00	4.21	0.40	252.60			
	Santhosh Nagara								
	1st Main Road	1	19.00	2.10	0.40	15.96			
	Vijaya Bank Layout								
	1st Cross Rd	1	58.50	5.30	0.40	124.02			
	2nd Cross Rd	1	31.30	5.60	0.40	70.11			
	3rd Cross Rd	1	63.15	6.25	0.40	157.88			
	Ayyappa Layout								
	8th Cross Rd	1	38.10	5.50	0.40	83.82			
	4th Main Road	1	33.00	7.00	0.40	92.40			
	For Cobble Stone								
	S-LIG - 10,11	1	39.80	6.20	0.10	24.68			
	S-LIG - 08,09	1	24.20	6.70	0.10	16.21			
	S-LIG - 07	1	6.80	4.00	0.10	2.72			
	S-LIG - 06	1	35.50	7.00	0.10	24.85			
	S-LIG - 05	1	4.20	4.20	0.10	1.76			
	S-LIG - 03	1	39.60	4.00	0.10	15.84			
	S-LIG - 01	1	34.60	6.26	0.10	21.66			
	Near Nandini Parlour(Indian Sweets Bakery)	1	31.30	3.50	0.10	10.96			
	Bheema Blocks HIG - B - 2	1	41.40	5.00	0.10	21.11			
	Concreet Road								
	Vaidhika Sabha Building Inside	1	68.30	5.95	0.35	142.23			
						12870.96	Cum		
				Upto 125%		10110.15	Cum	71.90	726884.07
				Above 125%		2760.81	Cum	71.90	198492.23
	Approved Amount	71.90							
12	Construction of **Granular Sub-Base** of required grading as per design mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401 (V-III, I No-4.1V,P No-19,KPWD SR 2021-22)								
	Asphalt Road								
	Cut Portion								
	Akshay Nagar								
	1st Cross Rd	1	67.60	1.00	0.15	10.14			
	Main Road From Sandeep Unnikrishan Rd	1	338.50	1.00	0.15	50.78			
	Tirumalanagara 1st Cross Rd	1	61.80	1.00	0.15	9.27			
	Escorts Colony								
	6th C Cross Rd	1	58.60	1.00	0.15	8.79			
	6th B Cross Rd	1	54.40	1.20	0.15	9.79			
	6th A Main Road	1	156.30	1.00	0.15	23.45			
	1st Cross Rd	1	208.70	1.00	0.15	31.31			
	7th A Main Rd From Dead End	1	238.20	1.00	0.15	35.73			
	Ramadasappa Garden								
	1st Cross Rd	1	266.80	1.00	0.15	40.02			
	Santhosh Nagara								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	2nd Cross Rd	1	159.60	1.00	0.15	23.94			
	Connecting Rd-1	1	25.00	1.00	0.15	3.75			
	Connecting Rd-2	1	24.30	1.00	0.15	3.65			
	6th Cross Rd	1	165.40	1.20	0.15	29.77			
	6th Cross Rd Continue	1	259.30	1.00	0.15	38.90			
	Cross rd-1	1	64.20	1.20	0.15	11.56			
	Cross rd-2	1	19.00	1.00	0.15	2.85			
	Helath Care Home Rd	1	49.00	1.00	0.15	7.35			
	Helath Care Home Rd Continue	1	79.50	1.00	0.15	11.93			
	Cross rd-3	1	21.30	1.00	0.15	3.20			
	Amruthnagar Care Rd	1	24.00	1.00	0.15	3.60			
	Cross rd-4	1	36.40	1.60	0.15	8.74			
	Cross rd-5	1	23.20	1.60	0.15	5.57			
	Sri Laasya Rd	1	24.20	1.60	0.15	5.81			
	Cross rd-6[Door 13]	1	24.80	1.60	0.15	5.95			
	Varaha Entreprises Rd	1	22.50	1.20	0.15	4.05			
	Manjunatha Nilaya Rd	1	19.00	1.60	0.15	4.56			
	7th Cross Rd	1	218.70	2.00	0.15	65.61			
	White Petal School Rd	1	27.20	1.00	0.15	4.08			
	Muneshwara Layout								
	11th Cross Rd	1	47.20	1.00	0.15	7.08			
	Left Side Roads								
	10th Cross Rd	1	46.00	1.00	0.15	6.90			
	9th Cross Rd	1	99.00	1.00	0.15	14.85			
	Right Side Roads								
	10th Cross Rd	1	170.00	1.00	0.15	25.50			
	4th Cross Rd	1	45.00	1.60	0.15	10.80			
	2nd Cross Rd From Dead End	1	44.20	1.60	0.15	10.61			
	1st Cross Rd	1	45.00	1.60	0.15	10.80			
	3rd Cross Rd	1	161.00	1.60	0.15	38.64			
	5th Cross rd	1	270.60	1.60	0.15	64.94			
	6th Cross Rd								
	3rd Cross Rd	1	23.30	1.00	0.15	3.50			
	4th Cross Rd	1	21.60	1.00	0.15	3.24			
	Veerasagara Main Rd								
	[Muneshwaara Layout]								
	6th Cross Rd	1	56.80	1.00	0.15	8.52			
	6th A Cross Rd	1	65.20	1.10	0.15	10.76			
	8th Main Cross Rd-2	1	36.30	1.00	0.15	5.45			
	9th Main Rd	1	109.60	1.60	0.15	26.30			
	10th Main Road	1	46.50	1.60	0.15	11.16			
	11th Main rd	1	53.40	1.60	0.15	12.82			
	Attur Village Rd	1	118.10	1.60	0.15	28.34			
	Attur Village Main Rd	1	92.10	1.60	0.15	22.10			
	Sri Sai Layout								
	Cross Rd-4	1	140.50	1.00	0.15	21.08			
	Chitra Layout								
	Harshitha Nilaya	1	74.20	1.20	0.15	13.36			
	5th cross rd Attur layout	1	26.80	1.40	0.15	5.63			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Ward No-04								
	B-sector								
	6th B Main Road	1	52.00	1.00	0.15	7.80			
	9th Cross Rd	1	45.30	1.00	0.15	6.80			
	7th B Main Rd	1	180.00	1.00	0.15	27.00			
	Edge Correction								
	Akshyanagar								
	2nd cross road	2	63.50	0.90	0.15	17.15			
	3rd cross road	2	64.50	0.95	0.15	18.38			
	4th cross road	2	63.50	1.00	0.15	19.05			
	5th cross road	2	60.00	1.20	0.15	21.60			
	6th cross road	2	65.00	0.90	0.15	17.55			
	7th cross road	2	64.00	0.95	0.15	18.24			
	8th A main road	2	257.60	1.00	0.15	77.28			
	State Bank of India road	2	139.00	1.20	0.15	50.04			
	2nd A main road	2	125.60	0.90	0.15	33.91			
	Attur Layout 2nd main road	2	341.90	0.95	0.15	97.44			
	Attur Layout 3rd main road	2	421.60	1.00	0.15	126.48			
	Attur Layout 4th main road (From End)	2	383.40	1.20	0.15	138.02			
	Attur Layout 5th main road	2	373.60	0.90	0.15	100.87			
	Attur Layout 6th main road (From End)	2	321.30	0.95	0.15	91.57			
	Attur Layout 7th main road	2	323.90	1.00	0.15	97.17			
	Attur Layout 8th main road	2	324.20	1.20	0.15	116.71			
	Attur Layout 1st cross road	2	226.20	0.55	0.15	37.32			
	Attur Layout 2nd cross road	2	255.10	0.50	0.15	38.27			
	Attur Layout 3rd cross road (From End)	2	285.70	0.49	0.15	42.00			
	Attur Layout 4th cross road	2	263.70	0.55	0.15	43.51			
	Under 11th cross Road (Muneshwara Layout)								
	1st Cross Road	2	33.00	0.55	0.15	5.45			
	2nd Cross Road	2	34.60	0.60	0.15	6.23			
	3rd Cross Road	2	38.20	0.45	0.15	5.16			
	Akshay Nagar								
	1st Cross Rd	2	67.60	0.50	0.15	10.14			
	Main Road From Sandeep Unnikrishan Rd	2	338.50	0.50	0.15	50.78			
	Tirumalanagara 1st Cross Rd	2	61.80	0.50	0.15	9.27			
	Escorts Colony								
	6th C Cross Rd	2	58.60	0.50	0.15	8.79			
	6th B Cross Rd	2	54.40	0.50	0.15	8.16			
	6th A Main Road	2	156.30	0.50	0.15	23.45			
	1st Cross Rd	2	208.70	0.50	0.15	31.31			
	7th A Main Rd From Dead End	2	238.20	0.50	0.15	35.73			
	Ramadasappa Garden								
	1st Cross Rd	2	266.80	0.50	0.15	40.02			
	Santhosh Nagara								
	2nd Cross Rd	2	159.60	0.50	0.15	23.94			
	Connecting Rd-1	2	25.00	0.50	0.15	3.75			
	Connecting Rd-2	2	24.30	0.50	0.15	3.65			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	1st Cross Rd	2	42.00	1.00	0.15	12.60			
	5th Phase 2nd Main Rd	2	119.10	1.10	0.15	39.30			
	Santhosh Nagara								
	1st Cross Rd	2	47.50	1.00	0.15	14.25			
	1st A Cross Rd	2	102.70	1.30	0.15	40.05			
	Mamatha Nilaya Rd	2	12.50	1.30	0.15	4.88			
	1st A Cross Rd Continue	2	33.10	1.30	0.15	12.91			
	Attur Layout								
	1st Cross Rd From 9th Main Rd	2	22.10	1.30	0.15	8.62			
	10th Main Road	2	184.70	1.30	0.15	72.03			
	4th Main Road[SFS 407]	2	128.10	1.05	0.15	40.35			
	2nd Main Rd[SFS 208]	2	211.20	1.50	0.15	95.04			
	1st Main Road[SFS 208]	2	166.00	1.50	0.15	74.70			
	1st Main Road Continue	2	145.10	1.50	0.15	65.30			
	1st Main Rd[25 to 38] SFS 208	2	158.10	1.50	0.15	71.15			
	SFS 208	2	200.00	1.50	0.15	90.00			
	SFS Cross Rd	2	300.00	1.60	0.15	144.00			
	SFS Cross Rd	2	265.00	1.50	0.15	119.25			
	Ward No-04								
	10th B Main B Sector	2	35.20	0.55	0.15	5.81			
	2nd B Main B Sector	2	72.10	0.60	0.15	12.98			
	11th B Cross Road B Sector	2	76.20	0.45	0.15	10.29			
	From Sandeep Unnikrishnan Main Road, 4th B Cross Road	2	137.30	0.55	0.15	22.65			
	th B Cross Road Continued	2	16.20	0.60	0.15	2.92			
	From 3rd B Cross Road, 7th B Main	2	67.30	0.60	0.14	11.48			
	B-sector								
	6th B Main Road	2	52.00	0.50	0.15	7.80			
	9th Cross Rd	2	45.30	0.55	0.15	7.47			
	7th B Main Rd	2	180.00	0.50	0.15	27.00			
	New Asphalt Road								
	Santhosh Nagara								
	1st Cross Rd	1	164.50	4.65	0.15	114.74			
	4th Cross Rd	1	148.10	4.80	0.15	106.63			
	Tharaman Sharma Rd	1	33.20	4.14	0.15	20.62			
	9th B Cross Rd	1	36.00	3.93	0.15	21.20			
	Muneshwara Layout								
	Right Side Roads								
	9th Cross Rd	1	170.00	4.76	0.15	121.38			
	4th Cross Rd	1	172.40	5.22	0.15	134.99			
	1st Cross Rd	1	27.50	4.39	0.15	18.11			
	2nd Cross Rd	1	25.00	5.00	0.15	18.75			
	Veerasagara Main Rd								
	[Muneshwaara Layout]								
	6th B Cross Rd	1	116.50	4.48	0.15	78.29			
	5th A Cross Rd	1	92.30	5.50	0.15	76.15			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	6th Cross Rd	1	133.00	5.05	0.15	100.75			
	Sri Sai Layout								
	Cross Rd-1	1	109.00	7.42	0.15	121.32			
	Cross RD-2	1	30.00	8.40	0.15	37.80			
	Cross RD-3	1	131.00	6.03	0.15	118.49			
	Chitra Layout								
	3rd Cross Rd	1	150.00	4.21	0.15	94.73			
	Santhosh Nagara								
	1st Main Road	1	19.00	2.10	0.15	5.99			
	Vijaya Bank Layout								
	1st Cross Rd	1	58.50	5.30	0.15	46.51			
	2nd Cross Rd	1	31.30	5.60	0.15	26.29			
	3rd Cross Rd	1	63.15	6.25	0.15	59.20			
	Ayyappa Layout								
	8th Cross Rd	1	38.10	5.50	0.15	31.43			
	4th Main Road	1	33.00	7.00	0.15	34.65			
	For Pathway								
	Ward No-03								
	S-LIG - 10,11	1	39.80	6.20	0.10	24.68			
	S-LIG - 08,09	1	24.20	6.70	0.10	16.21			
	S-LIG - 07	1	6.80	4.00	0.10	2.72			
	S-LIG - 06	1	35.50	7.00	0.10	24.85			
	S-LIG - 05	1	4.20	4.20	0.10	1.76			
	S-LIG - 03	1	39.60	4.00	0.10	15.84			
	S-LIG - 01	1	34.60	6.26	0.10	21.66			
	Near Nandini Parlour(Indian Sweets Bakery)	1	31.30	3.50	0.10	10.96			
	Bheema Blocks HIG - B - 2	1	41.40	5.00	0.10	21.11			
	SFS 208								
	15th Block	1	58.30	3.15	0.15	27.55			
	S-HIG 32	1	41.80	5.40	0.15	33.86			
	Opp To Annapurnashweri Catering	1	73.70	4.15	0.15	45.88			
	S-LIG 42								
	Beside Neha Praksha Hospital	1	48.50	3.40	0.15	24.74			
	SFS 208								
	2nd Main Road RHS	1	161.50	1.33	0.15	32.22			
	3rd Main Road LHS	1	28.30	1.00	0.15	4.25			
	4th Cross Rd RHS From United Residency Association	1	116.60	0.62	0.15	10.84			
	4th Cross Rd LHS From Dental Clinic	1	78.20	0.80	0.15	9.38			
	BMS Hostel Opp Road LHS	1	71.20	0.59	0.15	6.30			
	BMS Hostel Opp Road RHS	1	102.80	0.59	0.15	9.10			
	Urdhu School Surrounding	1	100.00	3.05	0.15	45.75			
	Ward No-04								
	7th B Cross Rd	1	24.00	1.00	0.15	3.60			
						5594.68	Cum		

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
				Upto 125%		5304.78	Cum	2596.02	13771278.26
				Above 125%		289.90	Cum	2596.02	752593.29
	Approved Amount	2596.02							
13	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density (V-III, P.No-24,I No-4.27A)of PWD SR 2021-22).								
	Asphalt Road								
	Cut Portion								
	Akshay Nagar								
	1st Cross Rd	1	67.60	1.00	0.23	15.55			
	Main Road From Sandeep Unnikrishan Rd	1	338.50	1.00	0.23	77.86			
	Tirumalanagara 1st Cross Rd	1	61.80	1.00	0.23	14.21			
	Escorts Colony								
	6th C Cross Rd	1	58.60	1.00	0.23	13.48			
	6th B Cross Rd	1	54.40	1.20	0.23	15.01			
	6th A Main Road	1	156.30	1.00	0.23	35.95			
	1st Cross Rd	1	208.70	1.00	0.23	48.00			
	7th A Main Rd From Dead End	1	238.20	1.00	0.23	54.79			
	Ramadasappa Garden								
	1st Cross Rd	1	266.80	1.00	0.23	61.36			
	Santhosh Nagara								
	2nd Cross Rd	1	159.60	1.00	0.23	36.71			
	Connecting Rd-1	1	25.00	1.00	0.23	5.75			
	Connecting Rd-2	1	24.30	1.00	0.23	5.59			
	6th Cross Rd	1	165.40	1.20	0.23	45.65			
	6th Cross Rd Continue	1	259.30	1.00	0.23	59.64			
	Cross rd-1	1	64.20	1.20	0.23	17.72			
	Cross rd-2	1	19.00	1.00	0.23	4.37			
	Helath Care Home Rd	1	49.00	1.00	0.23	11.27			
	Helath Care Home Rd Continue	1	79.50	1.00	0.23	18.29			
	Cross rd-3	1	21.30	1.00	0.23	4.90			
	Amruthnagar Care Rd	1	24.00	1.00	0.23	5.52			
	Cross rd-4	1	36.40	1.60	0.23	13.40			
	Cross rd-5	1	23.20	1.60	0.23	8.54			
	Sri Laasya Rd	1	24.20	1.60	0.23	8.91			
	Cross rd-6[Door 13]	1	24.80	1.60	0.23	9.13			
	Varaha Entreprises Rd	1	22.50	1.20	0.23	6.21			
	Manjunatha Nilaya Rd	1	19.00	1.60	0.23	6.99			
	7th Cross Rd	1	218.70	2.00	0.23	100.60			
	White Petal School Rd	1	27.20	1.00	0.23	6.26			
	Muneshwara Layout								
	11th Cross Rd	1	47.20	1.00	0.23	10.86			
	Left Side Roads								
	10th Cross Rd	1	46.00	1.00	0.23	10.58			
	9th Cross Rd	1	99.00	1.00	0.23	22.77			
	Right Side Roads								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	10th Cross Rd	1	170.00	1.00	0.23	39.10			
	4th Cross Rd	1	45.00	1.60	0.23	16.56			
	2nd Cross Rd From Dead End	1	44.20	1.60	0.23	16.27			
	1st Cross Rd	1	45.00	1.60	0.23	16.56			
	3rd Cross Rd	1	161.00	1.60	0.23	59.25			
	5th Cross rd	1	270.60	1.60	0.23	99.58			
	6th Cross Rd								
	3rd Cross Rd	1	23.30	1.00	0.23	5.36			
	4th Cross Rd	1	21.60	1.00	0.23	4.97			
	Veerasagara Main Rd								
	[Muneshwaara Layout]								
	6th Cross Rd	1	56.80	1.00	0.23	13.06			
	6th A Cross Rd	1	65.20	1.10	0.23	16.50			
	8th Main Cross Rd-2	1	36.30	1.00	0.23	8.35			
	9th Main Rd	1	109.60	1.60	0.23	40.33			
	10th Main Road	1	46.50	1.60	0.23	17.11			
	11th Main rd	1	53.40	1.60	0.23	19.65			
	Attur Village Rd	1	118.10	1.60	0.23	43.46			
	Attur Village Main Rd	1	92.10	1.60	0.23	33.89			
	Sri Sai Layout								
	Cross Rd-4	1	140.50	1.00	0.23	32.32			
	Chitra Layout								
	Harshitha Nilaya	1	74.20	1.20	0.23	20.48			
	5th cross rd Attur layout	1	26.80	1.40	0.23	8.63			
	Ward No-04								
	B-sector								
	6th B Main Road	1	52.00	1.00	0.23	11.96			
	9th Cross Rd	1	45.30	1.00	0.23	10.42			
	7th B Main Rd	1	180.00	1.00	0.23	41.40			
	Edge Correction								
	Akshyanagar								
	2nd cross road	2	63.50	0.90	0.23	26.29			
	3rd cross road	2	64.50	0.95	0.23	28.19			
	4th cross road	2	63.50	1.00	0.23	29.21			
	5th cross road	2	60.00	1.20	0.23	33.12			
	6th cross road	2	65.00	0.90	0.23	26.91			
	7th cross road	2	64.00	0.95	0.23	27.97			
	8th A main road	2	257.60	1.00	0.23	118.50			
	State Bank of India road	2	139.00	1.20	0.23	76.73			
	2nd A main road	2	125.60	0.90	0.23	52.00			
	Attur Layout 2nd main road	2	341.90	0.95	0.23	149.41			
	Attur Layout 3rd main road	2	421.60	1.00	0.23	193.94			
	Attur Layout 4th main road (From End)	2	383.40	1.20	0.23	211.64			
	Attur Layout 5th main road	2	373.60	0.90	0.23	154.67			
	Attur Layout 6th main road (From End)	2	321.30	0.95	0.23	140.41			
	Attur Layout 7th main road	2	323.90	1.00	0.23	148.99			
	Attur Layout 8th main road	2	324.20	1.20	0.23	178.96			
	Attur Layout 1st cross road	2	226.20	0.55	0.23	57.23			
	Attur Layout 2nd cross road	2	255.10	0.50	0.23	58.67			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Attur Layout 3rd cross road (From End)	2	285.70	0.49	0.23	64.40			
	Attur Layout 4th cross road	2	263.70	0.55	0.23	66.72			
	Under 11th cross Road (Muneshwara Layout)								
	1st Cross Road	2	33.00	0.55	0.23	8.35			
	2nd Cross Road	2	34.60	0.60	0.23	9.55			
	3rd Cross Road	2	38.20	0.45	0.23	7.91			
	Akshay Nagar								
	1st Cross Rd	2	67.60	0.50	0.23	15.55			
	Main Road From Sandeep Unnikrishan Rd	2	338.50	0.50	0.23	77.86			
	Tirumalanagara 1st Cross Rd	2	61.80	0.50	0.23	14.21			
	Escorts Colony								
	6th C Cross Rd	2	58.60	0.50	0.23	13.48			
	6th B Cross Rd	2	54.40	0.50	0.23	12.51			
	6th A Main Road	2	156.30	0.50	0.23	35.95			
	1st Cross Rd	2	208.70	0.50	0.23	48.00			
	7th A Main Rd From Dead End	2	238.20	0.50	0.23	54.79			
	Ramadasappa Garden								
	1st Cross Rd	2	266.80	0.50	0.23	61.36			
	Santhosh Nagara								
	2nd Cross Rd	2	159.60	0.50	0.23	36.71			
	Connecting Rd-1	2	25.00	0.50	0.23	5.75			
	Connecting Rd-2	2	24.30	0.50	0.23	5.59			
	6th Cross Rd	2	165.40	0.50	0.23	38.04			
	6th Cross Rd Continue	2	259.30	0.60	0.23	71.57			
	Cross rd-1	2	64.20	0.50	0.23	14.77			
	Cross rd-2	2	19.00	0.35	0.23	3.06			
	Helath Care Home Rd	2	49.00	0.50	0.23	11.27			
	Helath Care Home Rd Continue	2	79.50	0.50	0.23	18.29			
	Cross rd-3	2	21.30	0.50	0.23	4.90			
	Amruthnagar Care Rd	2	24.00	0.50	0.23	5.52			
	Cross rd-4	2	36.40	0.50	0.23	8.37			
	Cross rd-5	2	23.20	0.40	0.23	4.27			
	Sri Laasya Rd	2	24.20	0.50	0.23	5.57			
	Cross rd-6[Door 13]	2	24.80	0.40	0.23	4.56			
	Varaha Entreprises Rd	2	22.50	0.40	0.23	4.14			
	Manjunatha Nilaya Rd	2	19.00	0.50	0.23	4.37			
	7th Cross Rd	2	218.70	0.50	0.23	50.30			
	White Petal School Rd	2	27.20	0.50	0.23	6.26			
	Muneshwara Layout								
	11th Cross Rd	2	47.20	0.50	0.23	10.86			
	Left Side Roads								
	10th Cross Rd	2	46.00	0.50	0.23	10.58			
	9th Cross Rd	2	99.00	0.50	0.23	22.77			
	Right Side Roads								
	10th Cross Rd	2	170.00	0.50	0.23	39.10			
	4th Cross Rd	2	45.00	0.50	0.23	10.35			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	2nd Cross Rd From Dead End	2	44.20	0.50	0.23	10.17			
	1st Cross Rd	2	45.00	0.50	0.23	10.35			
	3rd Cross Rd	2	161.00	0.50	0.23	37.03			
	5th Cross rd	2	270.60	0.50	0.23	62.24			
	6th Cross Rd								
	3rd Cross Rd	2	23.30	1.00	0.23	10.72			
	4th Cross Rd	2	21.60	1.00	0.23	9.94			
	Veerasagara Main Rd								
	[Muneshwaara Layout]								
	6th Cross Rd	2	56.80	0.65	0.23	16.98			
	6th A Cross Rd	2	65.20	0.50	0.23	15.00			
	8th Main Cross Rd-2	2	36.30	0.50	0.23	8.35			
	9th Main Rd	2	109.60	0.50	0.23	25.21			
	10th Main Road	2	46.50	0.40	0.23	8.56			
	11th Main rd	2	53.40	0.40	0.23	9.83			
	Attur Village Rd	2	118.10	0.50	0.23	27.16			
	Attur Village Main Rd	2	92.10	0.50	0.23	21.18			
	Sri Sai Layout								
	Cross Rd-4	2	140.50	0.50	0.23	32.32			
	Chitra Layout								
	Harshitha Nilaya	2	74.20	0.50	0.23	17.07			
	5th cross rd Attur layout	2	26.80	0.48	0.23	5.92			
	SFS 407								
	1st A Main Road From Dead End	2	98.80	1.00	0.23	45.45			
	1st Cross Rd	2	42.00	1.00	0.23	19.32			
	5th Phase 2nd Main Rd	2	119.10	1.10	0.23	60.26			
	Santhosh Nagara								
	1st Cross Rd	2	47.50	1.00	0.23	21.85			
	1st A Cross Rd	2	102.70	1.30	0.23	61.41			
	Mamatha Nilaya Rd	2	12.50	1.30	0.23	7.48			
	1st A Cross Rd Continue	2	33.10	1.30	0.23	19.79			
	Attur Layout								
	1st Cross Rd From 9th Main Rd	2	22.10	1.30	0.23	13.22			
	10th Main Road	2	184.70	1.30	0.23	110.45			
	4th Main Road[SFS 407]	2	128.10	1.05	0.23	61.87			
	2nd Main Rd[SFS 208]	2	211.20	1.50	0.23	145.73			
	1st Main Road[SFS 208]	2	166.00	1.50	0.23	114.54			
	1st Main Road Continue	2	145.10	1.50	0.23	100.12			
	1st Main Rd[25 to 38] SFS 208	2	158.10	1.50	0.23	109.09			
	SFS 208	2	200.00	1.50	0.23	138.00			
	SFS Cross Rd	2	300.00	1.60	0.23	220.80			
	SFS Cross Rd	2	265.00	1.50	0.23	182.85			
	Ward No-04								
	10th B Main B Sector	2	35.20	0.55	0.23	8.91			
	2nd B Main B Sector	2	72.10	0.60	0.23	19.90			
	11th B Cross Road B Sector	2	76.20	0.45	0.23	15.77			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	From Sandeep Unnikrishnan Main Road, 4th B Cross Road	2	137.30	0.55	0.23	34.74			
	th B Cross Road Continued	2	16.20	0.60	0.23	4.47			
	From 3rd B Cross Road, 7th B Main	2	67.30	0.60	0.20	15.76			
	B-sector								
	6th B Main Road	2	52.00	0.50	0.23	11.96			
	9th Cross Rd	2	45.30	0.55	0.23	11.46			
	7th B Main Rd	2	180.00	0.50	0.23	41.40			
	New Asphalt Road								
	Santhosh Nagara								
	1st Cross Rd	1	164.50	4.65	0.23	175.93			
	4th Cross Rd	1	148.10	4.80	0.23	163.50			
	Tharaman Sharma Rd	1	33.20	4.14	0.23	31.61			
	9th B Cross Rd	1	36.00	3.93	0.23	32.50			
	Muneshwara Layout								
	Right Side Roads								
	9th Cross Rd	1	170.00	4.76	0.23	186.12			
	4th Cross Rd	1	172.40	5.22	0.23	206.98			
	1st Cross Rd	1	27.50	4.39	0.23	27.77			
	2nd Cross Rd	1	25.00	5.00	0.23	28.75			
	Veerasagara Main Rd								
	[Muneshwaara Layout]								
	6th B Cross Rd	1	116.50	4.48	0.23	120.04			
	5th A Cross Rd	1	92.30	5.50	0.23	116.76			
	6th Cross Rd	1	133.00	5.05	0.23	154.48			
	Sri Sai Layout								
	Cross Rd-1	1	109.00	7.42	0.23	186.02			
	Cross RD-2	1	30.00	8.40	0.23	57.96			
	Cross RD-3	1	131.00	6.03	0.23	181.68			
	Chitra Layout								
	3rd Cross Rd	1	150.00	4.21	0.23	145.25			
	Santhosh Nagara								
	1st Main Road	1	19.00	2.10	0.23	9.18			
	Vijaya Bank Layout								
	1st Cross Rd	1	58.50	5.30	0.23	71.31			
	2nd Cross Rd	1	31.30	5.60	0.23	40.31			
	3rd Cross Rd	1	63.15	6.25	0.23	90.78			
	Ayyappa Layout								
	8th Cross Rd	1	38.10	5.50	0.23	48.20			
	4th Main Road	1	33.00	7.00	0.23	53.13			
						7984.29	**Cum**		
				Upto 125%		**7011.25**	**Cum**	**2648.00**	**18565805.45**
				Above 125%		**973.04**	**Cum**	**2648.00**	**2576621.64**
	Approved Amount	**2648.00**							
14	Providing and applying primer coat with SS1 grade Bitumen Emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.90 kg per m2 using mechanical means. (V-III, P.No-29,I No-5.1(i) of PWD SR 2021-22).								
	Asphalt Road								
	Cut Portion								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Akshay Nagar								
	1st Cross Rd	1	67.60	1.00		67.60			
	Main Road From Sandeep Unnikrishan Rd	1	338.50	1.00		338.50			
	Tirumalanagara 1st Cross Rd	1	61.80	1.00		61.80			
	Escorts Colony								
	6th C Cross Rd	1	58.60	1.00		58.60			
	6th B Cross Rd	1	54.40	1.20		65.28			
	6th A Main Road	1	156.30	1.00		156.30			
	1st Cross Rd	1	208.70	1.00		208.70			
	7th A Main Rd From Dead End	1	238.20	1.00		238.20			
	Ramadasappa Garden								
	1st Cross Rd	1	266.80	1.00		266.80			
	Santhosh Nagara								
	2nd Cross Rd	1	159.60	1.00		159.60			
	Connecting Rd-1	1	25.00	1.00		25.00			
	Connecting Rd-2	1	24.30	1.00		24.30			
	6th Cross Rd	1	165.40	1.20		198.48			
	6th Cross Rd Continue	1	259.30	1.00		259.30			
	Cross rd-1	1	64.20	1.20		77.04			
	Cross rd-2	1	19.00	1.00		19.00			
	Helath Care Home Rd	1	49.00	1.00		49.00			
	Helath Care Home Rd Continue	1	79.50	1.00		79.50			
	Cross rd-3	1	21.30	1.00		21.30			
	Amruthnagar Care Rd	1	24.00	1.00		24.00			
	Cross rd-4	1	36.40	1.60		58.24			
	Cross rd-5	1	23.20	1.60		37.12			
	Sri Laasya Rd	1	24.20	1.60		38.72			
	Cross rd-6[Door 13]	1	24.80	1.60		39.68			
	Varaha Entreprises Rd	1	22.50	1.20		27.00			
	Manjunatha Nilaya Rd	1	19.00	1.60		30.40			
	7th Cross Rd	1	218.70	2.00		437.40			
	White Petal School Rd	1	27.20	1.00		27.20			
	Muneshwara Layout								
	11th Cross Rd	1	47.20	1.00		47.20			
	Left Side Roads								
	10th Cross Rd	1	46.00	1.00		46.00			
	9th Cross Rd	1	99.00	1.00		99.00			
	Right Side Roads								
	10th Cross Rd	1	170.00	1.00		170.00			
	4th Cross Rd	1	45.00	1.60		72.00			
	2nd Cross Rd From Dead End	1	44.20	1.60		70.72			
	1st Cross Rd	1	45.00	1.60		72.00			
	3rd Cross Rd	1	161.00	1.60		257.60			
	5th Cross rd	1	270.60	1.60		432.96			
	6th Cross Rd								
	3rd Cross Rd	1	23.30	1.00		23.30			
	4th Cross Rd	1	21.60	1.00		21.60			
	Veerasagara Main Rd								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	[Muneshwaara Layout]								
	6th Cross Rd	1	56.80	1.00		56.80			
	6th A Cross Rd	1	65.20	1.10		71.72			
	8th Main Cross Rd-2	1	36.30	1.00		36.30			
	9th Main Rd	1	109.60	1.60		175.36			
	10th Main Road	1	46.50	1.60		74.40			
	11th Main rd	1	53.40	1.60		85.44			
	Attur Village Rd	1	118.10	1.60		188.96			
	Attur Village Main Rd	1	92.10	1.60		147.36			
	Sri Sai Layout								
	Cross Rd-4	1	140.50	1.00		140.50			
	Chitra Layout								
	Harshitha Nilaya	1	74.20	1.20		89.04			
	5th cross rd Attur layout	1	26.80	1.40		37.52			
	Ward No-04								
	B-sector								
	6th B Main Road	1	52.00	1.00		52.00			
	9th Cross Rd	1	45.30	1.00		45.30			
	7th B Main Rd	1	180.00	1.00		180.00			
	Edge Correction								
	Akshyanagar								
	2nd cross road	2	63.50	0.90		114.30			
	3rd cross road	2	64.50	0.95		122.55			
	4th cross road	2	63.50	1.00		127.00			
	5th cross road	2	60.00	1.20		144.00			
	6th cross road	2	65.00	0.90		117.00			
	7th cross road	2	64.00	0.95		121.60			
	8th A main road	2	257.60	1.00		515.20			
	State Bank of India road	2	139.00	1.20		333.60			
	2nd A main road	2	125.60	0.90		226.08			
	Attur Layout 2nd main road	2	341.90	0.95		649.61			
	Attur Layout 3rd main road	2	421.60	1.00		843.20			
	Attur Layout 4th main road (From End)	2	383.40	1.20		920.16			
	Attur Layout 5th main road	2	373.60	0.90		672.48			
	Attur Layout 6th main road (From End)	2	321.30	0.95		610.47			
	Attur Layout 7th main road	2	323.90	1.00		647.80			
	Attur Layout 8th main road	2	324.20	1.20		778.08			
	Attur Layout 1st cross road	2	226.20	0.55		248.82			
	Attur Layout 2nd cross road	2	255.10	0.50		255.10			
	Attur Layout 3rd cross road (From End)	2	285.70	0.49		279.99			
	Attur Layout 4th cross road	2	263.70	0.55		290.07			
	Under 11th cross Road (Muneshwara Layout)								
	1st Cross Road	2	33.00	0.55		36.30			
	2nd Cross Road	2	34.60	0.60		41.52			
	3rd Cross Road	2	38.20	0.45		34.38			
	Akshay Nagar								
	1st Cross Rd	2	67.60	0.50		67.60			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Main Road From Sandeep Unnikrishan Rd	2	338.50	0.50		338.50			
	Tirumalanagara 1st Cross Rd	2	61.80	0.50		61.80			
	Escorts Colony								
	6th C Cross Rd	2	58.60	0.50		58.60			
	6th B Cross Rd	2	54.40	0.50		54.40			
	6th A Main Road	2	156.30	0.50		156.30			
	1st Cross Rd	2	208.70	0.50		208.70			
	7th A Main Rd From Dead End	2	238.20	0.50		238.20			
	Ramadasappa Garden								
	1st Cross Rd	2	266.80	0.50		266.80			
	Santhosh Nagara								
	2nd Cross Rd	2	159.60	0.50		159.60			
	Connecting Rd-1	2	25.00	0.50		25.00			
	Connecting Rd-2	2	24.30	0.50		24.30			
	6th Cross Rd	2	165.40	0.50		165.40			
	6th Cross Rd Continue	2	259.30	0.50		259.30			
	Cross rd-1	2	64.20	0.50		64.20			
	Cross rd-2	2	19.00	0.50		19.00			
	Helath Care Home Rd	2	49.00	0.50		49.00			
	Helath Care Home Rd Continue	2	79.50	0.50		79.50			
	Cross rd-3	2	21.30	0.50		21.30			
	Amruthnagar Care Rd	2	24.00	0.50		24.00			
	Cross rd-4	2	36.40	0.50		36.40			
	Cross rd-5	2	23.20	0.40		18.56			
	Sri Laasya Rd	2	24.20	0.50		24.20			
	Cross rd-6[Door 13]	2	24.80	0.40		19.84			
	Varaha Entreprises Rd	2	22.50	0.40		18.00			
	Manjunatha Nilaya Rd	2	19.00	0.50		19.00			
	7th Cross Rd	2	218.70	0.50		218.70			
	White Petal School Rd	2	27.20	0.50		27.20			
	Muneshwara Layout								
	11th Cross Rd	2	47.20	0.50		47.20			
	Left Side Roads								
	10th Cross Rd	2	46.00	0.50		46.00			
	9th Cross Rd	2	99.00	0.50		99.00			
	Right Side Roads								
	10th Cross Rd	2	170.00	0.50		170.00			
	4th Cross Rd	2	45.00	0.50		45.00			
	2nd Cross Rd From Dead End	2	44.20	0.50		44.20			
	1st Cross Rd	2	45.00	0.50		45.00			
	3rd Cross Rd	2	161.00	0.50		161.00			
	5th Cross rd	2	270.60	0.50		270.60			
	6th Cross Rd								
	3rd Cross Rd	2	23.30	1.00		46.60			
	4th Cross Rd	2	21.60	1.00		43.20			
	Veerasagara Main Rd								
	[Muneshwaara Layout]								
	6th Cross Rd	2	56.80	0.65		73.84			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	6th A Cross Rd	2	65.20	0.50		65.20			
	8th Main Cross Rd-2	2	36.30	0.50		36.30			
	9th Main Rd	2	109.60	0.50		109.60			
	10th Main Road	2	46.50	0.40		37.20			
	11th Main rd	2	53.40	0.40		42.72			
	Attur Village Rd	2	118.10	0.50		118.10			
	Attur Village Main Rd	2	92.10	0.50		92.10			
	Sri Sai Layout								
	Cross Rd-4	2	140.50	0.50		140.50			
	Chitra Layout								
	Harshitha Nilaya	2	74.20	0.50		74.20			
	5th cross rd Attur layout	2	26.80	0.48		25.73			
	SFS 407								
	1st A Main Road From Dead End	2	98.80	1.00		197.60			
	1st Cross Rd	2	42.00	1.00		84.00			
	5th Phase 2nd Main Rd	2	119.10	1.10		262.02			
	Santhosh Nagara								
	1st Cross Rd	2	47.50	1.00		95.00			
	1st A Cross Rd	2	102.70	1.30		267.02			
	Mamatha Nilaya Rd	2	12.50	1.30		32.50			
	1st A Cross Rd Continue	2	33.10	1.30		86.06			
	Attur Layout								
	1st Cross Rd From 9th Main Rd	2	22.10	1.30		57.46			
	10th Main Road	2	184.70	1.30		480.22			
	4th Main Road[SFS 407]	2	128.10	1.05		269.01			
	2nd Main Rd[SFS 208]	2	211.20	1.50		633.60			
	1st Main Road[SFS 208]	2	166.00	1.50		498.00			
	1st Main Road Continue	2	145.10	1.50		435.30			
	1st Main Rd[25 to 38] SFS 208	2	158.10	1.50		474.30			
	SFS 208	2	200.00	1.50		600.00			
	SFS Cross Rd	2	300.00	1.60		960.00			
	SFS Cross Rd	2	265.00	1.50		795.00			
	Ward No-04								
	10th B Main B Sector	2	35.20	0.55		38.72			
	2nd B Main B Sector	2	72.10	0.60		86.52			
	11th B Cross Road B Sector	2	76.20	0.45		68.58			
	From Sandeep Unnikrishnan Main Road, 4th B Cross Road	2	137.30	0.55		151.03			
	th B Cross Road Continued	2	16.20	0.60		19.44			
	From 3rd B Cross Road, 7th B Main	2	67.30	0.60		68.51			
	B-sector								
	6th B Main Road	2	52.00	0.50		52.00			
	9th Cross Rd	2	45.30	0.55		49.83			
	7th B Main Rd	2	180.00	0.50		180.00			
	New Asphalt Road								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Santhosh Nagara								
	1st Cross Rd	1	164.50	4.65		764.93			
	4th Cross Rd	1	148.10	4.80		710.88			
	Tharaman Sharma Rd	1	33.20	4.14		137.45			
	9th B Cross Rd	1	36.00	3.93		141.30			
	Muneshwara Layout								
	Right Side Roads								
	9th Cross Rd	1	170.00	4.76		809.20			
	4th Cross Rd	1	172.40	5.22		899.93			
	1st Cross Rd	1	27.50	4.39		120.73			
	2nd Cross Rd	1	25.00	5.00		125.00			
	Veerasagara Main Rd								
	[Muneshwaara Layout]								
	6th B Cross Rd	1	116.50	4.48		521.92			
	5th A Cross Rd	1	92.30	5.50		507.65			
	6th Cross Rd	1	133.00	5.05		671.65			
	Sri Sai Layout								
	Cross Rd-1	1	109.00	7.42		808.78			
	Cross RD-2	1	30.00	8.40		252.00			
	Cross RD-3	1	131.00	6.03		789.93			
	Chitra Layout								
	3rd Cross Rd	1	150.00	4.21		631.50			
	Santhosh Nagara								
	1st Main Road	1	19.00	2.10		39.90			
	Vijaya Bank Layout								
	1st Cross Rd	1	58.50	5.30		310.05			
	2nd Cross Rd	1	31.30	5.60		175.28			
	3rd Cross Rd	1	63.15	6.25		394.69			
	Ayyappa Layout								
	8th Cross Rd	1	38.10	5.50		209.55			
	4th Main Road	1	33.00	7.00		231.00			
						34668.16	Sqm	48.67	1687243.12
	Approved Amount	48.67							
15	Providing and applying tack coat with RS1 Bituminous Emulsion using emulsion pressure distributor at the rate of 0.20 kg/m2 on the prepared bituminous surface cleaned with mechanical broom.(V-III, P.No-29,I No-5.3(i) of PWD SR 2021-22).								
	Asphalt Road								
	Akshyanagar								
	2nd cross road	1	63.50	6.10		387.35			
	3rd cross road	1	64.50	6.10		393.45			
	4th cross road	1	63.50	5.90		374.65			
	5th cross road	1	60.00	6.70		402.00			
	6th cross road	1	65.00	6.00		390.00			
	7th cross road	1	64.00	6.20		396.80			
	8th A main road	1	257.60	6.45		1661.52			
	State Bank of India road	1	139.00	6.15		854.85			
	2nd A main road	1	125.60	3.95		496.12			
	Attur Layout 2nd main road	1	341.90	4.05		1384.70			
	Attur Layout 3rd main road	1	421.60	3.70		1559.92			
	Attur Layout 4th main road (From End)	1	383.40	3.95		1514.43			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Attur Layout 5th main road	1	373.60	4.70		1755.92			
	Attur Layout 6th main road (From End)	1	321.30	3.70		1188.81			
	Attur Layout 7th main road	1	323.90	4.10		1327.99			
	Attur Layout 8th main road	1	324.20	4.30		1394.06			
	Attur Layout 1st cross road	1	226.20	5.90		1334.58			
	Attur Layout 2nd cross road	1	255.10	5.70		1454.07			
	Attur Layout 3rd cross road (From End)	1	285.70	5.90		1685.63			
	Attur Layout 4th cross road	1	263.70	5.80		1529.46			
	Under 11th cross Road (Muneshwara Layout)								
	1st Cross Road	1	33.00	4.70		155.10			
	2nd Cross Road	1	34.60	4.85		167.81			
	3rd Cross Road	1	38.20	5.20		198.64			
	1st Cross Rd	1	67.60	6.57		444.13			
	Main Road From Sandeep Unnikrishan Rd	1	338.50	6.47		2188.40			
	Tirumalanagara 1st Cross Rd	1	61.80	6.48		400.46			
	Escorts Colony								
	6th C Cross Rd	1	58.60	4.33		253.74			
	6th B Cross Rd	1	54.40	4.40		239.36			
	6th A Main Road	1	156.30	4.68		731.48			
	1st Cross Rd	1	208.70	6.82		1423.33			
	7th A Main Rd From Dead End	1	238.20	4.85		1155.27			
	Ramadasappa Garden								
	1st Cross Rd	1	266.80	4.42		1179.26			
	Santhosh Nagara								
	1st Cross Rd	1	164.50	4.65		764.93			
	2nd Cross Rd	1	159.60	3.99		637.12			
	4th Cross Rd	1	148.10	4.80		710.88			
	Connecting Rd-1	1	25.00	4.45		111.25			
	Connecting Rd-2	1	24.30	4.95		120.29			
	6th Cross Rd	1	165.40	5.41		894.81			
	6th Cross Rd Continue	1	259.30	5.33		1380.77			
	Cross rd-1	1	64.20	4.82		309.44			
	Cross rd-2	1	19.00	4.30		81.70			
	Helath Care Home Rd	1	49.00	5.36		262.64			
	Helath Care Home Rd Continue	1	79.50	5.15		409.43			
	Cross rd-3	1	21.30	3.30		70.29			
	Amruthnagar Care Rd	1	24.00	3.45		82.80			
	Cross rd-4	1	36.40	4.36		158.70			
	Cross rd-5	1	23.20	3.85		89.32			
	Sri Laasya Rd	1	24.20	4.40		106.48			
	Cross rd-6[Door 13]	1	24.80	4.85		120.28			
	Varaha Entreprises Rd	1	22.50	4.55		102.38			
	Manjunatha Nilaya Rd	1	19.00	5.00		95.00			
	7th Cross Rd	1	218.70	4.10		896.67			
	White Petal School Rd	1	27.20	2.75		74.80			
	Tharaman Sharma Rd	1	33.20	4.14		137.45			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	9th B Cross Rd	1	36.00	3.93		141.30			
	Muneshwara Layout								
	11th Cross Rd	1	47.20	5.60		264.32			
	Left Side Roads								
	10th Cross Rd	1	46.00	4.42		203.32			
	9th Cross Rd	1	99.00	4.98		493.02			
	Right Side Roads								
	10th Cross Rd	1	170.00	4.86		826.20			
	9th Cross Rd	1	170.00	4.76		809.20			
	4th Cross Rd	1	45.00	5.88		264.60			
	2nd Cross Rd From Dead End	1	44.20	4.64		205.09			
	1st Cross Rd	1	45.00	4.80		216.00			
	3rd Cross Rd	1	161.00	6.55		1054.55			
	4th Cross Rd	1	172.40	5.22		899.93			
	5th Cross rd	1	270.60	5.33		1440.95			
	6th Cross Rd								
	1st Cross Rd	1	27.50	4.39		120.73			
	2nd Cross Rd	1	25.00	5.00		125.00			
	3rd Cross Rd	1	23.30	5.15		120.00			
	4th Cross Rd	1	21.60	4.89		105.62			
	Veerasagara Main Rd								
	[Muneshwaara Layout]								
	6th Cross Rd	1	56.80	3.40		193.12			
	6th B Cross Rd	1	116.50	4.48		521.92			
	6th A Cross Rd	1	65.20	4.47		291.44			
	5th A Cross Rd	1	92.30	5.50		507.65			
	6th Cross Rd	1	133.00	5.05		671.65			
	8th Main Cross Rd-2	1	36.30	6.74		244.66			
	9th Main Rd	1	109.60	4.35		476.76			
	10th Main Road	1	46.50	5.84		271.56			
	11th Main rd	1	53.40	5.27		281.42			
	Attur Village Rd	1	118.10	5.99		707.42			
	Attur Village Main Rd	1	92.10	6.68		615.23			
	Sri Sai Layout								
	Cross Rd-1	1	109.00	7.42		808.78			
	Cross RD-2	1	30.00	8.40		252.00			
	Cross RD-3	1	131.00	6.03		789.93			
	Cross Rd-4	1	140.50	6.62		929.41			
	Chitra Layout								
	3rd Cross Rd	1	150.00	4.21		631.50			
	Harshitha Nilaya	1	74.20	3.86		286.41			
	5th cross rd Attur layout	1	26.80	4.35		116.58			
	SFS 407								
	1st A Main Road From Dead End	1	98.80	7.90		780.52			
	1st Cross Rd	1	42.00	5.80		243.60			
	5th Phase 2nd Main Rd	1	119.10	5.45		649.10			
	Santhosh Nagara								
	1st Main Road	1	19.00	2.10		39.90			
	1st Cross Rd	1	47.50	4.45		211.38			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	1st A Cross Rd	1	102.70	5.76		591.55			
	Mamatha Nilaya Rd	1	12.50	4.10		51.25			
	1st A Cross Rd Continue	1	33.10	6.20		205.22			
	Attur Layout								
	1st Cross Rd From 9th Main Rd	1	22.10	5.50		121.55			
	10th Main Road	1	184.70	3.91		722.18			
	Vijaya Bank Layout								
	1st Cross Rd	1	58.50	5.30		310.05			
	2nd Cross Rd	1	31.30	5.60		175.28			
	3rd Cross Rd	1	63.15	6.25		394.69			
	Ayyappa Layout								
	8th Cross Rd	1	38.10	5.50		209.55			
	4th Main Road	1	33.00	7.00		231.00			
	4th Main Road[SFS 407]	1	128.10	9.60		1229.76			
	2nd Main Rd[SFS 208]	1	211.20	7.48		1579.78			
	1st Main Road[SFS 208]	1	166.00	8.95		1485.70			
	1st Main Road Continue	1	145.10	9.10		1320.41			
	1st Main Rd[25 to 38] SFS 208	1	158.10	8.52		1347.01			
	SFS 208	1	200.00	7.00		1400.00			
	SFS Cross Rd	1	300.00	7.00		2100.00			
	SFS Cross Rd	1	265.00	7.00		1855.00			
	Ward No-04								
	10th B Main B Sector	1	35.20	6.00		211.20			
	2nd B Main B Sector	1	72.10	6.30		454.23			
	11th B Cross Road B Sector	1	76.20	5.80		441.96			
	From Sandeep Unnikrishnan Main Road, 4th B Cross Road	1	137.30	6.65		913.05			
	th B Cross Road Continued	1	16.20	7.12		115.34			
	From 3rd B Cross Road, 7th B Main	1	67.30	6.30		423.99			
	Deduction	-1	960.68			-960.68			
	B-sector								
	6th B Main Road	1	52.00	5.86		304.72			
	9th Cross Rd	1	45.30	6.98		316.19			
	7th B Main Rd	1	180.00	6.10		1097.28			
						74099.72	**Sqm**	**13.27**	**983539.99**
	Approved Amount	13.27							
16	Providing and laying **Dense Graded Bituminous Macadam** with 40/60 TPH capacity HMP using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 505 complete in all respects. (V-III, P.No-33,I No-5.12C of PWD SR 2021-22).								
	Asphalt Road								
	Cut Portion								
	Akshay Nagar								
	1st Cross Rd	1	67.60	1.00	0.05	3.38			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Main Road From Sandeep Unnikrishan Rd	1	338.50	1.00	0.05	16.93			
	Tirumalanagara 1st Cross Rd	1	61.80	1.00	0.05	3.09			
	Escorts Colony								
	6th C Cross Rd	1	58.60	1.00	0.05	2.93			
	6th B Cross Rd	1	54.40	1.20	0.05	3.26			
	6th A Main Road	1	156.30	1.00	0.05	7.82			
	1st Cross Rd	1	208.70	1.00	0.05	10.44			
	7th A Main Rd From Dead End	1	238.20	1.00	0.05	11.91			
	Ramadasappa Garden								
	1st Cross Rd	1	266.80	1.00	0.05	13.34			
	Santhosh Nagara								
	2nd Cross Rd	1	159.60	1.00	0.05	7.98			
	Connecting Rd-1	1	25.00	1.00	0.05	1.25			
	Connecting Rd-2	1	24.30	1.00	0.05	1.22			
	6th Cross Rd	1	165.40	1.20	0.05	9.92			
	6th Cross Rd Continue	1	259.30	1.00	0.05	12.97			
	Cross rd-1	1	64.20	1.20	0.05	3.85			
	Cross rd-2	1	19.00	1.00	0.05	0.95			
	Helath Care Home Rd	1	49.00	1.00	0.05	2.45			
	Helath Care Home Rd Continue	1	79.50	1.00	0.05	3.98			
	Cross rd-3	1	21.30	1.00	0.05	1.07			
	Amruthnagar Care Rd	1	24.00	1.00	0.05	1.20			
	Cross rd-4	1	36.40	1.60	0.05	2.91			
	Cross rd-5	1	23.20	1.60	0.05	1.86			
	Sri Laasya Rd	1	24.20	1.60	0.05	1.94			
	Cross rd-6[Door 13]	1	24.80	1.60	0.05	1.98			
	Varaha Entreprises Rd	1	22.50	1.20	0.05	1.35			
	Manjunatha Nilaya Rd	1	19.00	1.60	0.05	1.52			
	7th Cross Rd	1	218.70	2.00	0.05	21.87			
	White Petal School Rd	1	27.20	1.00	0.05	1.36			
	Muneshwara Layout								
	11th Cross Rd	1	47.20	1.00	0.05	2.36			
	Left Side Roads								
	10th Cross Rd	1	46.00	1.00	0.05	2.30			
	9th Cross Rd	1	99.00	1.00	0.05	4.95			
	Right Side Roads								
	10th Cross Rd	1	170.00	1.00	0.05	8.50			
	4th Cross Rd	1	45.00	1.60	0.05	3.60			
	2nd Cross Rd From Dead End	1	44.20	1.60	0.05	3.54			
	1st Cross Rd	1	45.00	1.60	0.05	3.60			
	3rd Cross Rd	1	161.00	1.60	0.05	12.88			
	5th Cross rd	1	270.60	1.60	0.05	21.65			
	6th Cross Rd								
	3rd Cross Rd	1	23.30	1.00	0.05	1.17			
	4th Cross Rd	1	21.60	1.00	0.05	1.08			
	Veerasagara Main Rd								
	[Muneshwaara Layout]								
	6th Cross Rd	1	56.80	1.00	0.05	2.84			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	6th A Cross Rd	1	65.20	1.10	0.05	3.59			
	8th Main Cross Rd-2	1	36.30	1.00	0.05	1.82			
	9th Main Rd	1	109.60	1.60	0.05	8.77			
	10th Main Road	1	46.50	1.60	0.05	3.72			
	11th Main rd	1	53.40	1.60	0.05	4.27			
	Attur Village Rd	1	118.10	1.60	0.05	9.45			
	Attur Village Main Rd	1	92.10	1.60	0.05	7.37			
	Sri Sai Layout								
	Cross Rd-4	1	140.50	1.00	0.05	7.03			
	Chitra Layout								
	Harshitha Nilaya	1	74.20	1.20	0.05	4.45			
	5th cross rd Attur layout	1	26.80	1.40	0.05	1.88			
	Ward No-04								
	B-sector								
	6th B Main Road	1	52.00	1.00	0.05	2.60			
	9th Cross Rd	1	45.30	1.00	0.05	2.27			
	7th B Main Rd	1	180.00	1.00	0.05	9.00			
	Edge Correction								
	Akshyanagar								
	2nd cross road	2	63.50	0.90	0.05	5.72			
	3rd cross road	2	64.50	0.95	0.05	6.13			
	4th cross road	2	63.50	1.00	0.05	6.35			
	5th cross road	2	60.00	1.20	0.05	7.20			
	6th cross road	2	65.00	0.90	0.05	5.85			
	7th cross road	2	64.00	0.95	0.05	6.08			
	8th A main road	2	257.60	1.00	0.05	25.76			
	State Bank of India road	2	139.00	1.20	0.05	16.68			
	2nd A main road	2	125.60	0.90	0.05	11.30			
	Attur Layout 2nd main road	2	341.90	0.95	0.05	32.48			
	Attur Layout 3rd main road	2	421.60	1.00	0.05	42.16			
	Attur Layout 4th main road (From End)	2	383.40	1.20	0.05	46.01			
	Attur Layout 5th main road	2	373.60	0.90	0.05	33.62			
	Attur Layout 6th main road (From End)	2	321.30	0.95	0.05	30.52			
	Attur Layout 7th main road	2	323.90	1.00	0.05	32.39			
	Attur Layout 8th main road	2	324.20	1.20	0.05	38.90			
	Attur Layout 1st cross road	2	226.20	0.55	0.05	12.44			
	Attur Layout 2nd cross road	2	255.10	0.50	0.05	12.76			
	Attur Layout 3rd cross road (From End)	2	285.70	0.49	0.05	14.00			
	Attur Layout 4th cross road	2	263.70	0.55	0.05	14.50			
	Under 11th cross Road (Muneshwara Layout)								
	1st Cross Road	2	33.00	0.55	0.05	1.82			
	2nd Cross Road	2	34.60	0.60	0.05	2.08			
	3rd Cross Road	2	38.20	0.45	0.05	1.72			
	Akshay Nagar								
	1st Cross Rd	2	67.60	0.50	0.05	3.38			
	Main Road From Sandeep Unnikrishan Rd	2	338.50	0.50	0.05	16.93			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Tirumalanagara 1st Cross Rd	2	61.80	0.50	0.05	3.09			
	Escorts Colony								
	6th C Cross Rd	2	58.60	0.50	0.05	2.93			
	6th B Cross Rd	2	54.40	0.50	0.05	2.72			
	6th A Main Road	2	156.30	0.50	0.05	7.82			
	1st Cross Rd	2	208.70	0.50	0.05	10.44			
	7th A Main Rd From Dead End	2	238.20	0.50	0.05	11.91			
	Ramadasappa Garden								
	1st Cross Rd	2	266.80	0.50	0.05	13.34			
	Santhosh Nagara								
	2nd Cross Rd	2	159.60	0.50	0.05	7.98			
	Connecting Rd-1	2	25.00	0.50	0.05	1.25			
	Connecting Rd-2	2	24.30	0.50	0.05	1.22			
	6th Cross Rd	2	165.40	0.50	0.05	8.27			
	6th Cross Rd Continue	2	259.30	0.50	0.05	12.97			
	Cross rd-1	2	64.20	0.50	0.05	3.21			
	Cross rd-2	2	19.00	0.50	0.05	0.95			
	Helath Care Home Rd	2	49.00	0.50	0.05	2.45			
	Helath Care Home Rd Continue	2	79.50	0.50	0.05	3.98			
	Cross rd-3	2	21.30	0.50	0.05	1.07			
	Amruthnagar Care Rd	2	24.00	0.50	0.05	1.20			
	Cross rd-4	2	36.40	0.50	0.05	1.82			
	Cross rd-5	2	23.20	0.40	0.05	0.93			
	Sri Laasya Rd	2	24.20	0.50	0.05	1.21			
	Cross rd-6[Door 13]	2	24.80	0.40	0.05	0.99			
	Varaha Entreprises Rd	2	22.50	0.40	0.05	0.90			
	Manjunatha Nilaya Rd	2	19.00	0.50	0.05	0.95			
	7th Cross Rd	2	218.70	0.50	0.05	10.94			
	White Petal School Rd	2	27.20	0.50	0.05	1.36			
	Muneshwara Layout								
	11th Cross Rd	2	47.20	0.50	0.05	2.36			
	Left Side Roads								
	10th Cross Rd	2	46.00	0.50	0.05	2.30			
	9th Cross Rd	2	99.00	0.50	0.05	4.95			
	Right Side Roads								
	10th Cross Rd	2	170.00	0.50	0.05	8.50			
	4th Cross Rd	2	45.00	0.50	0.05	2.25			
	2nd Cross Rd From Dead End	2	44.20	0.50	0.05	2.21			
	1st Cross Rd	2	45.00	0.50	0.05	2.25			
	3rd Cross Rd	2	161.00	0.50	0.05	8.05			
	5th Cross rd	2	270.60	0.50	0.05	13.53			
	6th Cross Rd								
	3rd Cross Rd	2	23.30	1.00	0.05	2.33			
	4th Cross Rd	2	21.60	1.00	0.05	2.16			
	Veerasagara Main Rd								
	[Muneshwaara Layout]								
	6th Cross Rd	2	56.80	0.65	0.05	3.69			
	6th A Cross Rd	2	65.20	0.50	0.05	3.26			
	8th Main Cross Rd-2	2	36.30	0.50	0.05	1.82			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	9th Main Rd	2	109.60	0.50	0.05	5.48			
	10th Main Road	2	46.50	0.40	0.05	1.86			
	11th Main rd	2	53.40	0.40	0.05	2.14			
	Attur Village Rd	2	118.10	0.50	0.05	5.91			
	Attur Village Main Rd	2	92.10	0.50	0.05	4.61			
	Sri Sai Layout								
	Cross Rd-4	2	140.50	0.50	0.05	7.03			
	Chitra Layout								
	Harshitha Nilaya	2	74.20	0.50	0.05	3.71			
	5th cross rd Attur layout	2	26.80	0.48	0.05	1.29			
	SFS 407								
	1st A Main Road From Dead End	2	98.80	1.00	0.05	9.88			
	1st Cross Rd	2	42.00	1.00	0.05	4.20			
	5th Phase 2nd Main Rd	2	119.10	1.10	0.05	13.10			
	Santhosh Nagara								
	1st Cross Rd	2	47.50	1.00	0.05	4.75			
	1st A Cross Rd	2	102.70	1.30	0.05	13.35			
	Mamatha Nilaya Rd	2	12.50	1.30	0.05	1.63			
	1st A Cross Rd Continue	2	33.10	1.30	0.05	4.30			
	Attur Layout								
	1st Cross Rd From 9th Main Rd	2	22.10	1.30	0.05	2.87			
	10th Main Road	2	184.70	1.30	0.05	24.01			
	4th Main Road[SFS 407]	2	128.10	1.10	0.05	14.09			
	2nd Main Rd[SFS 208]	2	211.20	1.50	0.05	31.68			
	1st Main Road[SFS 208]	2	166.00	1.50	0.05	24.90			
	1st Main Road Continue	2	145.10	1.50	0.05	21.77			
	1st Main Rd[25 to 38] SFS 208	2	158.10	1.50	0.05	23.72			
	SFS 208	2	200.00	1.50	0.05	30.00			
	SFS Cross Rd	2	300.00	1.60	0.05	48.00			
	SFS Cross Rd	2	265.00	1.50	0.05	39.75			
	Ward No-04								
	10th B Main B Sector	2	35.20	0.55	0.05	1.94			
	2nd B Main B Sector	2	72.10	0.60	0.05	4.33			
	11th B Cross Road B Sector	2	76.20	0.45	0.05	3.43			
	From Sandeep Unnikrishnan Main Road, 4th B Cross Road	2	137.30	0.55	0.05	7.55			
	th B Cross Road Continued	2	16.20	0.60	0.05	0.97			
	From 3rd B Cross Road, 7th B Main	2	67.30	0.60	0.05	4.00			
	B-sector								
	6th B Main Road	2	52.00	0.50	0.05	2.60			
	9th Cross Rd	2	45.30	0.55	0.05	2.49			
	7th B Main Rd	2	180.00	0.50	0.05	9.00			
	Profile correction								
	Under 11th cross Road (Muneshwara Layout)								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	1st Cross Road	2	33.00	0.55	0.05	1.82			
	2nd Cross Road	2	34.60	0.60	0.05	2.08			
	3rd Cross Road	2	38.20	0.45	0.05	1.72			
	Akshay Nagar								
	1st Cross Rd	1	67.60	1.00	0.05	3.38			
	Main Road From Sandeep Unnikrishan Rd	1	338.50	0.80	0.05	13.54			
	Tirumalanagara 1st Cross Rd	1	61.80	1.00	0.05	3.09			
	Escorts Colony								
	6th C Cross Rd	1	58.60	1.00	0.05	2.93			
	6th B Cross Rd	1	54.40	1.20	0.05	3.26			
	6th A Main Road	1	156.30	3.00	0.05	23.45			
	1st Cross Rd	1	208.70	3.00	0.05	31.31			
	7th A Main Rd From Dead End	1	238.20	3.00	0.05	35.73			
	Ramadasappa Garden								
	1st Cross Rd	1	266.80	1.00	0.05	13.34			
	Santhosh Nagara								
	2nd Cross Rd	1	159.60	1.00	0.05	7.98			
	Connecting Rd-1	1	25.00	1.00	0.05	1.25			
	Connecting Rd-2	1	24.30	1.00	0.05	1.22			
	6th Cross Rd	1	165.40	3.00	0.05	24.81			
	6th Cross Rd Continue	1	259.30	2.70	0.05	35.01			
	Cross rd-1	1	64.20	2.00	0.05	6.42			
	Cross rd-2	1	19.00	2.00	0.05	1.90			
	Helath Care Home Rd	1	49.00	2.00	0.05	4.90			
	Helath Care Home Rd Continue	1	79.50	1.00	0.05	3.98			
	Cross rd-3	1	21.30	1.00	0.05	1.07			
	Amruthnagar Care Rd	1	24.00	1.00	0.05	1.20			
	Cross rd-4	1	36.40	3.00	0.05	5.46			
	Cross rd-5	1	23.20	3.00	0.05	3.48			
	Sri Laasya Rd	1	24.20	3.00	0.05	3.63			
	Cross rd-6[Door 13]	1	24.80	3.00	0.05	3.72			
	Varaha Entreprises Rd	1	22.50	1.20	0.05	1.35			
	Manjunatha Nilaya Rd	1	19.00	1.60	0.05	1.52			
	7th Cross Rd	1	218.70	3.00	0.05	32.81			
	White Petal School Rd	1	27.20	1.00	0.05	1.36			
	Muneshwara Layout								
	11th Cross Rd	1	47.20	1.00	0.05	2.36			
	Left Side Roads								
	10th Cross Rd	1	46.00	1.00	0.05	2.30			
	9th Cross Rd	1	99.00	1.00	0.05	4.95			
	Right Side Roads								
	10th Cross Rd	1	170.00	1.00	0.05	8.50			
	4th Cross Rd	1	45.00	1.60	0.05	3.60			
	2nd Cross Rd From Dead End	1	44.20	1.60	0.05	3.54			
	1st Cross Rd	1	45.00	1.60	0.05	3.60			
	3rd Cross Rd	1	161.00	1.60	0.05	12.88			
	5th Cross rd	1	270.60	3.00	0.05	40.59			
	6th Cross Rd								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	3rd Cross Rd	1	23.30	0.70	0.05	0.82			
	4th Cross Rd	1	21.60	1.90	0.05	2.05			
	Veerasagara Main Rd								
	[Muneshwaara Layout]								
	6th Cross Rd	1	56.80	1.00	0.05	2.84			
	6th A Cross Rd	1	65.20	1.10	0.05	3.59			
	8th Main Cross Rd-2	1	36.30	1.00	0.05	1.82			
	9th Main Rd	1	109.60	2.00	0.05	10.96			
	10th Main Road	1	46.50	2.50	0.05	5.81			
	11th Main rd	1	53.40	2.50	0.05	6.68			
	Attur Village Rd	1	118.10	2.50	0.05	14.76			
	Attur Village Main Rd	1	92.10	2.50	0.05	11.51			
	Sri Sai Layout								
	Cross Rd-4	1	140.50	1.00	0.05	7.03			
	Chitra Layout								
	Harshitha Nilaya	1	74.20	1.20	0.05	4.45			
	5th cross rd Attur layout	1	26.80	1.40	0.05	1.88			
	SFS 407								
	1st A Main Road From Dead End	1	98.80	1.00	0.05	4.94			
	1st Cross Rd	1	42.00	1.00	0.05	2.10			
	5th Phase 2nd Main Rd	1	119.10	1.10	0.05	6.55			
	Santhosh Nagara								
	1st Cross Rd	1	47.50	1.00	0.05	2.38			
	1st A Cross Rd	1	102.70	1.30	0.05	6.68			
	Mamatha Nilaya Rd	1	12.50	1.30	0.05	0.81			
	1st A Cross Rd Continue	1	33.10	1.30	0.05	2.15			
	Attur Layout								
	1st Cross Rd From 9th Main Rd	1	22.10	1.30	0.05	1.44			
	10th Main Road	1	184.70	1.30	0.05	12.01			
	4th Main Road[SFS 407]	1	128.10	1.00	0.05	6.41			
	2nd Main Rd[SFS 208]	1	211.20	1.50	0.05	15.84			
	1st Main Road[SFS 208]	1	166.00	1.40	0.05	11.62			
	1st Main Road Continue	1	145.10	1.50	0.05	10.88			
	1st Main Rd[25 to 38] SFS 208	1	158.10	1.50	0.05	11.86			
	SFS 208	1	200.00	1.50	0.05	15.00			
	SFS Cross Rd	1	300.00	1.00	0.05	15.00			
	SFS Cross Rd	1	265.00	1.00	0.05	13.25			
	Ward No-04								
	10th B Main B Sector	2	35.20	0.55	0.05	1.94			
	2nd B Main B Sector	2	67.50	0.60	0.05	4.05			
	11th B Cross Road B Sector	2	50.00	0.45	0.05	2.25			
	B-sector								
	6th B Main Road	1	52.00	2.00	0.05	5.20			
	9th Cross Rd	1	45.30	2.00	0.05	4.53			
	7th B Main Rd	1	180.00	2.00	0.05	18.00			
	New Asphalt Road								
	Santhosh Nagara								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	1st Cross Rd	1	164.50	4.65	0.05	38.25			
	4th Cross Rd	1	148.10	4.80	0.05	35.54			
	Theraman Sharma Rd	1	33.20	4.14	0.05	6.87			
	9th B Cross Rd	1	36.00	3.93	0.05	7.07			
	Muneshwara Layout								
	Right Side Roads								
	9th Cross Rd	1	170.00	4.76	0.05	40.46			
	4th Cross Rd	1	172.40	5.22	0.05	45.00			
	1st Cross Rd	1	27.50	4.39	0.05	6.04			
	2nd Cross Rd	1	25.00	5.00	0.05	6.25			
	Veerasagara Main Rd								
	(Muneshwaara Layout)								
	6th B Cross Rd	1	116.50	4.48	0.05	26.10			
	5th A Cross Rd	1	92.30	5.50	0.05	25.38			
	6th Cross Rd	1	133.00	5.05	0.05	33.58			
	Sri Sai Layout								
	Cross Rd-1	1	109.00	7.42	0.05	40.44			
	Cross RD-2	1	30.00	8.40	0.05	12.60			
	Cross RD-3	1	131.00	6.03	0.05	39.50			
	Chitra Layout								
	3rd Cross Rd	1	150.00	4.21	0.05	31.58			
	Santhosh Nagara								
	1st Main Road	1	19.00	2.10	0.05	2.00			
	Vijaya Bank Layout								
	1st Cross Rd	1	58.50	5.30	0.05	15.50			
	2nd Cross Rd	1	31.30	5.60	0.05	8.76			
	3rd Cross Rd	1	63.15	6.25	0.05	19.73			
	Ayyappa Layout								
	8th Cross Rd	1	38.10	5.50	0.05	10.48			
	4th Main Road	1	33.00	7.00	0.05	11.55			
						2344.67	**Cum**	**10938.22**	**25646563.18**
	Approved Amount	**10938.22**							
17	Providing and laying Bituminous Concrete with 40/60 TPH capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 5.4 per cent of mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects (V-III, P.No.36, I.No.5.16C of PWD SR 2021-22).								
	For BC								
	Asphalt Road								
	Akshyanagar								
	2nd cross road	1	63.50	6.10	0.04	15.49			
	3rd cross road	1	64.50	6.10	0.04	15.74			
	4th cross road	1	63.50	5.90	0.04	14.99			
	5th cross road	1	60.00	6.70	0.04	16.08			
	6th cross road	1	65.00	6.00	0.04	15.60			
	7th cross road	1	64.00	6.20	0.04	15.87			
	8th A main road	1	257.60	6.45	0.04	66.46			
	State Bank of India road	1	139.00	6.15	0.04	34.19			
	2nd A main road	1	125.60	3.95	0.04	19.84			
	Attur Layout 2nd main road	1	341.90	4.05	0.04	55.39			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Attur Layout 3rd main road	1	421.60	3.70	0.04	62.40			
	Attur Layout 4th main road (From End)	1	383.40	3.95	0.04	60.58			
	Attur Layout 5th main road	1	373.60	4.70	0.04	70.24			
	Attur Layout 6th main road (From End)	1	321.30	3.70	0.04	47.55			
	Attur Layout 7th main road	1	323.90	4.10	0.04	53.12			
	Attur Layout 8th main road	1	324.20	4.30	0.04	55.76			
	Attur Layout 1st cross road	1	226.20	5.90	0.04	53.38			
	Attur Layout 2nd cross road	1	255.10	5.70	0.04	58.16			
	Attur Layout 3rd cross road (From End)	1	285.70	5.90	0.04	67.43			
	Attur Layout 4th cross road	1	263.70	5.80	0.04	61.18			
	Under 11th cross Road (Muneshwara Layout)								
	1st Cross Road	1	33.00	4.70	0.04	6.20			
	2nd Cross Road	1	34.60	4.85	0.04	6.71			
	3rd Cross Road	1	38.20	5.20	0.04	7.95			
	1st Cross Rd	1	67.60	6.57	0.04	17.77			
	Main Road From Sandeep Unnikrishan Rd	1	338.50	6.47	0.04	87.54			
	Tirumalanagara 1st Cross Rd	1	61.80	6.48	0.04	16.02			
	Escorts Colony								
	6th C Cross Rd	1	58.60	4.33	0.04	10.15			
	6th B Cross Rd	1	54.40	4.40	0.04	9.57			
	6th A Main Road	1	156.30	4.68	0.04	29.26			
	1st Cross Rd	1	208.70	6.82	0.04	56.93			
	7th A Main Rd From Dead End	1	238.20	4.85	0.04	46.21			
	Ramadasappa Garden								
	1st Cross Rd	1	266.80	4.42	0.04	47.17			
	Santhosh Nagara								
	1st Cross Rd	1	164.50	4.65	0.04	30.60			
	2nd Cross Rd	1	159.60	3.99	0.04	25.48			
	4th Cross Rd	1	148.10	4.80	0.04	28.44			
	Connecting Rd-1	1	25.00	4.45	0.04	4.45			
	Connecting Rd-2	1	24.30	4.95	0.04	4.81			
	6th Cross Rd	1	165.40	5.41	0.04	35.79			
	6th Cross Rd Continue	1	259.30	5.33	0.04	55.23			
	Cross rd-1	1	64.20	4.82	0.04	12.38			
	Cross rd-2	1	19.00	4.30	0.04	3.27			
	Helath Care Home Rd	1	49.00	5.36	0.04	10.51			
	Helath Care Home Rd Continue	1	79.50	5.15	0.04	16.38			
	Cross rd-3	1	21.30	3.30	0.04	2.81			
	Amruthnagar Care Rd	1	24.00	3.45	0.04	3.31			
	Cross rd-4	1	36.40	4.36	0.04	6.35			
	Cross rd-5	1	23.20	3.85	0.04	3.57			
	Sri Laasya Rd	1	24.20	4.40	0.04	4.26			
	Cross rd-6[Door 13]	1	24.80	4.85	0.04	4.81			
	Varaha Entreprises Rd	1	22.50	4.55	0.04	4.10			
	Manjunatha Nilaya Rd	1	19.00	5.00	0.04	3.80			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	7th Cross Rd	1	218.70	4.10	0.04	35.87			
	White Petal School Rd	1	27.20	2.75	0.04	2.99			
	Thiraman Sharma Rd	1	33.20	4.14	0.04	5.50			
	9th B Cross Rd	1	36.00	3.93	0.04	5.65			
	Muneshwara Layout								
	11th Cross Rd	1	47.20	5.60	0.04	10.57			
	Left Side Roads								
	10th Cross Rd	1	46.00	4.42	0.04	8.13			
	9th Cross Rd	1	99.00	4.98	0.04	19.72			
	Right Side Roads								
	10th Cross Rd	1	170.00	4.86	0.04	33.05			
	9th Cross Rd	1	170.00	4.76	0.04	32.37			
	4th Cross Rd	1	45.00	5.88	0.04	10.58			
	2nd Cross Rd From Dead End	1	44.20	4.64	0.04	8.20			
	1st Cross Rd	1	45.00	4.80	0.04	8.64			
	3rd Cross Rd	1	161.00	6.55	0.04	42.18			
	4th Cross Rd	1	172.40	5.22	0.04	36.00			
	5th Cross rd	1	270.60	5.33	0.04	57.64			
	6th Cross Rd								
	1st Cross Rd	1	27.50	4.39	0.04	4.83			
	2nd Cross Rd	1	25.00	5.00	0.04	5.00			
	3rd Cross Rd	1	23.30	5.15	0.04	4.80			
	4th Cross Rd	1	21.60	4.89	0.04	4.22			
	Veerasagara Main Rd								
	(Muneshwaara Layout)								
	6th Cross Rd	1	56.80	3.40	0.04	7.72			
	6th B Cross Rd	1	116.50	4.48	0.04	20.88			
	6th A Cross Rd	1	65.20	4.47	0.04	11.66			
	5th A Cross Rd	1	92.30	5.50	0.04	20.31			
	6th Cross Rd	1	133.00	5.05	0.04	26.87			
	8th Main Cross Rd-2	1	36.30	6.74	0.04	9.79			
	9th Main Rd	1	109.60	4.35	0.04	19.07			
	10th Main Road	1	46.50	5.84	0.04	10.86			
	11th Main rd	1	53.40	5.27	0.04	11.26			
	Attur Village Rd	1	118.10	5.99	0.04	28.30			
	Attur Village Main Rd	1	92.10	6.68	0.04	24.61			
	Sri Sai Layout								
	Cross Rd-1	1	109.00	7.42	0.04	32.35			
	Cross RD-2	1	30.00	8.40	0.04	10.08			
	Cross RD-3	1	131.00	6.03	0.04	31.60			
	Cross Rd-4	1	140.50	6.62	0.04	37.18			
	Chitra Layout								
	3rd Cross Rd	1	150.00	4.21	0.04	25.26			
	Harshitha Nilaya	1	74.20	3.86	0.04	11.46			
	5th cross rd Attur layout	1	26.80	4.35	0.04	4.66			
	SFS 407								
	1st A Main Road From Dead End	1	98.80	7.90	0.04	31.22			
	1st Cross Rd	1	42.00	5.80	0.04	9.74			
	5th Phase 2nd Main Rd	1	119.10	5.45	0.04	25.96			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Santhosh Nagara								
	1st Main Road	1	19.00	2.10	0.04	1.60			
	1st Cross Rd	1	47.50	4.45	0.04	8.46			
	1st A Cross Rd	1	102.70	5.76	0.04	23.66			
	Mamatha Nilaya Rd	1	12.50	4.10	0.04	2.05			
	1st A Cross Rd Continue	1	33.10	6.20	0.04	8.21			
	Attur Layout								
	1st Cross Rd From 9th Main Rd	1	22.10	5.50	0.04	4.86			
	10th Main Road	1	184.70	3.91	0.04	28.89			
	Vijaya Bank Layout								
	1st Cross Rd	1	58.50	5.30	0.04	12.40			
	2nd Cross Rd	1	31.30	5.60	0.04	7.01			
	3rd Cross Rd	1	63.15	6.25	0.04	15.79			
	Ayyappa Layout								
	8th Cross Rd	1	38.10	5.50	0.04	8.38			
	4th Main Road	1	33.00	7.00	0.04	9.24			
	4th Main Road[SFS 407]	1	128.10	9.60	0.04	49.19			
	2nd Main Rd[SFS 208]	1	211.20	7.48	0.04	63.19			
	1st Main Road[SFS 208]	1	166.00	8.95	0.04	59.43			
	1st Main Road Continue	1	145.10	9.10	0.04	52.82			
	1st Main Rd[25 to 38] SFS 208	1	158.10	8.52	0.04	53.88			
	SFS 208	1	200.00	7.00	0.04	56.00			
	SFS Cross Rd	1	300.00	7.00	0.04	84.00			
	SFS Cross Rd	1	265.00	7.00	0.04	74.20			
	Ward No-04								
	10th B Main B Sector	1	35.20	6.00	0.04	8.45			
	2nd B Main B Sector	1	72.10	6.30	0.04	18.17			
	11th B Cross Road B Sector	1	76.20	5.80	0.04	17.68			
	From Sandeep Unnikrishnan Main Road, 4th B Cross Road	1	137.30	6.65	0.04	36.52			
	th B Cross Road Continued	1	16.20	7.12	0.04	4.61			
	From 3rd B Cross Road, 7th B Main	1	67.30	6.30	0.04	16.96			
	B-sector								
	6th B Main Road	1	52.00	5.86	0.04	12.19			
	9th Cross Rd	1	45.30	6.98	0.04	12.65			
	7th B Main Rd	1	180.00	6.10	0.04	43.89			
						3002.42	**Cum**	**12754.44**	**38294136.87**
	Approved Amount	**12754.44**							
18	Providing and laying of **hot applied thermoplastic compound** 2.5 mm thick including reflectorising glass beads @ 250 g/ m2 area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35:2015.The finished surface to be level, uniform and free from streaks and holes.(V-III,I No-8.15, P.No-57 of KPWD SR 2021-22)								
	For BC								
	Asphalt Road								
	Akshyanagar	2	63.50	0.10		12.70			
	2nd cross road	2	64.50	0.10		12.90			
	3rd cross road								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	4th cross road	2	63.50	0.10		12.70			
	5th cross road	2	60.00	0.10		12.00			
	6th cross road	2	65.00	0.10		13.00			
	7th cross road	2	64.00	0.10		12.80			
	8th A main road	2	257.60	0.10		51.52			
	State Bank of India road	2	139.00	0.10		27.80			
	2nd A main road	2	125.60	0.10		25.12			
	Attur Layout 2nd main road	2	341.90	0.10		68.38			
	Attur Layout 3rd main road	2	421.60	0.10		84.32			
	Attur Layout 4th main road (From End)	2	383.40	0.10		76.68			
	Attur Layout 5th main road	2	373.60	0.10		74.72			
	Attur Layout 6th main road (From End)	2	321.30	0.10		64.26			
	Attur Layout 7th main road	2	323.90	0.10		64.78			
	Attur Layout 8th main road	2	324.20	0.10		64.84			
	Attur Layout 1st cross road	2	226.20	0.10		45.24			
	Attur Layout 2nd cross road	2	255.10	0.10		51.02			
	Attur Layout 3rd cross road (From End)	2	285.70	0.10		57.14			
	Attur Layout 4th cross road	2	263.70	0.10		52.74			
	Under 11th cross Road (Muneshwara Layout)								
	1st Cross Road	2	33.00	0.10		6.60			
	2nd Cross Road	2	34.60	0.10		6.92			
	3rd Cross Road	2	38.20	0.10		7.64			
	1st Cross Rd	2	67.60	0.10		13.52			
	Main Road From Sandeep Unnikrishan Rd	2	338.50	0.10		67.70			
	Tirumalanagara 1st Cross Rd	2	61.80	0.10		12.36			
	Escorts Colony								
	6th C Cross Rd	2	58.60	0.10		11.72			
	6th B Cross Rd	2	54.40	0.10		10.88			
	6th A Main Road	2	156.30	0.10		31.26			
	1st Cross Rd	2	208.70	0.10		41.74			
	7th A Main Rd From Dead End	2	238.20	0.10		47.64			
	Ramadasappa Garden								
	1st Cross Rd	2	266.80	0.10		53.36			
	Santhosh Nagara								
	1st Cross Rd	2	164.50	0.10		32.90			
	2nd Cross Rd	2	159.60	0.10		31.92			
	4th Cross Rd	2	148.10	0.10		29.62			
	Connecting Rd-1	2	25.00	0.10		5.00			
	Connecting Rd-2	2	24.30	0.10		4.86			
	6th Cross Rd	2	165.40	0.10		33.08			
	6th Cross Rd Continue	2	259.30	0.10		51.86			
	Cross rd-1	2	64.20	0.10		12.84			
	Cross rd-2	2	19.00	0.10		3.80			
	Helath Care Home Rd	2	49.00	0.10		9.80			
	Helath Care Home Rd Continue	2	79.50	0.10		15.90			
	Cross rd-3	2	21.30	0.10		4.26			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Amruthnagar Care Rd	2	24.00	0.10		4.80			
	Cross rd-4	2	36.40	0.10		7.28			
	Cross rd-5	2	23.20	0.10		4.64			
	Sri Laasya Rd	2	24.20	0.10		4.84			
	Cross rd-6[Door 13]	2	24.80	0.10		4.96			
	Varaha Entreprises Rd	2	22.50	0.10		4.50			
	Manjunatha Nilaya Rd	2	19.00	0.10		3.80			
	7th Cross Rd	2	218.70	0.10		43.74			
	White Petal School Rd	2	27.20	0.10		5.44			
	Tharaman Sharma Rd	2	33.20	0.10		6.64			
	9th B Cross Rd	2	36.00	0.10		7.20			
	Muneshwara Layout								
	11th Cross Rd	2	47.20	0.10		9.44			
	Left Side Roads								
	10th Cross Rd	2	46.00	0.10		9.20			
	9th Cross Rd	2	99.00	0.10		19.80			
	Right Side Roads								
	10th Cross Rd	2	170.00	0.10		34.00			
	9th Cross Rd	2	170.00	0.10		34.00			
	4th Cross Rd	2	68.00	0.10		13.60			
	2nd Cross Rd From Dead End	2	44.20	0.10		8.84			
	1st Cross Rd	2	45.00	0.10		9.00			
	3rd Cross Rd	2	161.00	0.10		32.20			
	4th Cross Rd	2	172.40	0.10		34.48			
	5th Cross rd	2	270.60	0.10		54.12			
	6th Cross Rd								
	1st Cross Rd	2	27.50	0.10		5.50			
	2nd Cross Rd	2	25.00	0.10		5.00			
	3rd Cross Rd	2	23.30	0.10		4.66			
	4th Cross Rd	2	21.60	0.10		4.32			
	Veerasagara Main Rd								
	[Muneshwaara Layout]								
	6th Cross Rd	2	56.80	0.10		11.36			
	6th B Cross Rd	2	116.50	0.10		23.30			
	6th A Cross Rd	2	65.20	0.10		13.04			
	5th A Cross Rd	2	92.30	0.10		18.46			
	6th Cross Rd	2	133.00	0.10		26.60			
	8th Main Cross Rd-2	2	36.30	0.10		7.26			
	9th Main Rd	2	109.60	0.10		21.92			
	10th Main Road	2	46.50	0.10		9.30			
	11th Main rd	2	53.40	0.10		10.68			
	Attur Village Rd	2	118.10	0.10		23.62			
	Attur Village Main Rd	2	92.10	0.10		18.42			
	Sri Sai Layout								
	Cross Rd-1	2	109.00	0.10		21.80			
	Cross RD-2	2	30.00	0.10		6.00			
	Cross RD-3	2	131.00	0.10		26.20			
	Cross Rd-4	2	140.50	0.10		28.10			
	Chitra Layout								
	3rd Cross Rd	2	150.00	0.10		30.00			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Harshitha Nilaya	2	74.20	0.10		14.84			
	5th cross rd Attur layout	2	26.80	0.10		5.36			
	SFS 407								
	1st A Main Road From Dead End	2	98.80	0.10		19.76			
	1st Cross Rd	2	42.00	0.10		8.40			
	5th Phase 2nd Main Rd	2	119.10	0.10		23.82			
	Santhosh Nagara								
	1st Main Road	2	19.00	0.10		3.80			
	1st Cross Rd	2	47.50	0.10		9.50			
	1st A Cross Rd	2	102.70	0.10		20.54			
	Mamatha Nilaya Rd	2	12.50	0.10		2.50			
	1st A Cross Rd Continue	2	33.10	0.10		6.62			
	Attur Layout								
	1st Cross Rd From 9th Main Rd	2	22.10	0.10		4.42			
	10th Main Road	2	184.70	0.10		36.94			
	Vijaya Bank Layout								
	1st Cross Rd	2	58.50	0.10		11.70			
	2nd Cross Rd	2	31.30	0.10		6.26			
	3rd Cross Rd	2	63.15	0.10		12.63			
	Ayyappa Layout								
	8th Cross Rd	2	38.10	0.10		7.62			
	4th Main Road	2	33.00	0.10		6.60			
	4th Main Road[SFS 407]	2	128.10	0.10		25.62			
	2nd Main Rd[SFS 208]	2	211.20	0.10		42.24			
	1st Main Road[SFS 208]	2	166.00	0.10		33.20			
	1st Main Road Continue	2	145.10	0.10		29.02			
	1st Main Rd[25 to 38] SFS 208	2	158.10	0.10		31.62			
	SFS 208	2	200.00	0.10		40.00			
	SFS Cross Rd	2	300.00	0.10		60.00			
	SFS Cross Rd	2	265.00	0.10		53.00			
	Ward No-04								
	10th B Main B Sector	2	35.20	0.10		7.04			
	2nd B Main B Sector	2	72.10	0.10		14.42			
	11th B Cross Road B Sector	2	76.20	0.10		15.24			
	From Sandeep Unnikrishnan Main Road, 4th B Cross Road	2	137.30	0.10		27.46			
	th B Cross Road Continued	2	16.20	0.10		3.24			
	From 3rd B Cross Road, 7th B Main	2	67.30	0.10		13.46			
	B-sector								
	6th B Main Road	2	52.00	0.10		10.40			
	9th Cross Rd	2	45.30	0.10		9.06			
	7th B Main Rd	2	180.00	0.10		36.00			
						2756.23	**Sqm**	**528.72**	**1457261.69**
	Approved Amount	**528.72**							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
19	Dismantling of **cement concrete pavement** by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials separatel (V-III Page No.10, Item No.2.19 of PWD SR 2021-22)								
	CC Road								
	4th Phase								
	Opp To Annapurnashwari Catering								
	Beside Apartment	1	19.60	3.03	0.25	14.85			
	Chaitra Layout								
	3rd Cross Rd	1	27.00	3.96	0.25	26.73			
	3rd Cross Rd[Connecting Rd]	1	17.00	4.40	0.25	18.70			
	Attur Layout								
	3rd A Main Road	1	131.10	3.84	0.25	125.86			
	5th Cross Road	1	101.50	3.12	0.25	79.17			
	Veerabadeshwara Nilaya House Rd	1	34.00	5.59	0.25	47.52			
	Escorts Engineering Layout 7th Cross Rd	1	11.10	4.85	0.25	13.46			
	Vaidhika Sabha Building Entrance Road	1	122.10	5.48	0.25	167.28			
						493.55	**Cum**	**466.77**	**230378.05**
	Approved Amount	**466.77**							
20	Providing and laying in position **plain cement concrete** for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) **Mix 1:5:10** Using 40 mm nominal size graded crushed coarse aggregates(V-I,I No-2.11, P.No-15of KPWD SR 2021-22)								
	CC Road								
	4th Phase								
	Opp To Annapurnashwari Catering								
	Beside Apartment	1	19.60	3.03	0.15	8.91			
	Chaitra Layout								
	3rd Cross Rd	1	27.00	3.96	0.15	16.04			
	3rd Cross Rd[Connecting Rd]	1	17.00	4.40	0.15	11.22			
	Attur Layout								
	3rd A Main Road	1	131.10	3.84	0.15	75.51			
	5th Cross Road	1	101.50	3.12	0.15	47.50			
	Veerabadeshwara Nilaya House Rd	1	34.00	5.59	0.15	28.51			
	Escorts Engineering Layout 7th Cross Rd	1	11.10	4.85	0.15	8.08			
	Vaidhika Sabha Building Entrance Road	1	122.10	5.48	0.15	100.37			
	Vaidhika Sabha Building Inside	1	68.30	5.95	0.15	60.96			
						357.09	**Cum**	**5503.95**	**1965405.90**
	Approved Amount	**5503.95**							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
21	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, , primer, sealant , curing of concrete slabs for 14- days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete. as per the directions of the Engineer-in-charge of the work.(V-III, P.No-138,I No-20.29, KPWD SR 2021-22).								
	CC Road								
	4th Phase								
	Opp To Annapurnashwari Catering								
	Beside Apartment	1	19.60	3.03	0.15	8.91			
	Chaitra Layout								
	3rd Cross Rd	1	27.00	3.96	0.15	16.04			
	3rd Cross Rd[Connecting Rd]	1	17.00	4.40	0.15	11.22			
	Attur Layout								
	3rd A Main Road	1	131.10	3.84	0.15	75.51			
	5th Cross Road	1	101.50	3.12	0.15	47.50			
	Veerabadeshwara Nilaya House Rd	1	34.00	5.59	0.15	28.51			
	Escorts Engineering Layout 7th Cross Rd	1	11.10	4.85	0.15	8.08			
	Vaidhika Sabha Building Entrance Road	1	122.10	5.48	0.15	100.37			
	Vaidhika Sabha Building Inside	1	68.30	5.95	0.15	60.96			
						357.09	**Cum**	**7562.41**	**2700460.99**
	Approved Amount	**7562.41**							
22	Providing and laying heavy **duty cobble stones 60mm thick** interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per m2 over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level , including cost of materials, labour and Usage charges of machinery complete as per specifications. (V-I.No 9.31,Page No-64 PWD SR 2021-22)								
	For Pathway								
	Ward No-03								
	S-LIG - 10,11	1	39.80	6.20		246.76			
	S-LIG - 08,09	1	24.20	6.70		162.14			
	S-LIG - 07	1	6.80	4.00		27.20			
	S-LIG - 06	1	35.50	7.00		248.50			
	S-LIG - 05	1	4.20	4.20		17.64			
	S-LIG - 03	1	39.60	4.00		158.40			
	S-LIG - 01	1	34.60	6.26		195.18			
	Bheema Blocks HIG - B - 2	1	41.40	5.00		207.00			
	SFS 208								
	15th Block	1	58.30	3.15		183.65			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	S-HIG 32	1	41.80	5.40		225.72			
	Opp To Annapurnashwari Catering	1	73.70	4.15		305.86			
	S-LIG 42								
	Beside Neha Praksha Hospital	1	48.50	3.40		164.90			
	SFS 208								
	2nd Main Road RHS	1	161.50	1.33		214.80			
	3rd Main Road LHS	1	28.30	1.00		28.30			
	4th Cross Rd RHS From United Residency Association	1	116.60	0.62		72.29			
	4th Cross Rd LHS From Dental Clinic	1	78.20	0.80		62.56			
	BMS Hostel Opp Road LHS	1	71.20	0.60		42.72			
	BMS Hostel Opp Road RHS	1	102.80	0.59		60.96			
	Urdhu School Surrounding	1	100.00	3.05		305.00			
	Ward No-04								
	7th B Cross Rd	1	24.00	1.00		24.00			
						2953.57	Sqm	1202.33	3551168.17
	Approved Amount	1202.33							
23	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km (V-III Page No.3, Item No.1.4 A of PWD SR 2021-22)								
	Qty frm Item No-2		9123.77	1.28		11678.43			
	Qty frm Item No-11		12870.96	1.28		16474.82			
	Qty frm Item No-24		252.76	1.28		323.53			
	Qty frm Item No-19		493.55	2.10		1036.46			
						29513.25	t.Km	106.19	3133880.71
	Approved Amount	106.19							
24	Earth work excavation for Foundation by mechanical means for all works & depth upto 3 m, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenaces required to complete the work Depth exceeding 1.5 m, but not exceeding 3 (V-I Page No.8, Item No.1.15.2 of PWD SR 2021-22)								
	Vaidhika Sabha Building								
	Footings	19	1.80	1.80	2.10	129.28			
	SSM Foundation								
	Ritual Rooom-1, Ritual Rooom-2, Ritual Rooom-3 and Store Room								
	Long Wall	2	24.57	0.75	0.90	33.17			
	Short Wall	5	4.88	0.75	0.90	16.47			
	Kitchen, Room, Room-1, Bath and Toilet								
	Long Wall	2	19.56	0.75	0.90	26.41			
	Short Wall	6	3.58	0.75	0.90	14.50			
	Corridor	2	5.50	0.75	0.90	7.43			
	Staircase	2	2.00	0.75	0.90	2.70			
	Near Compound	2	0.90	0.75	0.90	1.22			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	S-HIG 32	1	41.80	5.40		225.72			
	Opp To Annapurnashwari Catering	1	73.70	4.15		305.86			
	S-LIG 42								
	Beside Neha Praksha Hospital	1	48.50	3.40		164.90			
	SFS 208								
	2nd Main Road RHS	1	161.50	1.33		214.80			
	3rd Main Road LHS	1	28.30	1.00		28.30			
	4th Cross Rd RHS From United Residency Association	1	116.60	0.62		72.29			
	4th Cross Rd LHS From Dental Clinic	1	78.20	0.80		62.56			
	BMS Hostel Opp Road LHS	1	71.20	0.60		42.72			
	BMS Hostel Opp Road RHS	1	102.80	0.59		60.96			
	Urdhu School Surrounding	1	100.00	3.05		305.00			
	Ward No-04								
	7th B Cross Rd	1	24.00	1.00		24.00			
						2953.57	**Sqm**	**1202.33**	**3551168.17**
	Approved Amount	**1202.33**							
23	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km (V-III Page No.3, Item No.1.4 A of PWD SR 2021-22)								
	Qty frm Item No-2		9123.77	1.28		11678.43			
	Qty frm Item No-11		12870.96	1.28		16474.82			
	Qty frm Item No-24		252.76	1.28		323.53			
	Qty frm Item No-19		493.55	2.10		1036.46			
						29513.25	**t.Km**	**106.19**	**3133880.71**
	Approved Amount	**106.19**							
24	**Earth work excavation for Foundation** by mechanical means for all works & depth upto 3 m, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenaces required to complete the work Depth exceeding 1.5 m, but not exceeding 3 (V-I Page No.8, Item No 1.15.2 of PWD SR 2021-22)								
	Vaidhika Sabha Building								
	Footings	19	1.80	1.80	2.10	129.28			
	SSM Foundation								
	Ritual Rooom-1, Ritual Rooom-2, Ritual Rooom-3 and Store Room								
	Long Wall	2	24.57	0.75	0.90	33.17			
	Short Wall	5	4.88	0.75	0.90	16.47			
	Kitchen, Room, Room-1, Bath and Toilet								
	Long Wall	2	19.56	0.75	0.90	26.41			
	Short Wall	6	3.58	0.75	0.90	14.50			
	Corridor	2	5.50	0.75	0.90	7.43			
	Staircase	2	2.00	0.75	0.90	2.70			
	Near Compound	2	0.90	0.75	0.90	1.22			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Sump	1	3.00	3.00	2.40	21.60			
						252.76	Cum	353.95	89465.04
	Approved Amount	353.95							
25	Providing and laying in position Reinforced cement concrete for all Foundation works. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticizers laid in finished layers, well compacted using needle vibrators, including all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) **M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates** (V-I Page No.15, Item No.2.2.2.1 of PWD SR 2021-22)								
	Vaidhika Sabha Building								
	Footings	19	1.80	1.80	0.45	27.70			
	Coloum - 1 up to Plinth	14	0.20	0.45	1.60	2.02			
	Coloum - 2 up to Plinth	5	0.20	0.40	1.60	0.64			
	Plinth Beam								
	Ritual Rooom-1, Ritual Rooom-2, Ritual Rooom-3 and Store Room								
	Long Wall	2	24.40	0.30	0.23	3.37			
	Short Wall	5	5.86	0.30	0.23	2.02			
	Kitchen, Room, Room-1, Bath and Toilet								
	Long Wall	2	18.58	0.30	0.23	2.56			
	Short Wall	6	4.56	0.30	0.23	1.89			
	Corridor	2	5.50	0.30	0.23	0.76			
	Sump Raft Bottom	1	3.00	3.00	0.15	1.35			
	Slab								
		1	1.00	1.10	0.15	0.17			
		1	5.00	7.30	0.15	5.48			
		1	21.00	16.90	0.15	53.24			
	Deduction								
		-1	2.40	1.00	0.15	-0.36			
	Beam								
		4	16.90	0.23	0.30	4.66			
		2	24.80	0.23	0.30	3.42			
		2	21.00	0.23	0.30	2.90			
		1	5.90	0.23	0.30	0.41			
	Staircase	1	2.80	1.00	0.15	0.42			
	Landing	1	2.00	1.30	0.15	0.39			
	Waist Slab 1	1	4.90	1.30	0.15	0.96			
	Waist Salb 2								
	Steps	19	0.02	1.30		0.56			
	1/2 * 0.3*0.15*1.3	2	3.00	0.20	2.10	2.52			
	Coloum - 1 above Plinth	14	0.20	0.45	4.00	5.04			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Coloum - 2 above Plinth	5	0.20	0.40	4.00	1.60			
						123.70	Cum		
				Upto 125%		104.01	Cum	7647.02	795385.55
				Above 125%		19.68	Cum	7647.02	150519.56
	Approved Amount	7647.02							
26	Providing and laying in position Reinforced cement concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/ trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement, dowel bars & formwork to be paid separately)M20 **Design Mix Using 20 mm nominal size** graded crushed coarse aggregates (V-I Page No.17, Item No.2.5.1 of PWD SR 2021-22)								
	Vaidhika Sabha Building								
	Column Above Plinth	14	0.20	0.45	2.10	2.65			
	Column Above Plinth	5	0.20	0.40	2.10	0.84			
	Sump Slab Top	1	3.0	3.00	0.15	1.35			
	Sump Wall	2	3.0	0.20	2.10	2.52			
		2	3.0	0.20	2.10	2.52			
	Chejja Internal								
	Store Room	1	5.90	0.45	0.15	0.40			
	Kitchen	1	7.70	0.45	0.15	0.52			
	Room	1	4.00	0.45	0.15	0.27			
	Room - 1	1	3.00	0.45	0.15	0.20			
	Chejja External								
	W	7	1.80	0.30	0.15	0.57			
	V	3	0.90	0.30	0.15	0.12			
						11.96	Cum	7873.33	94125.62
	Approved Amount	7873.33							
27	**Providing Size Stone masonry** with hard stone in foundation & plinth with Cement mortar 1:6(1 cement : 6 coarse sand) (V-II Page No.9, Item No.5.4 of PWD SR 2021-22)								
	Vaidhika Sabha building								
	SSM Foundation								
	Ritual Rooom-1, Ritual Rooom-2, Ritual Rooom-3 and Store Room								
	Long Wall	2	24.57	0.75	1.20	44.23			
	Short Wall	5	4.88	0.75	1.20	21.96			
	Kitchen, Room, Room-1, Bath and Toilet								
	Long Wall	2	19.56	0.75	0.60	17.60			
	Short Wall	6	3.58	0.75	0.60	9.67			
	Corridor	2	5.50	0.75	0.80	6.60			
	Near Compound	2	0.90	0.75	1.20	1.62			
	SSM Foundation								
	Compound Wall								
	1st Step								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
		1	87.20	0.60	0.60	31.39			
	2nd Step								
		1	87.20	0.45	0.60	23.54			
						156.61	Cum		
				Upto 125%		154.14	Cum	5997.27	924404.43
				Above 125%		2.47	Cum	5997.27	14,840.25
	Approved Amount	5997.27							
28	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations and other similar works etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.(V-I Page No.7, Item No.1.9 of PWD SR 2021-22)								
	Vaidhika Sabha building								
	Ritual Rooom-1	1	6.40	5.7	1.20	43.78			
	Ritual Rooom-2	1	6.40	5.7	1.20	43.78			
	Ritual Rooom-3	1	6.40	5.7	1.20	43.78			
	Store Room	1	5.70	4.9	1.20	33.52			
	Kitchen	1	4.40	3.8	0.60	10.03			
	Room	1	4.40	3.8	0.60	10.03			
	Room-1	1	3.30	3.8	0.60	7.52			
	Toilet-1	1	3.80	2.9	0.60	6.61			
	Toilet-2	1	4.40	3.8	0.60	10.03			
	Corridor	1	19.20	7	0.80	107.52			
						316.60	Cum	225.64	71438.08
	Approved Amount	225.64							
29	Providing Thermo-Mechanically Treated bars of grade Fe-500D or more Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position, binding and anchoring to adjacent members whereever necessary complete as per Design including cost of material, labour, usage charges complete as per specifications. (The laps and wastages shall not be measured separately) (V-II Page No.11.32, Item No.84 of PWD SR 2021-22)								
	Vaidhika Sabha building								
	Column	1	5.88		120.00	705.13			
	Footing	1	27.70		65.00	1800.50			
	Plinth Beam	1	22.58		100.00	2258.00			
	Sump	1	3.84		80.00	307.20			
	Roof Beam	1	11.40		101.00	1151.40			
	Roof Slab	1	58.52		67.50	3950.10			
	Staircase	1	11.25		23.00	258.75			
	Gate Columns	1	0.34		80.00	26.86			
						10458.94	Kg	117.25	1226275.09
	Approved Amount	117.25							
30	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x200x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications. (V-II Page No.17, Item No.6.32 of PWD SR 2021-22)								
	Vaidhika Sabha Building								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Ritual Rooom-1, Ritual Rooom-2, Ritual Rooom-3 and Store Room								
	Long Wall	2	24.05		2.10	101.01			
	Short Wall	5	5.40		2.10	56.70			
	Kitchen, Room, Room-1, Bath and Toilet								
	Long Wall	2	19.04		2.10	79.97			
	Short Wall	6	4.10		2.10	51.66			
	Deductions								
	Columns	-18	0.23		2.10	-8.69			
	Deduction								
	D	-6	1.2		2.1	-15.12			
	D1	-3	0.9		2.1	-5.67			
	W	-9	1.4		1.5	-18.9			
	V	-6	0.6		0.6	-2.16			
	Ritual Rooom-1, Ritual Rooom-2, Ritual Rooom-3 and Store Room								
	Long Wall	2	24.05		0.90	43.29			
	Short Wall	5	5.40		0.90	24.30			
	Kitchen, Room, Room-1, Bath and Toilet								
	Long Wall	2	19.04		0.90	34.27			
	Short Wall	6	4.10		0.90	22.14			
	Deductions								
	Columns	-18	0.23		0.90	-3.73			
						359.07	**Sqm**	**1329.53**	**477394.91**
	Approved Amount	**1329.53**							
31	Providing and constructing **load bearing wall with Solid** Concrete blocks of size **400x100x200mm** having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572 2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.(V-II Page No 17, Item No.6.34 of PWD SR 2021-22)								
	Vaidhika Sabha Building								
	Toilet-1								
	Long Wall	1	4.10		2.10	8.61			
	Short Wall	1	1.50		2.10	3.15			
	Toilet-2								
	Long Wall	2	4.10		2.10	17.22			
	Short Wall	2	1.50		2.10	6.30			
	Doors	-6	0.9		2.1	-11.34			
	Toilet-1								
	Long Wall	1	4.10		0.90	3.69			
	Short Wall	1	1.50		0.90	1.35			
	Toilet-2								
	Long Wall	2	4.10		0.90	7.38			
	Short Wall	2	1.50		0.90	2.70			
	Parapet Wall								
		1	82.35		1.00	82.35			
	Staircase Side	1	1.80		1.75	3.15			
	Supporting Pillars	4	0.30		1.00	1.20			
		2	0.10		1.00	0.20			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
		6	0.37		1.00	2.22			
		1	0.24		1.00	0.24			
	Front and Rear Entrance	4	1.90		0.90	6.84			
	Supporting Pillars	4	0.30		3.00	3.60			
	Compound Wall								
		1	87.20		1.50	130.80			
	Supporting Pillars	20	0.30		1.50	9.00			
						278.66	Sqm		
				Upto 125%		30.56	Sqm	1046.37	31,979.69
				Above 125%		248.10	Sqm	1046.37	259601.81
	Approved Amount	1046.37							
32	Providing and laying water proofing treatment to the Roof with PU based single component elastomeric pure polyurethane based coating on New terrace/Chajjas/Sunken portion of WC:Bathroom, cold applied PU waterproofing membrane that is highly elastic with elongation greater than 400% and tensile strength greater than 2MPa as per ASTM D412. The waterproofing membrane to be applied in 2coats @ 1.6kg per m2 to achieve final DFT (dry film thickness) of 1mm including prime coat of epoxy primer @150 g per m2 and protection with 120gsm Geo-textile over the waterproofing membrane. The finished cost to include surface preparation, making coving at Junction, Bore Packing, treatment of construction joints completely as per specification & with a 10 years warranty on product & work from certified manufacturers as per the direction of the Engineer in charge.(V-II Page No.133, Item No.15.1 of PWD SR 2021-22)								
	Basic Rate	745.00							
	Area weihgtage 10%	74.50							
	Total	819.50							
	Vaidhika Sabha building								
	Slab								
		1	1.00	1.10		1.10			
		1	5.00	7.30		36.50			
		1	21.00	16.90		354.90			
	Deduction								
		-1	2.40	1.00		-2.40			
						390.10	Sqm		
				Upto 125%		354.81	Sqm	824.04	292381.16
				Above 125%		35.29	Sqm	824.04	29,078.46
	Approved Amount	824.04							
33	Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, usage charges complete as per specifications.(V-II Page No.99, Item No.12.11 of PWD SR 2021-22)								
	Vaidhika Sabha Building	Sqm							
	D	6	5.40		0.125	4.05			
	D1	9	5.10		0.100	4.59			
	Main Door	2	7.30		0.125	1.83			
						10.47	Sqm		
				Upto 125%		6.08	Sqm	99983.69	607400.92

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
				Above 125%		4.39	Sqm	99983.69	438928.40
	Approved Amount	99983.69							
34	Fixing of door frame in an existing opening including embedding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debris with lead upto 50 m. including cost of materials, labour charges, complete as per specifications (V-II Page No 105, Item No 12.51 of PWD								
	Vaidhika Sabha Building	Sqm							
	D	6				6.00			
	D1	9				9.00			
						15.00	Nos		
				Upto 125%		9.00	Nos	1642.56	14,783.02
				Above 125%		6.00	Nos	1642.56	9,855.35
	Approved Amount	1642.56							
35	Providing and fixing flush door shutter made out of solid core block board type, well seasoned , chemicaly treated hard wood battens and internal frame with minimum 45 mm wide wooden frame alround door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door useing liquid phenol formaldehyde resin as per IS specifications 2202 (part-I) 1991. from manufacturer complete as per spcification. 30 mm thick both side commercial (V-II Page No.105, Item No.12.51 of PWD SR 2021-22).								
	Vaidhika Sabha building	Sqm							
	Main Door	2	2.60		2.10	10.92			
	D	6	1.2		2.100	15.12			
	D1	1	0.9		1.200	1.08			
						27.12	Sqm	2917.89	79133.19
	Approved Amount	2917.89							
36	Providing & fixing of 2-track x 2-panel sliding windows made out of multi chambered UPVC(Matching to RAL-9016) sections and with minimum TiO2(Titanium Dioxide) at 6 PHR with TPE (Thermo Plastic Elastomer) and lead free, gaskets -grey color having isolated drainage and reinforced with Galvanized Iron profile through-out the window frame. The outer frame having an overall size of 44mm width x 40mmheight with reinforcement of 1mm thickness and Sash with overall size of 27mm X 53mm with UPVC honeycomb structure inside in lieu of GI reinforcement. Coextruded Glazing bead for fixing of glass shall be of size 9.5mm x 21.5mm. Windows shall be provided with 5mm plain float glass, standard hardware& single point locking system with Crescent Locks. Wall thickness of frame & sash shall be of 2 mm.Maximum possible size – 1219mm x 1219mm. (The cost is inclusive of all fixtures and separate charges for minor T&P's shall not be								
	Vaidhika Sabha building								
	W	8	1.5		1.2	14.40			
	W1	1	1.2		1.2	1.44			
	V	4	1.7		0.9	6.12			
						21.96	Sqm	4550.50	99928.98
	Approved Amount	4550.50							
37	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to steel windows by welding (V-II, Page No.85, Item No.11.34A of PWD SR 2021-22)								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Vaidhika Sabha Building								
	W	8	1.50		1.20	14.40			
	W1	1	1.20		1.20	1.44			
	V	6	0.60		0.60	2.16			
	Front and Rear Entrance								
	V	4	1.7		1.90	12.92			
						30.92			
	Total Qty in kgs (qty in Sqm *21 kg/sqm)					649.32			
						649.32	Sqm	144.90	94085.84
	Approved Amount	144.90							
38	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6 mm angle iron and 3 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using M.S. angels 40x40x6 mm for diagonal braces including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.(V-II, Page No.75, Item No.11.5.1 of PWD SR								
	Vaidhika Sabha building	Sqm							
	Front and Rear Entrance								
	D2	9	0.9		2.10	17.01			
						17.01	Sqm		
					Upto 125%	11.81	Sqm	4048.33	47,820.90
					Above 125%	5.20	Sqm	4048.33	21,041.20
	Approved Amount	4048.33							
39	Providing 15 mm cement plaster on the rough side of single or half brick wall of mix 1:4 (1 cement: 4 fine sand) including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.(V-II, Page No.41, Item No.8.2.1 of PWD SR 2021-22)								
	Vaidhika Sabha Building								
	Ceiling								
	Store Room	1	5.90		4.80	28.32			
	Ritual Room	3	5.90		6.15	108.86			
	Kitchen	1	4.00		4.00	16.00			
	Room	1	4.00		4.00	16.00			
	Room - 1	1	3.00		4.00	12.00			
	Passage	1	19.20		6.05	116.16			
	Toilet	6	1.50		1.95	17.55			
	Toilet Passage	2	0.90		4.00	7.20			
	Internal Walls								
	Store Room	2	5.90		2.90	34.22			
	Store Room	2	4.80		2.90	27.84			
	Ritual Room	6	5.90		2.90	102.66			
	Ritual Room	6	6.15		2.90	107.01			
	Kitchen	2	4.00		2.90	23.20			
	Kitchen	2	4.00		2.90	23.20			
	Room	2	4.00		2.90	23.20			
	Room	2	4.00		2.90	23.20			
	Room - 1	2	4.00		2.90	23.20			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Room - 1	2	3.00		2.90	17.40			
	Passage	2	19.20		2.90	111.36			
	Toilet	12	1.50		2.90	52.20			
	Toilet	12	1.95		2.90	67.86			
	Toilet Passage	4	4.00		2.90	46.40			
	Toilet Passage	4	0.90		2.90	10.44			
	Chejja								
	Store Room	1	5.90		1.00	5.90			
	Kitchen	1	7.70		1.00	7.70			
	Room	1	4.00		1.00	4.00			
	Room - 1	1	3.00		1.00	3.00			
	Beams								
		4	6.05		0.83	20.09			
	Window Sides								
	W	8	5.40		0.23	9.94			
	W1	1	4.80		0.23	1.10			
	V	6	2.40		0.23	3.31			
	Deduction								
	D	-12	1.2		2.1	-30.24			
	D1	-6	0.9		2.1	-11.34			
	D2	-12	0.9		2.1	-22.68			
	W	-8	1.5		1.2	-14.4			
	W1	-1	1.2		1.2	-1.44			
	V	-6	0.6		0.6	-2.16			
	Internal Walls								
	Front and Rear Entrance	4	1.90		0.90	6.84			
	Supporting Pillar								
		4.00	0.76		3.00	9.12			
						1004.21	Sqm		
					Upto 125%	964.63	Sqm	279.84	269943.72
					Above 125%	39.59	Sqm	279.84	11,078.43
	Approved Amount	279.84							
40	Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonary including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.(V-II, Page No.41, Item No.8.3.1 of PWD SR 2021-22)								
	Vaidhika Sabha Building								
	External								
	Store Room	2	5.03		3.00	30.18			
	Ritual Rooms	1	18.62		3.00	55.86			
	Kitchen, Room and Room 1	1	19.20		3.00	57.60			
	Front	1	4.46		3.00	13.38			
	Kitchen Rear	1	4.46		3.00	13.38			
	Ritual Room 3 Rear	1	6.61		3.00	19.83			
	SSM Portion								
		1	6.10		0.90	5.49			
		1	6.30		1.60	10.08			
		1	4.50		1.00	4.50			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Parapet	1	4.10		2.15	8.82			
	Supporting Pillars	4	0.83		1.00	3.32			
		2	0.43		1.00	0.86			
		6	0.97		1.00	5.82			
		1	0.71		1.00	0.71			
		1	2.45		1.00	2.45			
	Landing Portion	1	1.8		1.75	3.15			
	Extension								
		1	16.80		0.80	13.44			
		1	15.70		0.80	12.56			
	Staircase								
		2	1.20		2.90	6.96			
		2	0.50		0.50	0.50			
	0.5*4.6*2.4	2	5.52			11.04			
	Chejja External								
	W	7	1.80	0.75		9.45			
	V	3	0.90	0.75		2.03			
	Deduction								
	W	-8	1.5		1.2	-14.4			
	W1	-1	1.2		1.2	-1.44			
	V	-3	0.6		0.6	-1.08			
	External								
	Front and Rear Entrance	4	1.90		0.90	6.84			
	Compound Wall								
		1	87.20		3.23	281.66			
	Supporting Pillars	20	0.76		1.50	22.80			
	Entrance Gate								
	Pillars	2	1.10		1.50	3.30			
						589.08	Sqm	339.57	200034.04
	Approved Amount	339.57							
41	Providing and laying flooring and steps fine machine polished granite stone slabs 20 mm thick on cement mortar bed 1:6, 20 mm thick, and joints finished with cement mortar 1:3 over existing cement concrete bed including cost of materials, mortar, labour, curing complete as per specifications.(V-II, Page No.64, Item								
	Vaidhika Sabha building								
	Rooms								
	Store Room	1	5.90	4.80		28.32			
	Ritual Room	3	5.90	6.15		108.86			
	Kitchen	1	4.00	4.00		16.00			
	Room	1	4.00	4.00		16.00			
	Room - 1	1	3.00	4.00		12.00			
	Passage	1	19.20	6.05		116.16			
	At Door								
	Store Room	1	1.20	0.23		0.28			
	Ritual Room	3	1.20	0.23		0.83			
	Kitchen	1	1.20	0.23		0.28			
	Room	1	1.20	0.23		0.28			
	Room - 1	1	0.90	0.23		0.21			
	Skirting								
	Store Room	1	21.40		0.10	2.14			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Ritual Room	3	24.10		0.10	7.23			
	Kitchen	1	16.00		0.10	1.60			
	Room	1	16.00		0.10	1.60			
	Room - 1	1	14.00		0.10	1.40			
	Passage	1	50.50		0.10	5.05			
	Entrance Steps								
		1.00	6.00	0.90		5.40			
		2.00	6.00	0.15		1.80			
	Deduction								
	D	-12	1.2		0.10	-1.44			
	D1	-1.00	0.90		0.10	-0.09			
	Main Door	-2.00	1.50		0.10	-0.3			
						323.59	**Sqm**		
				Upto 125%		**285.11**	**Sqm**	**2655.75**	**757187.52**
				Above 125%		**38.48**	**Sqm**	**2655.75**	**102181.31**
	Approved Amount	**2655.75**							
42	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ m2 including pointing the joints with white cement and matching pigments etc., complete (V-II, Page No.60, Item No.9.11 of PWD SR 2021-22)								
		Sqm							
	Vaidhika Sadha Building Toilet Area								
	Flooring								
	Toilet	6	1.50	1.95		17.55			
	Toilet Passage	2	0.90	4.00		7.20			
						24.75	**Sqm**	**855.02**	**21161.75**
	Approved Amount	**855.02**							
43	Providing skirting, dadooing, rises of steps with white glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.(V-II, Page No.65, Item No.9.38 of PWD SR 2021-22)								
	Vaidhika Sadha Building Toilet Area								
	Dadooing								
	Toilet	6	3.45		2.10	43.47			
	Toilet Passage	2	4.90		2.10	20.58			
	Skirting								
	Toilet	6	6.90		0.10	4.14			
	Toilet Passage	2	9.80		0.10	1.96			
	Deduction								
	D1	-6	0.9		2.1	-11.34			
	V	-6	0.6		0.6	-2.16			
	D1	-12	0.9		0.1	-1.08			
						55.57	**Sqm**	**2171.27**	**120657.66**
	Approved Amount	**2171.27**							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
44	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade :Two coats on new work after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (V-II, Page No.48, Item								
	Ceiling								
	Store Room	1	5.90		4.80	28.32			
	Ritual Room	3	5.90		6.15	108.86			
	Kitchen	1	4.00		4.00	16.00			
	Room	1	4.00		4.00	16.00			
	Room - 1	1	3.00		4.00	12.00			
	Passage	1	19.20		6.05	116.16			
	Toilet	6	1.50		1.95	17.55			
	Toilet Passage	2	0.90		4.00	7.20			
	Internal Walls								
	Store Room	2	5.90		2.90	34.22			
	Store Room	2	4.80		2.90	27.84			
	Ritual Room	6	5.90		2.90	102.66			
	Ritual Room	6	6.15		2.90	107.01			
	Kitchen	2	4.00		2.90	23.20			
	Kitchen	2	4.00		2.90	23.20			
	Room	2	4.00		2.90	23.20			
	Room	2	4.00		2.90	23.20			
	Room - 1	2	4.00		2.90	23.20			
	Room - 1	2	3.00		2.90	17.40			
	Passage	2	19.20		2.90	111.36			
	Toilet	12	1.50		2.90	52.20			
	Toilet	12	1.95		2.90	67.86			
	Toilet Passage	4	4.00		2.90	46.40			
	Toilet Passage	4	0.90		2.90	10.44			
	Chejja								
	Store Room	1	5.90		1.00	5.90			
	Kitchen	1	7.70		1.00	7.70			
	Room	1	4.00		1.00	4.00			
	Room - 1	1	3.00		1.00	3.00			
	Beams								
		4	6.05		0.83	20.09			
	Window Sides								
	W	8	5.40		0.23	9.94			
	W1	1	4.80		0.23	1.10			
	V	6	2.40		0.23	3.31			
	Front and Rear Entrance	4	1.90		0.90	6.84			
	Deduction								
	D	-12	1.2		2.1	-30.24			
	D1	-6	0.9		2.1	-11.34			
	D2	-12	0.9		2.1	-22.68			
	W	-8	1.5		1.2	-14.4			
	W1	-1	1.2		1.2	-1.44			
	V	-6	0.6		0.6	-2.16			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
						995.09	Sqm		
				Upto 125%		943.83	Sqm	105.08	99,176.61
				Above 125%		51.27	Sqm	105.08	5,387.21
	Approved Amount	105.08							
45	Providing White washing with lime to give an even shade :New work (three coats) with lime of approved quality, including cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (V-II, Page No.44, Item No.8.21 of PWD SR 2021-22)								
	External								
	Store Room	2	5.03		3.00	30.18			
	Ritual Rooms	1	18.62		3.00	55.86			
	Kitchen, Room and Room 1	1	19.20		3.00	57.60			
	Front	1	4.46		3.00	13.38			
	Kitchen Rear	1	4.46		3.00	13.38			
	Ritual Room 3 Rear	1	6.61		3.00	19.83			
	SSM Portion								
		1	6.10		0.90	5.49			
		1	6.30		1.60	10.08			
		1	4.50		1.00	4.50			
	Parapet	1	4.10		2.15	8.82			
	Supporting Pillars	4	0.83		1.00	3.32			
		2	0.43		1.00	0.86			
		6	0.97		1.00	5.82			
		1	0.71		1.00	0.71			
		1	2.45		1.00	2.45			
	Landing Portion	1	1.8		1.75	3.15			
	Extension								
		1	16.80		0.80	13.44			
		1	15.70		0.80	12.56			
	Staircase								
		2	1.20		2.90	6.96			
		2	0.50		0.50	0.50			
	0.5*4.6*2.4	2	5.52			11.04			
	Chejja External								
	W	7	1.80	0.75		9.45			
	V	3	0.90	0.75		2.03			
	Front and Rear Entrance	4	1.90		0.90	6.84			
	Compound Wall								
		1	93.00		3.23	300.39			
	Supporting Pillars	16	0.76		1.50	17.67			
	Deduction								
	W	-8	1.5		1.2	-14.4			
	W1	-1	1.2		1.2	-1.44			
	V	-3	0.6		0.6	-1.08			
						599.38	Sqm	21.02	12596.50
	Approved Amount	21.02							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
46	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two coat applied @ 1.67 ltr/10 m² over and including priming coat of exterior primer applied @ 2.20 kg/10 m²) with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.(V-II, Page No.46, Item No.8.30 of PWD SR 2021-22)								
	Qty Same as External Plaster					599.38			
						599.38	Sqm	150.43	90164.45
	Approved Amount	150.43							
47	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :Two coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.(V-II, Page No.48, Item No.8.41 of PWD SR 2021-22)								
	External								
	W	8	1.5		1.2	14.40			
	W1	1	1.2		1.2	1.44			
	V	6	0.6		0.6	2.16			
						18.00	Sqm	143.79	2588.27
	Approved Amount	143.79							
48	Providing and fixing chromium plated brass handles of 100/125 mm with necessary screws etc. Complete(V-II Page No 107, Item No.12.62 of PWD SR 2021-								
	Valdhika Sabha building Toilet Area	14				14.00			
						14.00	Nos	193.57	2709.94
	Approved Amount	193.57							
49	Providing and fixing ISI marked M.S. pressed butt hinges bright finished with necessary screws etc.125x65x2.12mm(V-II Page No.107, Item No.12.68.1 of PWD SR 2021-22)								
	Valdhika Sabha building Toilet Area					0.00	Nos	42.03	0.00
	Approved Amount	42.03							
50	Providing and fixing bright finished brass tower bolts (barrel type) with necessary screws etc Complete 250x10mm (V-II Page No.109, Item No.12.76 of PWD SR 2021-22)								
	Valdhika Sabha building Toilet	8				8.00			
						8.00	Nos	372.76	2982.04
	Approved Amount	372.76							
51	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid (V-II Page No.123, Item								
	Valdhika Sabha building Toilet	6				6.00			
						6.00	Nos	5536.03	33216.17

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Approved Amount	**5536.03**							
52	Providing and fixing white vitreous china laboratory sink with C.I. brackets, C.P. brass chain with rubber plug, 40 mm C.P brass waste and 40mm C.P. brass trap with necessary C.P. brass unions complete, including painting of fittings and brackets, cutting and making good the wall wherever required : Size 600x450x200 mm (V-II Page No.126, Item No.14.11.2 of PWD SR 2021-22)								
	Vaidhika Sabha building Toilet	4				4.00			
						4.00	**Nos**	**5136.73**	**20546.90**
	Approved Amount	**5136.73**							
53	Providing and fixing white vitreous china flat back half stall urinal of size 580x380x350 mm with white PVC automatic flushing cistern, with fittings, standard size C.P. brass flush pipe, spreaders with unions and clamps (all in C.P. brass) with waste fitting as per IS : 2556, C.I. trap with outlet grating and other couplings in C.P. brass, including painting of fittings and cutting and making good the walls and floors wherever required : Single half stall urinal with 5 litre P.V.C. automatic flushing cistern (V-II Page No.124, Item No.14.5.1 of PWD SR								
	Vaidhika Sabha building Toilet	2				2.00			
						2.00	**Nos**	**7331.23**	**14662.45**
	Approved Amount	**7331.23**							
54	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in charge. Concealed work, including cutting chases and making good the walls etc. 20mm nominal dia pipes (V-								
	Vaidhika Sabha building Toilet	m	95.00			95.00			
						95.00	m		
					Upto 125%	**56.25**	m	**412.58**	**23,207.35**
					Above 125%	**38.75**	m	**412.58**	**15,987.29**
	Approved Amount	**412.58**							
55	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in charge. Concealed work, including cutting chases and making good the walls etc. 25mm nominal dia pipes (V-								
	Vaidhika Sabha building Toilet Area		60.00			60.00			
						60.00	**m**	**526.50**	**31590.20**
	Approved Amount	**526.50**							
56	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in charge. Concealed work, including cutting chases and making good the walls etc. 32mm nominal dia pipes (V-								
	Vaidhika Sabha building Toilet Area		30.00			30.00			
						30.00	**m**	**614.99**	**18449.74**
	Approved Amount	**614.99**							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
57	Supplying PVC ringtite pipes conforming to IS 4985:2000 with latest amendments and conveying to worksite, rolling and lowering into trenches, laying true to line and level and perfect linking at joints, testing and commissioning, including loading unloading at both destinations and cuts of pipes wherever necessary including jointing of PVC pipes and specials (excluding cost of specials) with jointing of approved type, with all labour with all lead & lift including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation etc complete and giving necessary hydraulic test to the required pressure as per ISS (Contractor will make his own arrangements for procuring water for testing) etc. for:PVC pipes 110mm dia., 6 kg/sqcm								
	Vaidhika Sabha building Toilet Area	1	45.00			45.00			
						45.00	M	396.18	17828.31
	Approved Amount	396.18							
58	Providing and fixing gun metal non- return valve of approved quality (screwed end)(V-II Page No.115, Item No.13.6.1.2 of PWD SR 2021-22)								
	Vaidhika Sabha building Toilet Area	6.00				6.00			
						6.00	Nos	611.67	3670.04
	Approved Amount	611.67							
59	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete(V-II Page No.115, Item No.13.5.2 of PWD SR 2021-22)								
	Vaidhika Sabha building Toilet Area	4.00				4.00			
						4.00	Each	398.20	1592.78
	Approved Amount	398.20							
60	Providing and fixing PTMT pillar cock of approved quality and colour15 mm nominal bore, 125 mm long foam flow, weighing not less than 120 gms(V-II Page No.118, Item No.13.20.2 of PWD SR 2021-22)								
	Vaidhika Sabha building Toilet Area	6				6.00			
						6.00	Each	243.34	1460.05
	Approved Amount	243.34							
61	Bottle trap 38 mm single piece moulded with height of 270 mm, effective length of tail pipe 260 mm from the centre of the waste coupling, 77 mm breadth with 25 mm minimum water seal, weighing not less than 263 gms (V-II Page No.129, Item No.14.37.2								
	Vaidhika Sabha building Toilet Area	6				6.00			
						6.00	Each	269.89	1619.33
	Approved Amount	269.89							
62	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 19/20mm dia 2mm thick conforming to IS 2509 with suitable size bends, metal/PVC junction boxes adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipes ends should be covred using PVC end enclosures. run with 18SWG GI fish wire wherever necessary.19/20mm dia 2mm thick (Page No.1, Item No.1.2.1 of PWD Electrical SR2022-								
	Vaidhika Sabha building Toilet Area	1	100.00			100.00			
						100.00	m	61.34	6133.82
	Approved Amount	61.34							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
63	Providing and fixing Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including cost of materials, labour, usage charges ofmachinery complete as per specifications and as per directions of the Engineer-in-Charge. (V-2 Page No.82, Item No.11.25.2 of PWD SR 2021-22) Issue Rate On 07-04-22								
	Vaidhika Sabha Building								
	Parapet Railing	1	6.00		1.00	6.00			
	Staircase	1	1.35		1.00	1.35			
		2	4.60		1.00	9.20			
	Main Gate								
		Kg	6.00		1.50	9.00	Sqm		
						25.55			
	Consider 55kg/Sqm					1405.25			
						1405.25	Kg		
				Upto 125%		577.50	Kg	147.11	84,956.74
				Above 125%		827.75	Kg	147.11	121771.32
	Approved Amount	147.11							
64	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 25mm dia 2mm thick conforming to IS 2509 with suitable size bends, metal/PVC junction boxes adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipes ends should be covred using PVC end enclosures. run with 18SWG GI fish wire wherever necessary.a)25mm dia 2 mm thick (Page No.1, Item No.1.2.2 of PWD Electrical SR 2021-22)								
	Hall	1	100.00			100.00			
						100.00	m	70.39	7038.82
	Approved Amount	70.39							
65	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 19/20mm dia 2mm metal/PVC junction boxes adhesive paste etc. By groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary 19/20mm dia 2mm thick(Page No.1, Item No.1.3.1 of PWD Electrical SR 2021-22)								
	Hall	1	100.00			100.00			
						100.00	m	75.42	7541.59
	Approved Amount	75.42							
66	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 25mm dia 2.mm metal/PVC junction boxes adhesive paste etc. By groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary.a)25mm dia 2 mm thick (Page No.1, Item No.1.3.2 of PWD Electrical SR 2021-22)								
	Hall	1	100.00			100.00			
						100.00	m	80.44	8044.36
	Approved Amount	80.44							
67	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 32mm dia 2.5mm metal/PVC junction boxes adhesive paste etc. By groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary.32mm dia 2.5 mm thick (Page No.1, Item No.1.3.3 of PWD Electrical SR 2021-22)								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Hall	2	50.00			100.00			
						100.00	m		
					Upto 125%	12.50	m	105.58	1,319.78
					Above 125%	87.50	m	105.58	9,238.44
	Approved Amount	105.58							
68	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multistrand Copper conductor single core cable in open or concealed system of wiring with specified IS-694:1990 & conforming to GTP of Group-A (Page No.3, Item No.2.3 of PWD Electrical SR 2021-22)								
	1.0 Sqm	2	100.00			200.00	m	18.10	3619.96
	1.5 Sqm	2	50.00			100.00	m	26.14	2614.42
	2.5 Sqm	2	85.00			170.00	m	40.22	6837.71
	4.0 Sqm	2	45.00			90.00	m	59.33	5339.44
	10.0 Sqm	2	20.00			40.00	m	157.87	6314.82
69	Point wiring using Copper wire without switch.Supplying and wiring adopting loop system in existing PVC Conduit/casing capping using 1100V Grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2x1.5 Sq.mm Cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose lenght in a wood/PVC round block, complete for each outlet.(5/2.3) Using class A materials (Page No.3, Item								
	Short point up to 3mtrs from tapping point to out let via switch (Page No 3, Item No.2.2.1 of PWD Electrical SR	1	25.00			25.00	Point	252.39	6309.79
	Medium point a above 3mtr up to 6mtr from tapping point to out let via switch (Page No.3, Item No.2.2.2 of PWD Electrical SR 2021-22)	1	5.00			5.00	Point	363.00	1815.01
	Long point a above 6mtr up to 10mtr from tapping point to out let via switch (Page No.3, Item No.2.2.3 of PWD Electrical SR 2021-22)	1	20.00			20.00	Point	545.01	10900.11
70	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve , indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required conforming to IEC60898.5-32Amps DP (Page No.13, Item No.5.17 of PWD Electrical SR 2021-22)								
	6-32Amps SP	12				12.00	Each	525.90	6310.80
	6-32 Amps DP	18				18.00	Each	1109.12	19964.09
	40 Amps TPN	8				8.00	Each	2406.27	19250.15
	50-63 Amps SP	8				8.00	Each	738.07	5904.56
71	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure,III-Single Door Group A12Way SP &N (Page No.13, Item								
	Hall	10				10.00			
						10.00	Each	1599.82	15998.22
	Approved Amount	1599.82							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
72	Supplying and fixing regular MCB distribution boards on wall/wood board/flush mounting using required clamps, bolts, nuts etc. with provision for fixing suitable type capacity MCB's single phase/3 phase/single door with power coated painting etc., complete: Double door 6 way TP &N , Group (A) (Page No.13, Item No.5.18.12 of PWD Electrical SR								
	Hall	5				5.00			
						5.00	Each	3755.71	18778.55
	Approved Amount	3755.71							
73	Supplying and fixing 32Amps security and energy saving DP switch with key tag suitable to operate on 230 Volts, 50Hz AC supply & completely wired on existing box. (Page No.6, Item No.3.7 of PWD Electrical SR 2021-22)								
	Hall	5				5.00			
						5.00	Each	751.14	3755.71
	Approved Amount	751.14							
74	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall 1-3 Way (Page No.5, Item No.3.4.1 of PWD Electrical SR								
	Hall	25				25.00			
						25.00	Each	123.68	3092.05
	Approved Amount	123.68							
75	Supplying and fixing of 20/40 Watts heavy duty open construction Ferromagnetic copper ballast for fluorescent tubes : Supplying and fixing of 20/40 Watts heavy duty open construction Ferromagnetic copper ballast for fluorescent tubes, Class H insulated copper wire, Vacuum impregnated high quality with Low loss silicon steel lamination operated on 240V,50Hz supply with IEC 60920 (Safety) & IEC 60921(Performance). Operating voltage range from 180V to 265V, 50Hz AC power Supply. (Page No.41, Item No.12.23 of PWD								
	Hall	20				20.00			
						20.00	Each	301.66	6033.27
	Approved Amount	301.66							
76	Supply and fixing metal fan box with round hook (Page No.2, Item No.1.12 of PWD Electrical SR 2021-22)								
	Hall	12				12.00			
						12.00	Nos	163.90	1966.85
	Approved Amount	163.90							
77	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293 (Page No.5, Item No.3.6 of PWD Electrical SR 2021								
	6Amps SP Switch	50				50.00	Each	88.49	4424.40
	6Amps 3way 5 pin socket	20				20.00	Each	162.90	3257.97
	16Amps SP Switch	10				10.00	Each	250.38	2503.81
	32Amps Flush/projected types DP switch	10				10.00	Each	377.08	3770.79
78	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall (Page No.5, Item No.3.4 of PWD Electrical SR 2021-22)								
	1-3Way	20				20.00	Each	123.68	2473.64
	4-5Way	20				20.00	Each	138.77	2775.30
	6Way	20				20.00	Each	213.18	4263.51
	8Way	24				24.00	Each	251.39	6033.27
	10-12Way	16				16.00	Each	326.80	5228.83

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	16Way	4				4.00	Each	355.96	1423.85
79	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. (Page No.5, Item No.3.5 of PWD Electrical SR								
	1 to 3 Module	20				20.00	Each	152.84	3056.86
	4Moudule	20				20.00	Each	175.97	3519.41
	6Moudule	20				20.00	Each	245.35	4907.06
	8Moudule	24				24.00	Each	303.67	7288.19
	10Moudule	16				16.00	Each	365.01	5840.21
	12Moudule	4				4.00	Each	405.23	1620.94
80	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies for operation on 230 Volts, 50 Cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system.(84/9.3)56" Sweep (1400mm) Regular model (Page No.22, Item No.6.3.2 of PWD Electrical SR 2021-22)								
	Hall	0				0.00			
						0.00	Each	2182.03	0.00
	Approved Amount	2182.03							
81	Supplying and fixing of Electronic Ballast suitable for T8 Lamp with housing made of Pre-coated steel/PC, Operating voltage range from 180V to 265V, 50Hz AC power Supply flicker free warm start with over voltage protection, Inrush current protection, De-activated lamp protection & End of Lamp life protection with PF> 0.95 & TC(deg C) > 65 degC. Operating voltage range from 180V to 265V, 50Hz AC power Supply.(Page No.40,								
	Hall	0				0.00			
						0.00	Each	729.02	0.00
	Approved Amount	729.02							
82	Fixing all types and all capacities of fluorescent / false ceiling / spot light / CFL / LED fittings indoor on the wall / ceiling / rafters / girders using 23/0.0076" twin twisted PVC insulated wires, required Nos of round blocks and clamps. 14.7.1 On wall / ceiling / Rafter / Girders (Page No.45, Item No.13.7.1 of PWD Electrical SR 2021-22)								
	Hall	0				0.00			
						0.00	Each	119.66	0.00
	Approved Amount	119.66							
83	**Geophysical investigation** at site for sinking borewells for supplying drinking water to the habitation either through the Hand Pump MWS or P.W.S.S. by vertical electrical sounding by adopting Veruner orSchlumbergers's method, including reconnaissance survey of geological formation. Geophysical investigation of existing ground water in the vicinity, its quality, quantity and acceptability of the users, indicating the location of the site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 metre in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instruments and accessories to work site, engaging technical personal and labour required etc. NOTE: 1) Additional rate on item 1&2 is allowed for drilling in over burden and fixing Casing pipes beyond 20 M (for fixing Casing pipes only) a) Above 20 M and upto 30 M - 15%, b) Above 30 M - 30% (Measurement of overburden is restricted to the depth of casing pipe fixed excluding initial depth of 20M and projection above ground level). 2) A sum of Rs. 100/- is to be deducted for Dry Borewell towards yield test. (P.151, I.No-4 Code No-0040A) BWSSB.SR 2021-22								
		1				1.00	Nos	5686.46	5686.46
	Approved Amount	5686.46							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
84	Sinking of Borewell of 165mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burdern upto 20 m. Fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicle, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (Excluding cost of casing pipes, collars, cap etc., complete)(P.151, I.No-1) BWSSB.SR 2021-22								
	0 to 50 m (Code No-0010A)	1	50.00			50.00	m	320.77	16038.44
	Approved Amount	320.77							
	50 to 100 m (Code No-00108)	1	50.00			50.00	m	402.62	20131.01
	Approved Amount	402.62							
	100 to 150 m (Code No-0010C)	1	50.00			50.00	m	428.06	21403.03
	Approved Amount	428.06							
	150 to 200 m (Code No-0010D)	1	50.00			50.00	m	496.64	24831.93
	Approved Amount	496.64							
	200 to 250 m (Code No-0010E)	1	50.00			50.00	m	582.91	29145.72
	Approved Amount	582.91							
	250 to 300 m (Code No-0010F)	1	39.00			39.00	m	617.20	24070.94
	Approved Amount	617.20							
	300 to 350 m (Code No-0010G)	1	0.00			0.00	m	685.78	0.00
	Approved Amount	685.78							
85	Supply of ISI mark 175mm nominal bore,plain and steel casing pipe grade of steel Fe 410 of wall thickness conforming to IS 4270-2001 and latest ammendments, electrical resistance welded steel tubes, material and conforming to IS 1387-1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5-7m both ends.threaded conforming to IS 554-1985 one end fixed with socket conforming to IS 4270-2001 and the other end with screwed pipes all shall be responsibaly free from defects. The tubes shall be responsible straight end should be with ISI marking weighing 25.10kg/m.prices include Collar-Medium duty (P 154, I.No 32, 0160A) BWSSB.SR 2021-22								
		1	70.00			70.00			
						70.00	Rmtr	2138.09	149666.32
	Approved Amount	2138.09							
86	Supply and delivery of galvanized mild steel tubes of 6mtr standard length heavy duty (C Class) as per IS 1239 (Part-I) 1990 with latest amendments with ISI Mark (one end fitted with Heavy Duty collar and other end fitted with protective cover) 50 mm (P. No.162, I. No. 33.1 BWSSB SR 2021-22)								
		0				0.00			
						0.00	Each	3373.60	0.00
	Approved Amount	3373.60							
87	PVC pipe - OD 250mm and 6 Kg/sqcm P.No-34, Sl.No.1175,BWSSB.SR 2021-22								
		1	6.00			6.00			
						6.00	Rmtr	1216.71	7300.26
	Approved Amount	1216.71							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
88	Supplying and drawing 3 core flat PVC sheathed **submersible pump cable** manufactured with electrolytic grade copper withflexible copper with low resistance conductor confirming to13:8130-1984 and virgin grade PVC insulation and powdercoating extruded PVC sheathed suitable for working voltageupto 1100 V as per IS-694:2010. 3C x 6 mm2 P. No. 4/ I No. 2.6.4 KPWD Electrical SR 2021-22								
		1	460.00			460.00			
						460.00	**Mtr**	**243.34**	**111937.27**
	Approved Amount	**243.34**							
89	Providing,supplying to work site, Submersible Pump Set of 150mm dia suitable for bore well and confirming to IS 8034-2000,3Phase, SS Bowl & Impeller with Low volt Motor as per specifications,as per necessary ammendments and instructions of engineer incharge of work. 15.00 HP - 120 LPM @ 266 m = 23 STG Outlet Dia - 2.00"(P. No.161, I. No. 18.6, BWSSB SR 2021-22)								
		1				1.00			
						1.00	**Nos**	**76606.27**	**76606.27**
	Approved Amount	**76606.27**							
90	Earthing: Supplying and fixing and wiring earth electrode for grounding circuits IC cutouts and other equipments on the meter board in the pit. The pits should be filled up with equal proportion of salt and charcoal 150mm around the pipe to complete depth. The connection from the pipe to the conduits etc. is to established through GI wire of sizes as per clause 7.3.3 of IS 732 using 12mm bolts, nuts, washers and check nuts, the pipe shall have 16 through holes of 12mm dia. (P. No.164, I. No. 45, BWSSB SR 2021-22)								
		1				1.00			
						1.00	**Job**	**4147.87**	**4147.87**
	Approved Amount	**4147.87**							
91	Supply and fixing polished wood board made of not lessthan 15mm thick plank on both sides of not more than 2pieces and fixing the same to the wall using tapered invertedwooden plugs screws. 20" x 20" x 2.5" (P No. 10 No.5.6.6,Part-I Electrical SR 2021-22)								
		1				1.00			
						1.00	**Each**	**316.75**	**316.75**
	Approved Amount	**316.75**							
92	Supplying & fixing of Porcelain fuse channel with cut out onexisting wooden/panel using necessary nuts, bolts andwashers 63 A (P No. 10 No.5 6.6,Part-I Electrical SR 2021-22)								
		1				1.00			
						1.00	**Each**	**374.06**	**374.06**
	Approved Amount	**374.06**							
93	Supplying & fixing miniature circuit breakers on existingMCB distribution boards using necessary fixing materialsand 'C' Type curve, indicator ON/OFF, energy cross-3 withShort circuit breaking capacity of 10K and complete wiring asrequired confirming to IEC 60898. 50-63 A TPN (P No. 13 I.No.5.17.9,Part-I Electrical SR 2021-22)								
		1				1.00			
						1.00	**Each**	**2412.30**	**2412.30**
	Approved Amount	**2412.30**							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
94	**Earth work excavation by manual means** for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such similar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenances required to complete the work.Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 14 m3) (V-I.No 1.4,Page								
	Pipeline	1	40.00	0.45	0.60	10.80			
						10.80	**Cum**	**205.73**	**2221.93**
	Approved Amount	**205.73**							
95	Supplying and filling in plinth with sand under floors, foundation of Bridges including watering, ramming, consolidating and dressing complete. (P.No-7,I No-1.11,V-I of PWD SR 2021-22)								
		1	40.00	0.30	0.30	3.60			
						3.60	**Cum**	**2407.98**	**8668.73**
	Approved Amount	**2407.98**							
96	Supplying PVC ringtite pipes conforming to IS 4985:2000 with latest amendments and conveying to worksite, rolling and lowering into trenches, laying true to line and level and perfect linking at joints, testing and commissioning, including loading unloading at both destinations and cuts of pipes wherever necessary including jointing of PVC pipes and specials (excluding cost of specials) with jointing of approved type, with all labour with all lead & lift including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation etc. complete and giving necessary hydraulic test to the required pressure as per ISS (Contractor will make his own arrangements for procuring water for testing) etc.63mm outer dia, 6kg/sqcm & class 3 for (P. No.134 I No 1.4 BWSSB SR 2021-22)								
		1	40.00			40.00			
						40.00	**Mtr**	**169.30**	**6772.00**
	Approved Amount	**169.30**							
97	**Refilling available earth** around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. including cost of all labour complete as per specifications P. No. 7, I No. 1.10,V-I PWD SR 2021-22								
		1	40.00	0.45	0.60	10.80			
						10.80	**Cum**	**135.02**	**1458.22**
	Approved Amount	**135.02**							
98	Supplying fully automatic star-delta starter unit push buttontype with suitable wires, 3 contactors, one adjustablethermal timer mounted on a common base plate held in steel enclosure for use on 400/440 V 3 phase and wired after fixingto the existing wooden board for motor. Above 12.5 HP upto 25 HP (P No. 10 I.No.5.2.2,Part-I Electrical SR 2021-22)								
		1				1.00			
						1.00	**Nos**	**8687.20**	**8687.20**
	Approved Amount	**8687.20**							
	EIRL								
E1	Fabricating supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clA with necessary cable entry pipe with gland and box should be finished with 7tanks treatment with powder coated paint and finally finished with approved colour etc., complete and as per the directions of the Engineer-in-charge of the work(I.No-5.42.2,Page No-15 BWSSB VOL-5 SR2021-22								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Basic rate	0.38							
	Above 0.55%	0.0021							
	Total	0.38							
		1	1100.00	20.00		22000.00			
						22000.00	Sq.cm	0.38	8405.98
E2	Labour charges for erection of outdoor type panel board and meter boardunits with all necessary materials and labour, tools and equipments including providing cement concrete foundation bed etc., complete as per specification, with testing of as per instructions and as per the directions of the Engineer-in-charge of the work(I.No-40,Page No-163 BWSSB VOL-5 SR2021-22								
	Basic rate	1350.00							
	Area Weightage 10%	135							
	Sub Total	1485.00							
	Above 0.55%	8.1675							
	Total	1493.17							
		1				1.00			
						1.00	Job	1493.17	1493.17
E3	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete cutting road surfaces and as per the directions of the Engineer-in-charge of the work(I.No-6.6 3,Page No-41 KPWD Electrical SR 19-20]								
	Basic rate	405.00							
	Above 0.55%	2.2275							
	Total	407.23							
		1	25.00			25.00			
						25.00	Mtr	407.23	10180.69
E4	Earthing Supplying and fixing and wiring earth electrode for grounding circuits IC cutouts and other equipments on the meter board in the pit. The pits should be filled up with equal proportion of salt and charcoal 150mm around the pipe to complete depth. The connection from the pipe to the conduits etc. is to established through GI wire of sizes as per clause 7.3.3 of IS 732 using 12mm bolts, nuts, washers and check nuts, the pipe shall have 16 through holes of 12mm dia and as per the directions of the Engineer-in-charge of the work(I.No45,Page No-164 BWSSB VOL-5 SR2021-22								
	Basic rate	3750.00							
	Area Weightage 10%	375							
	Sub Total	4125.00							
	Above 0.55%	22.6875							
	Total	4147.69							
		1				1.00			
						1.00	Job	4147.69	4147.69
E5	Supply and delivery at site of brand new best make gate valve as per IS 778/1984 with ISI Mark and as per its latest amendments Size 50 mm and as per the directions of the Engineer-in-charge of the work (I.No-27.1,Page No-162 BWSSB VOL-5 SR2021-22								
	Basic rate	1250.00							
	Area Weightage 10%	125							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Sub Total	1375.00							
	Above 0.55%	7.5625							
	Total	1382.56							
		1				1.00			
						1.00	Each	1382.56	1382.56
E6	Supply and delivery at site of brand new best make non-return valve as per IS 778/1984 with ISI Mark and as per its latest amendments Size 50 mm and as per the directions of the Engineer-in-charge of the work!.No-28.10,Page No-162 BWSSB VOL-5 SR2021-22								
	Basic rate	1275.00							
	Area Weightage 10%	127.5							
	Sub Total	1402.50							
	Above 0.55%	7.7138							
	Total	1410.21							
		1				1.00			
						1.00	Each	1410.21	1410.21
E7	Supplying, laying and jointing HDPE pipes of specified grade andconforming to IS 4984-2016 with latest ammendments and conveying to work site including loading and unloading at both destinations and rolling and lowering into trenches, laying true to line and jointing of pipes and specials with electrofusion welding, giving hydraulic test as per relevant ISS with all lead and lifts including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth availablefrom the excation, testing and commissioning. The rate is exclusive of required specials and fittings wherever necessary like saddle Tee, stub ends, flanged sets, bedns, reducers etc. complete (Contractor will make his own arrangements for procuring water for testing) etc. Note: Upto 110mm dia Coil shall be used.For Grade PE80 PN16.0 63 mm Dia(I.No-5.1,Page No-123 SOR CODE-K050A BWSSB VOL-5 SR2021-22								
	Basic rate	239.00							
	Area Weightage 10%	23.9							
	Sub Total	262.90							
	Above 0.55%	1.4460							
	Total	264.35							
		1	228.00			228.00			
						228.00	Mtr	264.35	60270.88
								Total Construction Cost	177958406.67
								18% GST for Construction Cost	32032513.20
								BESCOM Deposite Charges	11,000.00
								Sub Total	210001919.88
								Utility Shifting,Miscellaneous and Rounding off	35,818.52
								GRAND TOTAL	210037738.40

Technical Sanction
Accorded For ... 2021-22
Head of A/C ...
CER NO : ... Dt: ...

Assistant Engineer
Ward No-03 And 04
BBMP Bangalore

Executive Engineer,
Yelahanka Division
BBMP Bangalore